CAPITAL IMPROVEMENT PLAN REPORT DRAFT 1 2024-2028



October 19, 2022

Board Members, GLWA Team Members, Member Partners, and Service Area Communities,

The Great Lakes Water Authority (GLWA) Capital Improvement Planning Delivery Team presents you with draft 1 of the FY 24-28 Capital Improvement Plan (CIP). The CIP is a forward-looking document that outlines GLWA's water and wastewater infrastructure improvement strategy on a short- and long-term basis.

This year was exceptionally difficult to achieve CIP alignment with the financial plan due to inflationary pressures. Some difficult decisions were made to make sure that the FY 24-28 aligns with financial plan. This year's plan includes 168 projects for a total investment of approximately \$1.76 billion in the region's water and wastewater infrastructure over the next 5-year plan. As illustrated and proposed in the 5-year plan, the projects aim to improve the system's reliability, redundancy, and operational efficiency as well as protect health and safety.

The tremendous effort associated with the preparation of this plan would not have been possible without support from the GLWA's leadership, as well as the collaboration from the CIP delivery team members. The team worked tirelessly to shape this plan as we strive to continuously improve the content. Throughout the FY 24-28 CIP process, the CIP delivery team engaged Member Partners through improved project scoring. Thank you for your support of the GLWA CIP development. If you have any questions or need additional information, please do not hesitate to contact me.

Thank You,

Dima S. El-Gamal, PhD, PE, LEED AP Capital Improvement Planning Director

Great Lakes Water Authority • 9300 W Jefferson

- Ave, Suite 409 Detroit, MI 48209
- **C:** 313-400-3751
- D: 313-297-8819
- **E:** dima.elgamal@glwater.org

ACKNOWLEDGMENTS

[Acknowledgment page (cover photo contest winners) coming in future draft]

[Acknowledgment page (cover photo contest winners) coming in future draft]




TABLE OF CONTENTS

INTRODUCTION $\mathbf{01}$

1.1	Executive Summary	10
1.2	Primary Goals of the CIP	16
1.3	Team Members & Partners	16
1.4	CIP Strategy	17
1.5	CIP Optimization	17

CIP SUMMARY 02

2.1	CIP 5-Year Summary Tables	22
2.2	Project Status	28
2.3	Linear Assets	32
2.4	Projects by Jurisdiction	34
2.5	Specialty Projects	40
2.6	Project by Type	45
2.7	Project Scoring	51

CIP PROJECTS BY 03 **CATEGORY**

3.1	Largest CIP Projects	70
3.2	Largest Dollar Projects (<\$30M)	72
3.3	Largest 2023 Projected Spend (<\$5M)	76
3.4	Water Projects by Status	78
3.5	Wastewater Projects by Status	92
3.6	Centralized Services Projects	108
3.7	Ten-Year Water Outlook	110
3.8	Ten-Year Wastewater Outlook	120

GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1 6

04 | FINANCE

To be included in Draft 2

05 | WATER PROJECTS

5.1	Water Master Schedules	136
5.2	Water Projects One-Pagers	138

06 WASTEWATER PROJECTS

6.1	Wastewater Master Schedules	259
6.2	Wastewater Projects One-Pagers	261

CENTRALIZED SERVICES 07

6.1 Centralized Services One-Pagers 373

08 APPENDICES

Α	Water Business Case Evaluation
В	Wastewater Business Case Evaluation
С	Centralized Services Business Case Evaluations
D	System Background Information
E	Scoring Equation Tech Memo
F	Additional Reference Material: How to Navigate the CIP

GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

Placeholder for Image

01 INTRODUCTION





INTRODUCTION **1.1. EXECUTIVE SUMMARY**

We are pleased to submit the Great Lakes Water Authority (GLWA) Capital Improvement Plan (CIP) for fiscal years 2024-2028.

This document serves as a guide for the effective and efficient provision of capital assets and infrastructure, outlining timing, and financing for the five-year plan.

GLWA operates and maintains the largest water system in the United States in production and population served, and one of the largest wastewater treatment plants in capacity. To collaboratively ensure a One Water system approach to our regional water and wastewater systems, GLWA has a dedicated Member Outreach Program that collaborates with its Member Partners. Work groups are used to involve members in technical service and financial discussions that support decisionmaking at GLWA.

Four committees have been established by GLWA's six-member Board of Directors to provide oversight and policy guidance:

- Audit Committee
- **Capital Planning Committee**
- Legal Committee
- **Operations and Resources Committee**

GLWA's commitment to improved performance in the water and wastewater systems, environmental compliance, and Member Partner satisfaction aligns with the organization's goals to contribute to the economic success and the health and safety of the region it serves.



NOTE: *5 NEW PROJECT FROM PROGRAM

** IN ADDITION TO THE 168 PROJECTS, THERE ARE: +2 RECLASSIFIED PROJECTS +1 CANCELED PROJECTS

CIP AT A GLANCE

GLWA's CIP supports the continuation of major capital asset investments in programs and projects that will upgrade the Authority's aging water and wastewater system infrastructure, as well as the overarching centralized service infrastructure that supports both systems. The

CIP is a forward-thinking five-year plan which identifies capital projects and programs and their respective financing options. Annually, this plan is updated to reflect changing system needs, priorities, and funding opportunities.

WATER

Category	Amount	
5-Year Total	\$980,65	9
5-Year Average	\$196,13	2
10-Year Total	\$1,911,06	51
10-Year Average *Financial figures are in thou	\$191,10 sands of dollars (\$1.00 0	

are in thousands of doi

WASTEWATER

Category	Amount
5-Year Total	\$788,604
5-Year Average	\$157,721
10-Year Total	\$1,556,113
10-Year Average	\$155,611
*Financial finning and in t	the week and a field lieve (f.1 000)

*Financial figures are in thousands of dollars (\$1,000's)


PLAN SPENDING SUMMARY

5-Year Total \$1.77 Billion

10-Year Total \$3.46 Billion


5-Year Annual Average \$353 Million 10-Year Annual Average \$346 Million

Ongoing efforts to stabilize rates and plan realistically for what can be achieved led to the current capital improvement spending plan.



5-YEAR OUTLOOK


FY 24-28 CIP SCHEDULE



FY 22 KEY PERFORMANCE INDICATORS (KPIS)

ENTERPRISE RESILIENCY FY 2022 TOTAL WATER CIP SPEND

CUMULATIVE WATER CIP ACTIVITY FY 2022 THROUGH JUNE 30, 2022 (UNAUDITED, PRE-CLOSE)



GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

CURRENT STATUS: The water system incurred \$159 million of CIP costs through June 2022. This is 89% of the FY 2022 monthly prorated Approved CIP and 119% of the Adopted **Capital Spend Ratio** amount.

CURRENT STATUS: The sewer system incurred \$71 million of CIP costs through June 2022. This is 67% of the FY 2022 monthly Prorated Approved CIP and 89% of the Adopted **Capital Spend Ratio** amount.

WATER CIP COMPARISON

Financial figures are in thousands of dollars (\$1,000's)

CIP Document		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	5 - Year Total
Approved Water CIP FY 2023-2027	\$194,376	\$225,436	\$221,616	\$174,681	\$149,539	\$218,354	\$965,648
Water CIP FY 2024-2028		\$252,973	\$212,568	\$174,484	\$179,831	\$160,802	\$980,659
Difference		\$28	(\$9)	(\$0.2)	\$30	(\$58)	\$15
Difference %		12%	-4%	0%	20%	-26%	2%

WASTEWATER CIP COMPARISON

Financial figures are in thousands of dollars (\$1,000's)

CIP Document	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	5 - Year Total
Approved Wastewater CIP FY 2023-2027	\$125,932	\$162,313	\$184,523	\$157,689	\$131,307	\$171,068	\$761,764
Wastewater CIP FY 2024-2028		\$188,024	\$187,812	\$165,085	\$134,658	\$113,026	\$788,604
Difference		\$26	\$3	\$7	\$3	(\$58)	\$27
Difference %		16%	2%	5%	3%	-34%	4%

INTRODUCTION 1.1 EXECUTIVE SUMMARY

1.2. PRIMARY GOALS OF THE CIP

The primary goals of the GLWA's CIP are the following:


- Provide a condensed volume of projects in a central location.
- Demonstrate alignment with the GLWA financial plan.
- Share the GLWA integrated master schedule.
- Provide transparency to the organizational goals.
- Meet regulatory and operational needs.
- Provide an opportunity to Member Partners & Communities to contribute to the plan.
- Address projects that promote improved redundancy, system resiliency, and health and safety.

This CIP should be considered a forward looking planning document; it is a dynamic and evolving plan that requires continual review and improvement. Short-term project cost estimates are more defined than longterm project cost estimates because shortterm anticipated projects are typically better characterized by studies or scoped by design.

The project descriptions and summaries incorporated in this report represent brief synopses of the entire project scope; these descriptions are generally more defined for ongoing active projects than for newly planned projects, where specific project activities may have yet to be determined. Based upon the execution of programs and projects identified in the CIP, it is anticipated that existing levels of service currently provided will be met or exceeded. Copies of this CIP and past CIPs are available on GLWA's website at https://www.glwater.org/cip/.

1.3. TEAM MEMBERS & PARTNERS

Our members include the GLWA CIP Delivery Team (as depicted in Figure 1: Team Members & Partners), board members, water and wastewater partners, associated stakeholders, elected officials, consultants, and regulatory agencies. GLWA has a dedicated Member Outreach Program that collaborates with its members on water and wastewater activities.



The Capital Improvement Planning Group at GLWA works to develop and support the execution of the plan. The team members are listed below, along with their contact information:

- Dima El-Gamal, PhD, PE, LEED AP., dima. elgamal@glwater.org;
- Ian Thompson, PE, <u>ian.thompson@</u> glwater.org;
- Melissa Merideth-Phelan, <u>melissa.</u> phelan@glwater.org;
- Tiffany Oliver, tiffany.oliver@glwater.org;

1.4. CIP STRATEGY

GLWA's CIP lays out the organization's intentions for capital asset investment for the next five years to enhance and maintain system-wide assets. Updated annually, the plan reflects the organization's changing system needs, priorities, and financing opportunities over time. Projects are included in the CIP as recommended by the Water and Wastewater Master Plans, condition and needs assessments, regulatory requirements, and operational needs. The Comprehensive Water Master Plan and the Comprehensive Regional Wastewater Master Plan are long-term strategic planning tools that provide regional collaboration and planning to balance capital expenditures while implementing best practices in the treatment and transmission/conveyance of water and wastewater. Projects are vetted and prioritized to optimize capital investments. Water and Wastewater CIP Projects are developed utilizing Business Case Evaluations (BCE's), which are included in Appendices A, B, and C of this plan for Water, Wastewater, and Field Services, respectively.

The goals of the Authority's capital financing strategy are to:

- Recover the capital investment costs over the useful lives of the capital assets.
- Balance the needs of the water and sewage system with revenue requirements.
- Protect and enhance the Authority's financial position.

Maintain affordable charges by investing wisely in system renewal and revitalization.

Recognizing the difference in scope between the CIP and the tactical financial plan, GLWA implemented a "Capital Spend Rate Assumption Policy" adopted in 2018 by the Board of Directors. This policy provides an analytical approach to bridge the total dollar amount of projects in the CIP with what can realistically be spent due to limitations beyond GLWA's control. This rate is assessed annually and presented to the Board of Directors.

1.5. CIP OPTIMIZATION

As stated earlier, the CIP should be considered a forward-looking planning document. It is a dynamic and evolving plan that requires continual review, optimization, and improvement. To continuously improve the CIP process and reporting, the CIP group has made the following improvements:

CIP REPORT

The most visible change to the CIP process is the document itself. Continuing improvements from FY 2023 – 2027 CIP report, the outline of the content has been reordered and streamlined to provide a clearer sequencing.

In addition, a new section, Projects by Type, has been added to Chapter 2. The tables reflect CIP projects further broken down between Water – Treatment, Transmission, and Pump Station and Wastewater – Treatment, Conveyance, CSO, and Pump Station.

SCORING

The scoring this year followed the same methodology introduced in the FY23-27 CIP. This methodology was applied to improve and optimize the scoring and prioritization of projects by refining the alignment of the resulting project scores with GLWA's overall priorities and values. Below are a few additional actions implemented to streamline scoring revisions that were implemented:

- Projects that were reclassified maintain their highest score.
- Projects were not scored if they are under construction.
- Projects in the closeout stage were not scored.
- Projects under programs were scored, but programs were not scored.

The CIP processes will continue to improve and evolve to provide the various stakeholders with improved projections and reporting.

MILESTONES

The following schedule provides details related to the FY 24-28 CIP upcoming milestones:

- October 19, 2022 November 18, 2022: Public Comment Period
- December 13, 2021: Capital Planning Committee (CPC)
- Review of Preliminary Draft 2 January 2023: Present FY 24-28 CIP to GLWA Board
- January 2023: Capital Planning Committee (CPC)- Review of Final FY 24-28 CIP and recommendation to the GLWA Board
- February 2023: Board consideration and action on the FY 24-28 CIP.
- July 1, 2023: Effective date of FY 2024-2028



Placeholder for Image

02 **CIP SUMMARY**



CIP SUMMARY 2.1. CIP 5-YEAR SUMMARY TABLES

The Great Lakes Water Authority 2024-2028 CIP overall summary tables can be seen below. Please note that the Centralized Services CIP Categories table's projected project budgets and project categories are also included in the water CIP Categories and wastewater CIP Categories tables.

WATER

Financial figures are in thousands of dollars (\$1,000's)

Category		y Lifetime Actual er Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 CIP Total	FY 2029 & Beyond	Project Total
Treatment Plants and Facilities											
Lake Huron	111x	\$18,802	\$16,295	\$20,800	\$30,808	\$27,912	\$45,838	\$29,500	\$154,859	\$148,571	\$338,527
Northeast	112x	\$870	\$3,002	\$5,780	\$7,802	\$16,699	\$14,641	\$10,455	\$55,377	\$133,087	\$192,336
Southwest	113x	\$2,483	\$6,567	\$1,606	\$0	\$0	\$0	\$0	\$1,606	\$192,926	\$203,581
Springwells	114x	\$63,861	\$13,385	\$26,959	\$35,814	\$32,822	\$36,136	\$28,665	\$160,396	\$366,534	\$604,176
Water Works Park	115x	\$12,802	\$15,109	\$15,013	\$14,254	\$9,859	\$6,752	\$4,770	\$50,649	\$135,283	\$213,843
General Purpose	116x	\$56,113	\$16,991	\$18,084	\$11,885	\$0	\$0	\$0	\$29,969	\$0	\$103,073
Treatment Plants and Facilities Total		\$154,931	\$71,349	\$88,242	\$100,563	\$87,292	\$103,367	\$73,390	\$452,856	\$976,401	\$1,655,536
Field Services											
Transmission System	122x	\$152,629	\$138,311	\$132,846	\$93,288	\$60,486	\$37,861	\$38,589	\$363,070	\$348,888	\$1,002,898
Field Services Total		\$152,629	\$138,311	\$132,846	\$93,288	\$60,486	\$37,861	\$38,589	\$363,070	\$348,888	\$1,002,898
Systems Control Center											
Pump Station/Reservoir	132x	\$31,385	\$16,373	\$7,689	\$497	\$8,655	\$19,202	\$21,247	\$57,290	\$404,148	\$509,197
Systems Control Center total		\$31,385	\$16,373	\$7,689	\$497	\$8,655	\$19,202	\$21,247	\$57,290	\$404,148	\$509,197
Metering											
General Purpose	151x	\$10,102	\$2,642	\$3,205	\$3,196	\$3,196	\$3,196	\$3,205	\$16,000	\$0	\$28,744
Metering total		\$10,102	\$2,642	\$3,205	\$3,196	\$3,196	\$3,196	\$3,205	\$16,000	\$0	\$28,744
Programs											
Programs	17xx	\$22,854	\$18,281	\$19,923	\$13,956	\$14,853	\$16,205	\$24,347	\$89,285	\$225,779	\$356,200
Programs	38xx	\$0	\$489	\$1,069	\$1,066	\$0	\$0	\$0	\$2,135	\$0	\$2,624
Programs total		\$22,854	\$18,770	\$20,992	\$15,022	\$14,853	\$16,205	\$24,347	\$91,420	\$225,779	\$358,824
Security											
General Purpose	341x	\$5,258	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,259
Security total		\$5,258	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,259
General Purpose											
General Purpose	371x	\$0	\$0	\$0	\$0	\$0	\$0	\$23	\$23	\$24,977	\$25,000
General Purpose total		\$0	\$0	\$0	\$0	\$0	\$0	\$23	\$23	\$24,977	\$25,000
Grand Total		\$377,159	\$247,446	\$252,974	\$212,566	\$174,482	\$179,831	\$160,801	\$980,659	\$1,980,193	\$3,585,458

22 GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

23

WASTEWATER

Financial figures are in thousands of dollars (\$1,000's)

Category	Category	Lifetime Actual	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028	FY 2029 &	Project
	Number	Thru FY 2022							CIP Total	Beyond	Total
WRRF											
Primary Treatment	211x	\$74,515	\$16,070	\$25,721	\$33,944	\$32,864	\$30,121	\$34,132	\$156,782	\$231,311	\$478,678
Secondary Treatment and Disinfection	212x	\$969	\$2,971	\$11,039	\$11,090	\$11,090	\$13,322	\$13,825	\$60,366	\$147,314	\$211,620
Residuals Management	213x	\$22,237	\$2,469	\$1,050	\$413	\$2,794	\$4,166	\$3,443	\$11,867	\$201,757	\$238,330
Industrial Waste Control	214x	\$14,300	\$233	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$14,533
General Purpose	216x	\$16,263	\$20,101	\$22,577	\$35,425	\$24,868	\$21,341	\$4,410	\$108,621	\$95,425	\$240,410
WRRF Total		\$128,284	\$41,844	\$60,387	\$80,872	\$71,616	\$68,950	\$55,810	\$337,636	\$675,807	\$1,183,571
Field Services											
General Purpose	221x	\$3,577	\$12,159	\$7,254	\$1,466	\$1,466	\$2,471	\$1,046	\$13,702	\$38,164	\$67,603
Interceptor	222x	\$46,333	\$27,014	\$32,189	\$26,466	\$21,138	\$4,010	\$2,274	\$86,077	\$99,518	\$258,942
Field Services Total		\$49,910	\$39,173	\$39,443	\$27,932	\$22,604	\$6,481	\$3,320	\$99,779	\$137,682	\$326,545
Systems Control Center											
General Purpose	231x	\$37,583	\$28,848	\$36,752	\$30,326	\$16,594	\$6,679	\$9,537	\$99,888	\$16,217	\$182,536
Pump Stations	232x	\$55,358	\$8,661	\$24,311	\$26,206	\$29,461	\$29,461	\$17,433	\$126,872	\$413,989	\$604,880
In System Devices (Dams, ISD's)	233x	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$46,436	\$46,436
Systems Control Center Total		\$92,941	\$37,509	\$61,063	\$56,532	\$46,055	\$36,140	\$26,970	\$226,760	\$476,642	\$833,852
Programs											
Programs	26xx	\$27,101	\$15,654	\$17,353	\$13,145	\$14,914	\$9,816	\$4,038	\$59,266	\$1,031,335	\$1,133,356
Programs Total		\$27,101	\$15,654	\$17,353	\$13,145	\$14,914	\$9,816	\$4,038	\$59,266	\$1,031,335	\$1,133,356
CSO Facilities					. ,						
Multiple CSO Facilities	270x	\$5,627	\$7,697	\$5,430	\$3,172	\$4,184	\$7,976	\$12,075	\$32,836	\$70,404	\$116,563
Hubbell Southfield	273x	\$425	\$104	\$228	\$2,971	\$2,521	\$3,102	\$10,813	\$19,634	\$34,561	\$54,725
Conner Creek	276x	\$2,227	\$361	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,588
Baby Creek	277x	\$2,186	\$4,400	\$4,120	\$3,190	\$3,190	\$2,194	\$0	\$12,693	\$745	\$20,025
CSO Facilities Total		\$10,465	\$12,562	\$9,778	\$9,333	\$9,895	\$13,272	\$22,888	\$65,163	\$105,710	\$193,901
Security											
General Purpose	341x	\$2,345	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,363
Security Total		\$2,345	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,363
Grand Total		\$311,046	\$146,760	\$188,024	\$187,814	\$165,084	\$134,659	\$113,026	\$788,604	\$2,427,176	\$3,673,588

CIP SUMMARY 2.1. CIP 5-YEAR SUMMARY TABLES

CENTRALIZED SERVICES

Financial figures are in thousands of dollars (\$1,000's)

Class Level 2	Class Level 3	Category Number	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 CIP Total	FY 2029 & Beyond	Project Total
Security	General Purpose	341x	\$7,603	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,622
General Purpose	General Purpose	371x	\$0	\$0	\$0	\$0	\$0	\$0	\$23	\$23	\$24,977	\$25,000
Programs	Programs	38xx	\$0	\$489	\$1,069	\$1,066	\$0	\$0	\$0	\$2,135	\$0	\$2,624

Please note that these project categories and projected budgets also appear in water and wastewater tables above.

CIP SUMMARY 2.1. CIP 5-YEAR SUMMARY TABLES

2.2. PROJECT STATUS

A status is assigned to each project or program within the CIP. The project status designation provides a high-level understanding of the progress of the project or program. Projects are categorized by activity levels within the Work Breakdown Structure, and multiple activity levels are based on the contract type. As such, each activity level of a project will have its own status and contract number. Descriptions of each status are provided below. Projects that have been newly introduced into the CIP this year have been designated as "New to the CIP" based upon a checkmark within the Business

Project Status	Description
Active - Pre-Procurement - Construction	The RFB (and other supporting documents) are in development.
Active - Pre-Procurement - Design	The RFP (and other supporting documents) are in development.
Active - Procurement - Board Approved - Construction	The negotiated terms and conditions with the successful bidder have gone to the board and been approved but contract has not yet been execute.
Active - Procurement - Board Approved - Design	The negotiated terms and conditions with the successful bidder have gone to the board and been approved but contract has not yet been execute.
Active - Procurement - Construction	An RFB (and other required documentation) have been submitted to the Procurement group for solicitation of proposals.
Active - Procurement - Design	An RFP (and other required documentation) have been submitted to the Procurement group for solicitation of proposals.
Active - Procurement - Negotiation Phase - Construction	The lowest responsible bidder for contract labor services has been notified to begin negotiations.
Active - Procurement - Negotiation Phase - Design	The highest responsible scored bidder for professional services has been notified to begin negotiations.
Archived	Project that has been identified as Closed within the CIP the previous year.
Cancelled	Project that has been completely cancelled and removed from the CIP.
Closed	Project that has been officially completed.
Future Planned - Ten-Year CIP	Project Pushed out to years 6-10
Future Planned - Within 5 Year Plan	Project that was included in the previous CIP and does not have an assigned BS and A Project Number.
Pending Closeout	Project that has an assigned BS and A Project Number, a Notice to Start Work has been issued, has projected expenditures for the current fiscal year equal to \$100,000 or less - with no future projected expenditures and has reached substantial completion.
Project Execution - Construction	There is a fully executed contract for the active phase

Project Status

Project Execution - Design

Reclassified

Multiple CIP types are necessary to distinguish the differences in intent of how a CIP item is to be used. This CIP contains two primary CIP types: Projects and Programs. A typical project that has a specific scope and timeframe is considered a Project. Whereas Programs represent projects that address repetitive scope to address the replacement and/or rehabilitation of specific capital assets on an ongoing or reoccurring basis. Programs are typically constant and extend over many years.

Project Type

Project

Program

Description

There is a fully executed contract for the active phase Project that has been merged into the scope of work of an existing project.

Description

A "Project" consists of the replacement and/or rehabilitation of specific capital assets within a finite timeframe and scope.

A "Program" consists of the replacement and/or rehabilitation of specific capital assets on an ongoing or reoccurring basis. The program scope and/or projected expenses may vary from year-to-year depending on the needs identified within the program and as newly established programs develop consistent schedules, requirements, and history over time. Although not typically identified in the CIP future years projected expenses, these programs will typically be funded in perpetuity. Many projects have changed status since the last CIP update. These projects are shown in the following tables:

NEW PROJECTS ADDED TO THE CIP

CIPNumber	Title	Project_Status
112007	NEWTP-Header Galleries and Washwater Building Structural Repair	Future Planned - Within 5 Year Plan
113009	SW Flight and Chain Upgrades	Project Execution - Construction
170904*	Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II	Active - Procurement - Construction
222008	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure	Future Planned - Within 5 Year Plan
260210*	Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee	Future Planned - Within 5 Year Plan
260802*	2022 WRRF Roof Improvements Project	Project Execution - Design
260904*	WRRF 3rd Floor Renovation	Active - Procurement - Design
260905*	WRRF Plumbing Shop Renovation - 260905	Project Execution - Design
276002	Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility	Project Execution - Construction

*Project from a program

PROJECTS PROGRESSED TO ACTIVE STATUS

CIPNumber	Title	2023 Status	2024 Status
122019	Jefferson Main Replacement Project	Future Planned - Within 5 Year Plan	Project Execution - Design
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System	Future Planned - Within 5 Year Plan	Project Execution - Design
260900	WRRF Facility Optimization Program	Future Planned - Within 5 Year Plan	Project Execution - Design
270001	Pilot CSO Netting Facility	Future Planned - Within 5 Year Plan	Active - Pre-Procurement - Design
270006	CSO Facilities Improvements II	Future Planned - Within 5 Year Plan	Active - Procurement - Design
273001	Hubbell Southfield CSO Facility Improvements	Future Planned - Within 5 Year Plan	Active - Procurement - Design

PROJECTS WITH CLOSED STATUS IN FY24-28

CIPNumber	Title	2023 Status	2024 Status
111007	Lake Huron Water Treatment Plant, Raw Sludge Clarifier and Raw Sludge Pumping System Improvements	Pending Closeout	Closed
211001	WRRF Rehabilitation of Primary Clarifiers Rectangular Tanks, Drain Lines, Electrical/Mechanical Building and Pipe Gallery	Project Execution - Construction	Closed
214001	WRRF Relocation of Industrial Waste Control Division and Analytical Laboratory Operations	Project Execution - Construction	Closed
216007	DTE Primary Electric 3rd Feed Supply to WRRF	Pending Closeout	Closed
260504	Phase 2 Outfalls- 19000796	Project Execution - Construction	Closed
260613	Baby Creek HVAC Improvements	Project Execution - Construction	Closed
260615	Puritan Fenkell & Leib Site Improvements	Project Execution - Construction	Closed
260621	Conner Creek Dike Improvements	Project Execution - Construction	Closed
341001	Security Infrastructure Improvements on Water Facilities	Pending Closeout	Closed
341002	Security Infrastructure Improvements for Wastewater Facilities	Pending Closeout	Closed

PROJECTS PENDING CLOSEOUT STATUS IN FY 24-28

CIPNumber	Title	2023 Status	2024 Status
170109	GLWA-CS-187: FK Eng: Raw Water Intake	Project Execution - Design	Pending Closeout
260603	Conner Creek CSO RTB Automation Improvements	Project Execution - Construction	Pending Closeout
260620	Baby Creek Roof Replacement	Project Execution - Construction	Pending Closeout

PROJECTS WITH CANCELLED STATUS IN FY 24-28

CIPNumber	Title	2023 Status	2024 Status
113008	SWP Reservoir Replacement	Future Planned - Ten-Year CIP	Cancelled

RECLASSIFIED PROJECTS

CIPNumber	New CIP Number	Title	2023 Status	2024 Status
260617	270006	St. Aubin Chemical Disinfection Improvements	Active - Procurement - Design	Reclassified
270005	270006	CSO Facility Safety Improvements and Building Rehabilitation	Future Planned - Within 5 Year Plan	Reclassified

2.3. LINEAR ASSETS

Many projects included in the CIP take place at GLWA facilities and on what GLWA considers to be vertical assets. However, GLWA manages many miles of water transmission mains and sewer interceptors. Projects on these linear assets are listed below. A spatial view and understanding of these project locations can be found in the CIP Viewer located within the WAMR and GDRSS Member Outreach Portals after the Board Approval and adoption of the annual CIP Plan.

CIPNumber	Title
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements
122003	Water Works Park to Northeast Transmission Main
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations
122005	Schoolcraft Road Water Transmission Main
122006	Wick Road Water Transmission Main
122007	Merriman Road Water Transmission Main Loop
122011	Park-Merriman Road Water Transmission Main
122013	14 Mile Transmission Main Loop
122016	Downriver Transmission Main Loop
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation
122019	Jefferson Main Replacement Project
170109	GLWA-CS-187: FK Eng: Raw Water Intake

CIPNumber	Title
170400	Water Transmission Improvement F
170500	Transmission System Valve Rehab
170502	Transmission System Valve Rehab
170503	Transmission System Valve Replac
170504	Transmission Mains Valves and Urg
170600	Linear System Integrity Program
170601	Linear System Integrity Program
170900	Suburban Water Meter Pit Rehabili
170901	Suburban Water Meter Pit Rehabili
170902	Brownstown Meter Pit
170904	Wholesale Water Meterpit Rehabilit
222001	Oakwood District Intercommunity R
222002	Detroit River Interceptor (DRI) Eval
222008	North Interceptor East Arm (NIEA)
233003	Rouge River In-system Storage De
260200	Sewer and Interceptor Rehabilitation
260201	CON-149, Emergency Sewer Repa
260204	Conveyance System Engineering S
260205	NWI Rehabilitation
260206	Conveyance System Repairs (Sew
260207	Rehabilitation of Woodward Sewer
260209	Sewer Rehabilitation and Repair
260210	Rehabilitation of GLWA Sewers; As Shiawassee
260510	Conveyance System Repairs (Out
260700	Sewer System Infrastructure Impro
260701	Conveyance System Infrastructure
380700	As-Needed Geotechnical and Relat

2.3. LINEAR ASSETS

Program
pilitation and Replacement Program
pilitation and Replacement Program
cement
rgent
litation and Meter Replacement
litation and Meter Replacement
itation and Meter Upgrade - Phase II
Relief Sewer Modification at Oakwood District
aluation and Rehabilitation
7 Mile Road Diversion Structure
evices
on Program
air
Services-1802575
wers)
r Systems
shland Relief, Linwood, Lonyo, Second Avenue, and
tfalls)
ovements and Pumping Stations

Improvements

ated Engineering Services

2.4. PROJECTS BY JURISDICTION

The following projects listed are under the jurisdiction of the physical location of the project. Projects that are planned for multiple facilities within multiple jurisdictions are identified as "Multiple Counties". A spatial view and understanding of these project locations, will be able to be found in the CIP Viewer located within the WAMR and GDRSS Member Outreach Portals after the Board Approval and adoption of the yearly CIP Plan.

Jurisdiction	(CIPNumber				•		
City of Detroit								
	112003	112006	112007	115001	115005	115006	115007	115009
	116002	116005	116006	122003	122017	122018	122019	170304
	170305	170307	170803	211001	211002	211005	211006	211007
	211008	211009	211010	211011	212008	212009	212010	213006
	213007	213008	213009	214001	216004	216006	216007	216008
	216011	222002	222008	232001	232002	232004	260205	260206
	260207	260508	260510	260603	260615	260617	260618	260621
	260802	260900	260901	260902	260903	260904	260905	261000
	261001	270001	270002	270004	270008	270010	270011	270013
	270014	276002						
Lapeer County								
	132007	132021						
Multiple Counties								
	116007	122004	170109	170300	170303	170400	170500	170502
	170503	170504	170600	170601	170800	170801	170802	170900
	170901	170904	171500	171502	222001	260200	260201	260204
	260209	260500	260504	260600	260614	260619	260622	260700
	260701	260702	260800	270003	270007	270009	270012	277001
	341001	341002	380700	381000	383300			
Oakland County								
	122013	132010	132014	132016	132020	273001		
Saint Clair County								
	111001	111006	111007	111008	111009	111010	111011	111012

Wayne County -	Outside De	troit						
	113003	113006	113007	113008	113009	114002	114005	114007
	114008	114010	114011	114016	114017	114018	122005	122006
	122007	122011	122016	132012	132015	132018	132019	132022
	170302	170306	170902	233003	260210	260613	260620	260623
	270005	270006	273002	277002				

CIP SUMMARY 2.4. PROJECTS BY JURISDICTION


es Etterations, R. Id Parts Het man Parts Het man Parts Het man Parts Het man Parts	Jayoe Park Bornen Ave	7 Mie Ro 7 Mie Ro 6 Mie Ro 6 Mie Ro 6 Mie Ro 6 Mie Ro 6 Mie Ro 6 Mie Ro 8 ugust 6 Mie Ro 8 ugust 6 Mie Ro 8 ugust 6 meter 8 ugust 6 meter 8 ugust 8 ugust 9	
mai Rd	strai Dr	Giendale Par Redford Control F	Fulleron St Gange
Map#	CIP Title	CIP Nos	Rouge Park Golf Course 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1
1	7 Mile/Nevada Transmission Main Rehab & Carrie/Nevada Flow Control Station	122017	Plymouth Rd C 2 35 X0 V V V V V V V V V V V V V V V V V V
2	Freud & Conner Creek Pump Station Improvements	232002	Park 1 Pa
3	Detroit River Interceptor (DRI) Evaluation & Rehab	222002	Read In 18 19
4	Fairview Pumping Station - Replace Four Sanitary Pumps Jefferson Main Replacement Project	232001 122019	Rouge Park 2 Dover St and Joy Rd Joy
6	Water Resource Recovery Facility (WRRF) - Multiple Projects (29)	211002, 211005-011, 212008- 010, 213006-009, 216004, 216006, 216008, 216011, 260800, 260802, 260900-905, 261000- 261001	Samp Mary State And State
7	Northeast WTP - Multiple Projects (5)	112003, 112006-007,	All and a set of a se
8	Oakwood Pumping Station - Multiple Projects (3)	116002,170307 260618, 270004, 222001	
9	Water Board Building/System Wide - Multiple Projects (53)	116007, 170300, 170303, 170400, 170500, 170502-504, 170600- 601, 170800-803, 170904, 171500, 171502, 222008, 233003, 260200-001, 260204-210, 260500, 260508, 260510, 260600, 260614, 260619, 260622, 260700 702, 270001-002, 270005-014, 380700, 381000, 383300	Henry Ford Us Us
10	Water Works Park WTP - Multiple Projects (10)	115001, 115005-009, 122003, 122018, 170304-305	Ford Rouge St
11	St. Aubin Chemical Disinfection Improvements	260617	Proving Grounds
12	Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility	276002	and the state of t
13	Belle Isle Intake System Rehabilitation and Improvements - Multiple Projects (2)	116005-006	sense august and a sense and a sens
14	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure	222008	Penn St Carlysk St Carlysk St St Carlysk St
15	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements	116002	IS IS IS A VIEW SI SHARE
16	Conveyance System Engineering Services-1802575	260204	And the second s
17	Rehabilitation of Woodward Sewer Systems	260207	Milled M delen Ave of Pu ecolo River 401
18 19	New Water Main from NEWTP to WWP Garland, Hurlbut, Bewick Water Transmission System Rehabilitation	122003 122018	Black Oak
20	Water Transmission Improvement Program	170400	Soon Out at a soon Park
21	Conveyance System Repairs (Sewers)	260206	Allen Park
22	Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee	260210	Rob



CURRENT GLWA FY 2024-2028 CIP PROJECTS - INSIDE CITY OF DETROIT

Notes: Projects depicted on this map are based on the best available data at this time. They may not be completely accurate including spatial representations, leased statuses or attribute values. The user accepts responsibility for accuracy of any referenced information, spatial or otherwise.





CIP Title	CIP Nos	
roit Map		
and Jefferson	170901	
Main Relocation and Isolation Valve	122004	
ements Project - Multiple Projects (3)	277001-002, 260623	
ent Plant - Multiple Projects (7)	111001,11006, 111008-012	
Improvements	132020	
provements - Multiple Projects (2)	132007, 132021	
n Loop	122013	
ping Station	132010	
unt Plant Multiple Projects (E)	113003, 113006-007, 113009,	
nt Plant - Multiple Projects (5)	170302	
	114002, 114005, 114007-008,	
ent Plant - Multiple Projects (10)	114010-011, 114016-018,	
	170306	
ansmission Main	122005	
ssion Main	122006	
er Transmission Main	122011	
1ain Loop	122016	
Station Improvements	132012	
Pumping Station Improvements	132015	
ping Station Improvements	132016	
ot in the map)	170902	
nsmission Main Loop	122007	
on Improvements	132018	
on Improvements	132019	
tion Improvements	132014	
Improvements	132022	
Blue Hill Pump Station	232004	
cility Improvements - Multiple Projects (2)	273001-002	
and VR-15 Improvements	270002	
er and Trowbridge	170900	
an will be conducted throughout the Metro	270003	
(Not in the map)		
	ļ	

2.5. SPECIALTY PROJECTS

PROJECTS WITH THE POTENTIAL TO BE INNOVATIVE

One of GLWA's main organizational guiding pillars is to provide high quality through innovation. To ensure CIP projects are being considered for new and innovative technologies, during the project review process, projects that may be considered for innovative technologies, practices, or procedures were identified by the GLWA Energy, Research & Innovation Group. The following projects will be further evaluated for innovative opportunities during the scope development process:

CIPNumber	Title
111001	Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements
111006	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements
111011	Lake Huron WTP Pilot Plant
111012	LHWTP-Flocculation Improvements
113003	Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements
113007	Southwest Water Treatment Plant Architectural and Building Mechanical Improvements
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation
132007	Energy Management: Freeze Protection Pump Installation at Imlay Pump Station
132021	Imlay Pumping Station Improvements
132022	Joy Road Pumping Station Improvements
170600	Linear System Integrity Program
211006	WRRF PS No. 1 Improvements
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements
211008	WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System
211011	WRRF PS1 Screening and Grit Improvements
212008	WRRF Aeration Improvements 1 and 2
212009	WRRF Aeration Improvements 3 and 4
212010	WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite
213008	WRRF Rehabilitation of the Ash Handling Systems
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station
260603	Conner Creek CSO RTB Automation Improvements
260620	Baby Creek Roof Replacement
260902	WRRF 4th Floor Renovation
270014	Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities

WATER MASTER PLAN RIGHT-SIZING PROJECTS

Based upon the completion and acceptance of the 2015 Comprehensive Water Master Plan, many water projects are being considered with reduced capital investment to reduce the rated capacity to master plan identified levels based upon current population and water usage. The following projects have capital expenditure avoidance based upon water master planning efforts to right-size the system for current needs:

CIPNumber	Title
111001	Lake Huron Water Treatment Plant, I Improvements
111010	Filtration Improvements
111011	Lake Huron WTP Pilot Plant
112003	Northeast Water Treatment Plant Hig
113003	Southwest Water Treatment Plant, Lo System Improvements
114002	Springwells Water Treatment Plant, I
115001	Water Works Park Water Treatment
115007	Water Works Park High Lift Pumping
122003	Water Works Park to Northeast Trans
122007	Merriman Road Water Transmission
122017	7 Mile/Nevada Transmission Main Re
132007	Energy Management: Freeze Protec
132019	Wick Road Pumping Station Improve
132021	Imlay Pumping Station Improvement

WASTEWATER MASTER PLAN PROJECTS

GLWA has recently completed the first Wastewater Master Plan. The following projects have come about due to recommendations in this Master Plan:

Title
WRRF Biosolids Processing Improve
Rehabilitation of Screened Final Efflu
Oakwood District Intercommunity Re
North Interceptor East Arm (NIEA) 7
CONDITION ASSESSMENT AT BLU
Rouge River In-system Storage Devi
WRRF 3rd Floor Renovation
Pilot CSO Netting Facility
Meldrum Sewer Diversion and VR-15
Oakwood and Leib CSO Facilities Im

Low-Lift, High Lift and Filter Backwash Pumping System

igh-Lift Pumping Station Improvements Low- and High-Lift Pumping Station, Flocculation and Filtration

Low-Lift and High-Lift Pumping Station Improvements

Plant Yard Piping, Valves and Venturi Meters Replacement

g Station Modernization

nsmission Main

Main Loop

Rehab and Carrie/Nevada Flow Control Station

ction Pump Installation at Imlay Pump Station

rements

nts

ovements
ffluent (SFE) Pump Station
Relief Sewer Modification at Oakwood District
7 Mile Road Diversion Structure
LUE HILL PUMP STATION
evices

5 Improvements

nprovement Project

NORTHEAST WATER TREATMENT PLANT REPURPOSING RELATED PROJECTS

The 2015 Comprehensive Water Master Plan has identified reducing the number of water treatment facilities in full operation at GLWA. Initially, for long-term capital expenditure avoidance, the plan has identified the repurposing of the Northeast Water Treatment Plant. Several capital projects are necessary to repurpose this facility into a reservoir and pump station to achieve the savings identified in the master plan. The following projects are associated with the repurposing of the Northeast Water Treatment Plant:

CIPNumber	Title
112003	Northeast Water Treatment Plant High-Lift Pumping Station Improvements
112007	NEWTP-Header Galleries and Washwater Building Structural Repair
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement
115007	Water Works Park High Lift Pumping Station Modernization
122003	Water Works Park to Northeast Transmission Main
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation

REDUNDANCY PROJECTS

Projects which will increase the redundancy of GLWA infrastructure are listed below:

Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System ovements
Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering ovements
Huron Water Treatment Plant - High Lift Pumping, Water Production Flow Metering and Yard g Improvements
tion Improvements
east Water Treatment Plant High-Lift Pumping Station Improvements
gwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements
gwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists ovements
gwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements
gwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete ment Replacement
gwells Water Treatment Plant Flocculator Drive Replacements
r Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement
sylvania and Springwells Raw Water Supply Tunnel Improvements
r Works Park to Northeast Transmission Main

CIPNumber	Title
122004	96-inch Water Transmission Main Rele
122004	Schoolcraft Road Water Transmission
122005	Wick Road Water Transmission Main
122000	Merriman Road Water Transmission Main
122007	Park-Merriman Road Water Transmission
122013	14 Mile Transmission Main Loop
122016	Downriver Transmission Main Loop
122017	7 Mile/Nevada Transmission Main Rel
122018	Garland, Hurlbut, Bewick Water Trans
132007	Energy Management: Freeze Protecti
132010	West Service Center Pumping Station
132012	Ypsilanti Booster Pumping Station Imp
132015	Newburgh Road Booster Pumping Sta
132016	North Service Center Pumping Station
132018	Schoolcraft Pumping Station Improver
132019	Wick Road Pumping Station Improver
132021	Imlay Pumping Station Improvements
132022	Joy Road Pumping Station Improvem
170400	Water Transmission Improvement Pro
170500	Transmission System Valve Rehabilita
170800	System-Wide Finished Water Reserve
170801	Reservoir Inspection, Design and Cor Plant, Springwells Water Treatment P
170802	Reservoir Inspection, Design, and Co
170803	Reservoir Inspection, Design, and Co
211002	WRRF PS No. 2 Pumping Improvement
211005	WRRF PS No. 2 Improvements Phase
211006	WRRF PS No. 1 Improvements
211007	WRRF PS #2 Bar Racks Replacemen
211008	WRRF Rehabilitation of Ferric Chlorid
211009	WRRF Rehabilitation of the Circular P
211010	Rehabilitation of Sludge Processing C
211011	WRRF PS1 Screening and Grit Impro
212008	WRRF Aeration Improvements 1 and
212009	WRRF Aeration Improvements 3 and
213006	WRRF Improvements to Sludge Feed
213007	WRRF Modification to Incinerator Slug
213008	WRRF Rehabilitation of the Ash Hand

CIP SUMMARY 2.5. SPECIALTY PROJECTS

ocation and	Isolation	Valve	Installations

n Main

Main	Loop
sion	Main

- hab and Carrie/Nevada Flow Control Station
- smission System Rehabilitation
- ion Pump Installation at Imlay Pump Station
- n Reservoir, Reservoir Pumping, and Division Valve Upgrades
- tation Improvements
- n Improvements
- ements
- ments
- ;
- ents
- ogram
- ation and Replacement Program
- voir Inspection, Design and Rehabilitation
- nstruction Project at Imlay Station, Lake Huron Water Treatment Plant, And Southwest Water Treatment Plant
- onstruction Management Services Phase II
- III onstruction Management Services Phase III
- ents Phase 1
- e II
- nts and Grit Collection System Improvements
- de Feed System in PS-1 and Complex B Sludge Lines
- Primary Clarifier Scum Removal System
- Complexes A and B
- ovements
- 2
- 4
- d Pumps at Dewatering Facilities
- dge Feed Systems at Complex -II
- dling Systems

CIPNumber	Title
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities
222001	Oakwood District Intercommunity Relief Sewer Modification at Oakwood District
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation
222008	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure
232001	Fairview Pumping Station - Replace Four Sanitary Pumps
232002	Freud & Conner Creek Pump Station Improvements
232004	CONDITION ASSESSMENT AT BLUE HILL PUMP STATION
260200	Sewer and Interceptor Rehabilitation Program
260500	CSO Outfall Rehabilitation
260510	Conveyance System Repairs (Outfalls)
260600	CSO FACILITIES IMPROVEMENT PROGRAM
260619	Control System Upgrade - St Aubin, Lieb & Mile
260623	CSO Baby Creek Screen Rehabilitation
260800	WRRF ROOF REPLACEMENT FOR MULTIPLE FACILITIES PROGRAM
261000	WRRF Rehabilitation of the Secondary Clarifiers
261001	WRRF Rehabilitation of the Secondary Clarifiers Phase 1
270002	Meldrum Sewer Diversion and VR-15 Improvements
270010	HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities
273002	CSO Hubbell Southfield VR-8 Gate Improvements
277002	Baby Creek CSO Facility Influent Flushing System
381000	Power Quality: Electric Metering Improvement Program

2.6. PROJECT BY TYPE

The following are CIP projects further broken down by category type, divided between Water Treatment, Transmission/Storage, and Pump Station. Furthermore, wastewater CIP projects are also broken down by category types - Treatment, Conveyance, CSO, and Pump Station.

WATER: PUMP STATIONS

CIPNumber	Title
132007	Energy Management: Freeze Protect
132010	West Service Center Pumping Station
132012	Ypsilanti Booster Pumping Station Im
132014	Adams Road Pumping Station Improv
132015	Newburgh Road Booster Pumping St
132016	North Service Center Pumping Station
132018	Schoolcraft Pumping Station Improve
132019	Wick Road Pumping Station Improver
132020	Franklin Pumping Station Improveme
132021	Imlay Pumping Station Improvements
132022	Joy Road Pumping Station Improvem

ction Pump Installation at Imlay Pump Station on - Reservoir, Reservoir Pumping, and Division Valve Upgrades mprovements ovements Station Improvements on Improvements ements ements ents ts ments

CIP SUMMARY 2.6. PROJECT BY TYPE

WATER: TRANSMISSION AND STORAGE

CIPNumber	Title
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements
122003	Water Works Park to Northeast Transmission Main
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations
122005	Schoolcraft Road Water Transmission Main
122006	Wick Road Water Transmission Main
122007	Merriman Road Water Transmission Main Loop
122011	Park-Merriman Road Water Transmission Main
122013	14 Mile Transmission Main Loop
122016	Downriver Transmission Main Loop
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation
122019	Jefferson Main Replacement Project
170109	GLWA-CS-187: FK Eng: Raw Water Intake
170400	Water Transmission Improvement Program
170500	Transmission System Valve Rehabilitation and Replacement Program
170502	Transmission System Valve Rehabilitation and Replacement Program
170503	Transmission System Valve Replacement
170504	Transmission Mains Valves and Urgent
170600	Linear System Integrity Program
170601	Linear System Integrity Program
170800	System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation
170801	Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, Springwells Water Treatment Plant, And Southwest Water Treatment Plant
170802	Reservoir Inspection, Design, and Construction Management Services Phase II
170803	Reservoir Inspection, Design, and Construction Management Services Phase III
170900	Suburban Water Meter Pit Rehabilitation and Meter Replacement
170901	Suburban Water Meter Pit Rehabilitation and Meter Replacement
170902	Brownstown Meter Pit
170904	Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II
380700	As-Needed Geotechnical and Related Engineering Services

WATER: TREATMENT

CIPNumber	Title
111001	Lake Huron Water Treatment Plan Improvements
111006	Lake Huron Water Treatment Plan Improvements
111008	Lake Huron Water Treatment Plan Improvements
111009	Lake Huron Water Treatment Plan Piping Improvements
111010	Filtration Improvements
111011	Lake Huron WTP Pilot Plant
111012	LHWTP-Flocculation Improvemen
112003	Northeast Water Treatment Plant
112006	Northeast Water Treatment Plant
112007	NEWTP-Header Galleries and Wa
113003	Southwest Water Treatment Plant System Improvements
113006	Southwest Water Treatment Plant Improvements
113007	Southwest Water Treatment Plant
113009	SW Flight and Chain Upgrades
114002	Springwells Water Treatment Plan
114005	Springwells Water Treatment Plan Protection Loop
114007	Springwells Water Treatment Plan
114008	Springwells Water Treatment Plan Improvements
114010	Springwells Water Treatment Plan
114011	Springwells Water Treatment Plan Improvements
114016	Springwells Water Treatment Plan Pavement Replacement
114017	Springwells Water Treatment Plan
114018	Springwells Water Treatment Plan Improvements
115001	Water Works Park Water Treatme
115005	WWP WTP Building Ventilation Im
115006	Water Works Park Site/Civil Impro

CIP SUMMARY 2.6. PROJECT BY TYPE

nt, Low-Lift, High Lift and Filter Backwash Pumping System

- nt, Filter Instrumentation and Raw Water Flow Metering
- nt, Architectural Programming for Laboratory and Admin Building
- nt High Lift Pumping, Water Production Flow Metering and Yard

nts

- High-Lift Pumping Station Improvements
- Flocculator Replacements
- ashwater Building Structural Repair
- t, Low- and High-Lift Pumping Station, Flocculation and Filtration
- t Chlorine Scrubber, Raw Water Screens & Related
- t Architectural and Building Mechanical Improvements
- nt, Low-Lift and High-Lift Pumping Station Improvements nt, Administration Building Improvements & Underground Fire
- nt Powdered Activated Carbon System Improvements nt 1930 Sedimentation Basin Sluice Gates, Guides & Hoists
- nt, Yard Piping and High-Lift Header Improvements nt Steam, Condensate Return, and Compressed Air Piping
- nt 1958 Settled Water Conduits and Loading Dock Concrete
- nt Flocculator Drive Replacements nt - Service Building Electrical Substation and Miscellaneous
- ent Plant Yard Piping, Valves and Venturi Meters Replacement mprovements ovements

CIPNumber	Title						
115007	Water Works Park High Lift Pumping Station Modernization						
115009	Water Works Park Sedimentation Basins Structural Upgrades						
116005	Belle Isle Seawall Rehabilitation						
116006	Belle Isle Intake System Rehabilitation and Improvements						
116007	System Electrical Power Improvements						
170300	Water Treatment Plant Automation Program						
170302	SW SCADA System Upgrade						
170303	Power Monitoring Installation for Water Treatment Plants						
170304	WWP Scada Infrastructure Upgrade						
170305	WWP SCADA Network Upgrade						
170306	SPW SCADA PLC Network Upgrade						
170307	NE SCADA Network Upgrade						
171500	Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities						
171502	Lake Huron and Southwest Roof Replacement						
381000	Power Quality: Electric Metering Improvement Program						
383300	Masonry Replacement and Rehabilitation Program						

WASTEWATER: TREATMENT

CIPNumber	Title
211002	WRRF PS No. 2 Pumping Improvements - Phase 1
211005	WRRF PS No. 2 Improvements Phase II
211006	WRRF PS No. 1 Improvements
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements
211008	WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System
211010	Rehabilitation of Sludge Processing Complexes A and B
211011	WRRF PS1 Screening and Grit Improvements
212008	WRRF Aeration Improvements 1 and 2
212009	WRRF Aeration Improvements 3 and 4
212010	WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite
213006	WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities
213007	WRRF Modification to Incinerator Sludge Feed Systems at Complex -II
213008	WRRF Rehabilitation of the Ash Handling Systems
213009	WRRF Biosolids Processing Improvements
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station

CIPNumber	Title
216011	WRRF Structural Improvements
260800	WRRF ROOF REPLACEMENT FOR
260802	2022 WRRF Roof Improvements Pro
260900	WRRF Facility Optimization Program
260901	Rehabilitation of HAZMAT Facility at
260902	WRRF 4th Floor Renovation
260903	WRRF Front Entrance Rehabilitation
260904	WRRF 3rd Floor Renovation
260905	WRRF Plumbing Shop Renovation - 2
261000	WRRF Rehabilitation of the Seconda
261001	WRRF Rehabilitation of the Seconda

WASTEWATER: PUMP STATIONS

CIPNumber	Title
232001	Fairview Pumping Station - Replace Fe
232002	Freud & Conner Creek Pump Station I
232004	CONDITION ASSESSMENT AT BLUE
260702	Pump Station Assets Updates

WASTEWATER: CONVEYANCE

	T '(1,
CIPNumber	Title
222001	Oakwood District Intercommunity Re
222002	Detroit River Interceptor (DRI) Evalu
222008	North Interceptor East Arm (NIEA) 7
233003	Rouge River In-system Storage Devi
260200	Sewer and Interceptor Rehabilitation
260201	CON-149, Emergency Sewer Repair
260204	Conveyance System Engineering Se
260205	NWI Rehabilitation
260206	Conveyance System Repairs (Sewe
260207	Rehabilitation of Woodward Sewer S
260209	Sewer Rehabilitation and Repair
260210	Rehabilitation of GLWA Sewers; Ash
260510	Conveyance System Repairs (Outfa
260700	Sewer System Infrastructure Improve
260701	Conveyance System Infrastructure In

CIP SUMMARY 2.6. PROJECT BY TYPE

MULTIPLE FACILITIES PROGRAM

oject

WRRF

260905

ary Clarifiers

ary Clarifiers Phase 1

Four Sanitary Pumps

Improvements

E HILL PUMP STATION

elief Sewer Modification at Oakwood District

uation and Rehabilitation

7 Mile Road Diversion Structure

vices

n Program

r

ervices-1802575

vers)

Systems

hland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee falls) vements and Pumping Stations

Improvements

WASTEWATER: CSO

CIPNumber	Title			
260500	CSO Outfall Rehabilitation			
260508	B-39 Outfall Rehabilitation			
260600	CSO FACILITIES IMPROVEMENT PROGRAM			
260603	Conner Creek CSO RTB Automation Improvements			
260614	Structural Inspection & Structural Improvements			
260618	Oakwood HVAC Project			
260619	Control System Upgrade - St Aubin, Lieb & Mile			
260620	Baby Creek Roof Replacement			
260622	CSO Emergency Generator Improvements			
260623	CSO Baby Creek Screen Rehabilitation			
270001	Pilot CSO Netting Facility			
270002	Meldrum Sewer Diversion and VR-15 Improvements			
270003	Long Term CSO Control Plan			
270004	Oakwood and Leib CSO Facilities Improvement Project			
270006	CSO Facilities Improvements II			
270007 Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan F CSO Facilities				
270008 Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities				
270009	Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities			
270010	HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities			
270011	HVAC Improvements at Conner Creek and Belle Isle CSO Facilities			
270012	Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities			
270013	Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities			
270014	Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities			
273001	Hubbell Southfield CSO Facility Improvements			
273002	CSO Hubbell Southfield VR-8 Gate Improvements			
276002	Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility			
277001	Baby Creek Outfall Improvements Project			
277002	Baby Creek CSO Facility Influent Flushing System			

2.7. PROJECT SCORING

CRITERIA SCORING AND WEIGHTING

Water and wastewater projects continue to be scored based on the eight criteria shown in the table 1 of section 2.7. For each project, a criteria score of 1 to 5 has been assigned, with a score of 1 representing minimal value or benefit, and 5 representing high value or benefit based on established definitions and scoring guidelines for each criteria.

No.	Weight	Criteria
1	12%	Condition
2	15%	Performance (Service Level/ Reliability)
3	18%	Regulatory (Environmental/Legal)
4	11%	O&M
5	18%	Health and Safety
6	8%	Public Benefit
7	10%	Financial
8	8%	Efficiency and Innovation

Weights for the eight criteria in Table 1 have been established based on GLWA ranking of the relative importance of each criteria to GLWA's overall priorities. Two of the criteria weightings were revised last year to better reflect GLWA's overall priorities. The Health and Safety weighting was increased from 17% to 18% and the Efficiency & Innovation weighting was decreased from 9% to 8% to maintain a balanced total.

PROJECT SCORING AND PRIORITIZATION

The criteria scores and weighting are used to establish scores for each project by considering the following factors: 1) the single highest purpose and benefit of each project; and 2) the overall benefit of each project as follows:

- 1. The single highest purpose and benefit of each project represents the single criteria that provides the greatest relative benefit to GLWA. For example, a score of 5 for either Health and Safety or Regulatory criteria represents the greatest purpose and benefit to GLWA based on the established criteria weighting. This consideration has been reflected through the revised project scoring methodology and functions as the primary driver of the overall project score.
- 2. The overall benefit of each project accounts for all the benefits provided by the project and is represented by the sum of all the criteria scores for the project.

The calculation of project scores can be represented by the following equation, where factor 1 above contributes up to 70 out of 100 total points, and factor 2 contributes up to 30 of the total 100 points:

Total Project Score = Factor 1 (70/100)+ Factor 2 (30/100)

New projects and projects with significant changes were scored or re-scored by the Project Manager and the Review Committee. The Review Committee scores represent the final project score. Projects already existing in the CIP were evaluated using criteria scores applied in the previous CIP cycle. The pages that follow provide the new project scores from the Risk Committee along with those from the Project Manager for reference.

WATER PROJECT MANAGER & REVIEW COMMITTEE SCORES

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
111001	Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements	80.7	5	5	3	4	2	3	4	5	79.7	5	5	1	5	2	5	4	4
111006	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements	77.1	5	4	4	5	2	3	2	3	60.5	4	3	3	3	2	4	2	5
111007	Lake Huron Water Treatment Plant, Raw Sludge Clarifier and Raw Sludge Pumping System Improvements	54.4	3	3	3	1	1	2	1	2	74.4	5	5	1	2	2	1	4	1
111008	Lake Huron Water Treatment Plant, Architectural Programming for Laboratory and Admin Building Improvements	46	3	3	1	2	2	1	1	1	49.5	4	2	2	1	2	2	1	2
111009	Lake Huron Water Treatment Plant - High Lift Pumping, Water Pro- duction Flow Metering and Yard Piping Improvements	60.8	3	3	2	3	3	5	3	5	75.7	3	4	2	2	4	5	3	4
111010	Filtration Improvements	76.3	4	4	4	4	3	2	2	3	77.4	4	4	4	4	4	2	2	3
111011	Lake Huron WTP Pilot Plant	76.1	5	2	4	3	3	2	3	5	50.7	4	2	2	3	1	2	1	4
111012	LHWTP-Flocculation Improvements	92.1	5	4	5	4	2	2	3	4	91.5	5	4	5	4	2	2	2	4
112003	Northeast Water Treatment Plant High-Lift Pumping Station Im- provements	93.5	5	5	3	4	5	2	2	4	82.2	5	5	3	4	4	5	2	4
112006	Northeast Water Treatment Plant Flocculator Replacements	93	5	5	5	4	2	3	3	3	82.4	5	5	4	4	4	2	3	4
112007	NEWTP-Header Galleries and Washwater Building Structural Repair	96.1	5	5	5	2	5	5	5	1	95.2	5	5	4	3	5	4	5	1
113003	Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements	52.4	4	3	2	4	2	2	1	2	52.4	4	3	2	4	2	2	1	2
113006	Southwest Water Treatment Plant Chlorine Scrubber, Raw Water Screens & Related Improvements	90.6	4	3	4	2	5	4	1	3	90.6	4	3	4	2	5	4	1	3
113007	Southwest Water Treatment Plant Architectural and Building Me- chanical Improvements	40.8	3	1	2	3	1	3	2	4	38.7	3	2	1	3	1	1	2	2
113008	SWP Reservoir Replacement	27.4	1	1	1	2	1	2	2	3	75.6	4	3	4	4	3	2	4	1
113009	SW Flight and Chain Upgrades	68.7	5	4	3	4	3	3	4	4	68.7	5	4	3	4	3	3	4	4
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	98.3	5	5	4	5	5	5	4	5	90.9	5	5	1	5	5	2	1	3
114005	Springwells Water Treatment Plant, Administration Building Im- provements & Underground Fire Protection Loop	53.8	3	2	1	2	3	1	2	1	76.4	4	4	4	4	4	2	2	1
114007	Springwells Water Treatment Plant Powdered Activated Carbon System Improvements	36.8	3	2	1	1	1	2	1	1	36.8	3	2	1	1	1	2	1	1
114008	Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements	91.9	5	5	3	4	5	1	1	3	86.1	5	2	1	4	5	1	1	1
114010	Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements	68	5	4	2	4	3	5	3	4	58.3	3	3	1	3	3	4	3	3
114011	Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements	90.8	5	5	1	4	5	1	2	4	77	5	5	1	4	3	1	2	4

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
114016	Springwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete Pavement Replacement	72.6	5	4	1	3	4	1	1	2	71.7	5	3	1	3	4	1	1	2
114017	Springwells Water Treatment Plant Flocculator Drive Replacements	88.5	4	4	5	3	1	2	2	3	89.7	4	4	5	3	2	2	3	2
114018	Springwells Water Treatment Plant - Service Building Electrical Substation and Miscellaneous Improvements	56	4	3	1	3	3	1	2	1	62.7	4	4	2	3	3	1	2	1
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	78.1	5	5	1	5	2	4	3	3	77.9	5	5	2	3	2	4	3	3
115005	WWP WTP Building Ventilation Improvements	94.1	3	5	5	3	5	4	3	2	93	3	5	5	2	5	3	3	2
115006	Water Works Park Site/Civil Improvements	57	3	3	3	3	2	1	3	1	53.9	2	3	1	2	3	1	2	1
115007	Water Works Park High Lift Pumping Station Modernization	58.9	3	3	2	3	3	3	3	3	58.3	3	3	2	2	3	2	3	4
115009	Water Works Park Sedimentation Basins Structural Upgrades	75.3	4	3	4	1	4	2	5	1	75.3	4	3	4	1	4	2	5	1
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improve- ments	94.3	5	5	5	4	5	1	3	1	94.3	5	5	5	4	5	1	3	1
116005	Belle Isle Seawall Rehabilitation	57.1	4	3	2	2	3	1	3	1	57.5	4	3	2	2	3	2	3	1
116006	Belle Isle Intake System Rehabilitation and Improvements	55.8	3	3	3	3	1	1	2	2	55.8	3	3	3	3	1	1	2	2
116007	System Electrical Power Improvements	78.3	4	5	2	4	4	2	1	4	77.1	3	4	4	4	4	4	2	2
122003	Water Works Park to Northeast Transmission Main	78	2	5	3	4	4	1	1	5	76.8	1	5	1	5	1	5	5	5
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	83.5	5	5	4	5	4	5	3	2	77.5	2	5	2	5	4	5	1	1
122005	Schoolcraft Road Water Transmission Main	53.5	1	2	3	4	1	1	1	2	54.7	3	3	1	3	3	1	1	1
122006	Wick Road Water Transmission Main	63.8	4	4	3	1	3	2	1	4	62.9	4	4	1	3	3	3	1	3
122007	Merriman Road Water Transmission Main Loop	76.8	1	5	1	4	3	4	4	4	76.8	1	5	1	4	3	4	4	4
122011	Park-Merriman Road Water Transmission Main	76.9	4	5	1	4	4	3	2	1	44.1	1	3	1	2	1	1	2	1
122013	14 Mile Transmission Main Loop	77.4	3	5	2	3	4	5	1	2	76	1	5	2	3	4	5	1	2
122016	Downriver Transmission Main Loop	79.6	3	5	3	3	4	5	2	3	76	1	5	2	3	4	5	1	2
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station	51.9	1	1	3	2	1	2	2	1	81.2	5	4	4	4	4	4	4	5
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilita- tion	37.8	2	1	1	1	2	4	2	1	85	5	5	4	4	4	5	5	4
122019	Jefferson Main Replacement Project	36.2	1	1	2	1	1	1	2	2	37.2	1	1	2	1	1	2	3	2
132007	Energy Management: Freeze Protection Pump Installation at Imlay Pump Station	35.1	1	1	1	3	1	1	3	3	35.1	1	1	1	3	1	1	3	3
132010	West Service Center Pumping Station - Reservoir, Reservoir Pumping, and Division Valve Upgrades	64.4	3	4	2	4	3	2	1	5	62.6	3	4	1	4	1	5	1	5
132012	Ypsilanti Booster Pumping Station Improvements	61.4	4	4	1	3	1	4	2	2	47.6	3	3	1	3	1	3	2	2
132014	Adams Road Pumping Station Improvements	97.8	5	5	4	5	5	4	4	5	97.8	5	5	4	5	5	4	4	5
132015	Newburgh Road Booster Pumping Station Improvements	79.2	5	5	2	5	2	3	3	4	58.9	4	3	2	3	3	3	1	4
132016	North Service Center Pumping Station Improvements	98.1	5	5	5	4	5	5	3	5	98.7	5	5	5	4	5	5	4	5

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
132018	Schoolcraft Pumping Station Improvements	56.9	3	3	1	4	3	2	2	2	58.9	4	3	2	3	3	3	1	4
132019	Wick Road Pumping Station Improvements	67.2	5	4	2	4	3	3	4	3	67.2	5	4	2	4	3	3	4	3
132020	Franklin Pumping Station Improvements	78.4	4	5	3	4	2	3	3	3	77.7	4	5	2	3	3	3	2	4
132021	Imlay Pumping Station Improvements	65.3	4	4	1	4	3	3	3	4	59.4	4	3	2	3	3	4	1	4
132022	Joy Road Pumping Station Improvements	63.6	4	4	1	3	3	2	3	3	58.9	4	3	2	3	3	3	1	4
170302	SW SCADA System Upgrade	67.4	4	4	2	4	3	4	4	4	67.4	4	4	2	4	3	4	4	4
170303	Power Monitoring Installation for Water Treatment Plants	58.6	2	3	3	3	1	4	3	5	58.6	2	3	3	3	1	4	3	5
170304	WWP Scada Infrastructure Upgrade	59.5	3	3	3	3	3	3	3	2	59.5	3	3	3	3	3	3	3	2
170305	WWP SCADA Network Upgrade	60	3	3	3	3	3	3	3	3	65	3	4	3	3	2	3	3	4
170306	SPW SCADA PLC Network Upgrade	79.6	5	4	4	4	4	3	3	4	78.4	4	4	4	4	4	3	3	3
170307	NE SCADA Network Upgrade	67	5	4	3	3	3	3	3	3	59.6	4	3	3	3	2	3	3	3
170502	Transmission System Valve Rehabilitation and Replacement Pro- gram	25.4	2	1	1	1	1	1	1	1	25.4	2	1	1	1	1	1	1	1
170503	Transmission System Valve Replacement	44.5	2	1	2	4	1	1	1	2	44.5	2	1	2	4	1	1	1	2
170504	Transmission Mains Valves and Urgent	35.1	1	2	1	2	1	4	3	1	34.3	2	2	1	2	1	3	3	2
170601	Linear System Integrity Program	93.3	4	5	1	4	5	5	5	3	76.8	4	4	1	4	4	4	4	4
170801	Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, Springwells Water Treatment Plant, And Southwest Water Treatment Plant	94	4	5	2	5	5	4	4	3	94	4	5	2	5	5	4	4	3
170802	Reservoir Inspection, Design, and Construction Management Ser- vices Phase II	93.2	5	3	5	2	4	5	5	1	74.2	4	3	4	2	3	3	3	1
170803	Reservoir Inspection, Design, and Construction Management Ser- vices Phase III	93.2	5	3	5	2	4	5	5	1	90.3	4	3	5	2	3	4	4	1
170901	Suburban Water Meter Pit Rehabilitation and Meter Replacement	48.7	4	1	2	2	1	4	1	1	48.7	4	1	2	2	1	4	1	1
170902	Brownstown Meter Pit	63.8	2	4	2	4	2	3	3	4	63.8	2	4	2	4	2	3	3	4
170904	Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II	95.7	5	4	3	4	5	5	4	5	95.7	5	4	3	4	5	5	4	5
171502	Lake Huron and Southwest Roof Replacement	60.2	3	4	1	2	3	1	2	1	61.3	3	4	2	2	3	1	2	1

 STOT 4. Adams Rad Dengras Station Norosements 11002 5. HINPER Placing North Marcelle Mandelling 11002 5. HINPER Placement Norosements 11002 5. HINPER Norosement Norosements 11002 5. HINPER Norosements 11003 5. HINPER NOROSEMENT Norosements 11003 5. HINPER Norosements 11003 5. HINPER NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSE 5. HINPER NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSEMENT NOROSE			I	
Header Galleries and Washwater Bu Header Galleries and Washwater Bu WTP Building Ventilation Improver 012 - LHWTP-Flocculation Improver wells Water Treatment Plant, Low-Lit outhwest Water Treatment Plant Ch voir Inspection, Design, and Constru Synayer Is water Treatment Plant Ch voir Inspection, Design, and Constru Synayer Is Bewick Water Treatment Plant and, Hurlbut, Bewick Water Treatment Plant end, Hurlbut, Bewick Water Treatment Plant theast Water Treatment Plant, Plant end, Hurlbut, Bewick Water Treatment Plant theast Water Treatment Plant, Relocation theast Water Treatment Plant, Plant end, Hurlbut, Bewick Water Transmission Main theast Water Treatment Plant, Relocation water Treatment Plant, Relocation threats Water Treatment Plant, Raw Sy work Park Koad Pumping Station Improver in 1060 - Linear System Integrity Pro- lis Water Treatment Plant, Relocation water Treatment Plant, Plant, Plant 110008 - SWP Reservoir Replace thron Water Treatment Plant, Relocation in Road Water Treatment Plant, Plant 110008 - SWP Reservoir Replace thron Water Treatment Plant, Plant Si ick Road Pumping Station Improver pringwells Water Treatment Plant, Yard Plant, 170307 - NE SCADA Network Up in 170307 - NE SCADA Network Up in 20 end Pumping Station Improver in write Center Plant, Plant, 170307 - NE SCADA Network Up is the Works Park High Lift Pumping S in Mater Treatment Plant, Low- and itter Works Park Neter Treatment Plant, Architectur is booster Pumping Station Improver is Water Treatment Plant, Architectur is booster Pumping Station Improver is Water Treatment Plant, Architectur is booster Pumping Station Improver is Water Treatment Plant, Architectur is booster Pumping Station Improver is booster Pumping Station Improver is booster Pumping Station Improver is booster				
⁵ WTP Building Ventilation Improver 012 - LHWTP-Flocculation Improver wells Water Treatment Plant, Low-Lij uuthwest Water Treatment Plant Ch voir Inspection, Design, and Constru s Water Treatment Plant Flocculator Springwells Water Treatment Plant and, Hurbut, Bewick Water Transmi theast Water Treatment Plant, Plou Works Park Water Treatment Plant, Low-Lift, Pu teleNevada Transmission Main Rehal on Water Treatment Plant, Low-Lift, Pu teleNevada Transmission Main Rehal on Water Treatment Plant, Low-Lift, 111010 - Filtration Improver water Treatment Plant, Raw S voir Inspection, Design, and Constru Water Treatment Plant, Raw S voir Inspection Main Relocation Mater Treatment Plant, Raw S voir Inspection Design, and Constru Water Treatment Plant, Raw S voir Inspection Design, and Constru Water Treatment Plant, Raw S voir Inspection Design, and Constru Water Treatment Plant, Raw S voir Inspection Improver Pluron Water Treatment Plant, Raw S voir Inspection Design, and Constru Water Treatment Plant, Raw S voir Inspection Improver Pluron Water Treatment Plant, Raw S voir Inspection Improver Pluron Water Treatment Plant, Archite ils Water Treatment Plant, Yard Pipiny vice Center Pumping Station Improver Verkes Park Kligh Lift Pumping S thoolcraft Road Water Treatment Plant, Low- and 111011 - Lake Huron WTP Pliot water Treatment Plant, Low- and 111011 - Lake Huron Water Treatment Plant, Archite- it Booster Pumping Station Improver Water Treatment Plant, Low- and 111011 - Lake Huron Water Treatment Plant, Archite- Water Treatment Plant, Stetic/Clil Plant Water Treatment Plant, Stetic/Clil Plant Water Treatment Plant, Stetic/Clil Plant Water Treatment Plant, Stetic/Clil Plant Water Treatment Plant, Plant Water Treatment Plant, Stetic Plant Plant Water Treatm		I	T	l
012 - LHWTP-Flocculation Improver wells Water Treatment Plant, Low-Li wells Water Treatment Plant, Low-Li uthwest Water Treatment Plant and, Hurlbut, Bewick Water Treatment Plant and, Hurlbut, Bewick Water Treatment Plant and, Hurlbut, Bewick Water Treatment Plant theast Water Treatment Plant High-Lift Pur theast Water Treatment Plant High-Lift Pur lefNevada Transmission Main Rehal con Water Treatment Plant High-Lift Pur theast Water Treatment Plant, Low-Lift, Works Park Water Treatment Plant, Low-Lift, Morks Park Water Treatment Plant, Low-Lift, Norks Park Water Treatment Plant, Low-Lift, 111010 - Filtration Improver Water Treatment Plant, Administi theast Water Treatment Plant, Raw S voir Inspection, Design, and Constru- wells Water Treatment Plant, Raw S Water Treatment Plant, Raw S voir Inspection, Design, and Constru- wells Water Treatment Plant, Raw S voir Inspection, Design, and Constru- system Electrical Power Improver the Plant S inks Park b Nottheast Transmission Main 11006 - Jownriver Transmission Main 11006 - Jownriver Transmission Main 2006 - Wick Road Water Transmission Main 110016 - Downriver Transmission Main 110016 - Lownriver Treatment Plant, Raw S wells Water Treatment Plant, Administ 110000 - Linear System Improver 110000 - Linear System Rehabilitetion iter Works Park High Lift Pumping S thoolcraft Road Water Treatment Plant, Low- and 111011 - Lake Huron WTP Pliot ther Works Park SteleCrvil Improver it Booster Purmping Station Improver 110000 - Belle Isle Isle Isle Isle Isle Intake System Rehabilitetion ishoolcraft Road Water Treatment Plant, Low- and 111011 - Lake Huron WTP Pliot tron Water Treatment Plant, Archite- tet Works Park SteleCrvil Improver 110000 - Belle Isle Isle Vorter Preatment Plant, Archite isle Soster Purmping Station Improver 110000 - Jefferson Main Replacement Plant Water Treatment Plant Archite- tron Water Treatme	l	I	I	Ì.
wells Water Treatment Plant, Low-Li wells Water Treatment Plant Ch voir Inspection, Design, and Constru- voir Inspection, Design, and Constru- s Water Treatment Plant Flocculator Springwells Water Treatment Plant theast Water Treatment Plant Flocculator Springwells Water Treatment Plant Flocculator Mater Treatment Plant High-Lift Pur erNevada Transmission Main Rehal con Water Treatment Plant High-Lift Pur erNevada Transmission Main Rehal con Water Treatment Plant, Low-Lift, Works Park Water Treatment Plant, Low-Lift, Morks Park Water Treatment Plant Flocco Water Treatment Plant, Low-Lift, Norks Park Water Treatment Plant, Low-Lift, D6 - SPW SCADA PLC Network Up Water Treatment Plant, Raw S Work Park Water Treatment Plant, Station Main con Water Treatment Plant, Administ 22013 - 14 Mile Transmission Main Plant (1006) - Linear System Integrity Pro Mater Treatment Plant, Replace Lake Huron Water Treatment Plant, Replace I 13008 - SWP Reservoir Replace Lake Huron Water Treatment Plant, Administ 2006 - Wick Road Water Transmission Main Of 6 - Downriver Transmission Main Mater Treatment Plant, Administ 2007 - Linear System Integrity Pro Pringwells Water Treatment Plant, Administ 170307 - Linear System Integrity Pro Juster Treatment Plant, Administ 2008 - Wick Road Pumping Station Improver Voir Inspection, Design, and Constru- Water Treatment Plant, Yard Pipin, 170307 - Net Scada Purping Station Improver Joy Road Pumping Station Improver Vice Center Pumping Station Improver Vice Center Treatment Plant, Low- dueter Treatment Plant, Archite- elle Isle Intake System Rehabilitation Auster Treatment Plant, Archite- i Blooster Pumping Station Improver Vater Treatment Plant, Archite- dueter Treatment Plant, Archite-	l	L	I	Ĺ
 outhwest Water Treatment Plant Ch outhwest Water Treatment Plant Flocculator Water Treatment Plant Flocculator Springwells Water Treatment Plant Flocculator Water Treatment Plant, Hurbut, Bewick Water Transmission Main theast Water Treatment Plant, Low-Lift, Pur Works Park Water Treatment Plant, Low-Lift, Pur Works Park Water Treatment Plant, Low-Lift, Pur Franklin Pumping Station Improver Works Park Nater Treatment Plant, Raw S Works Park Noter Treatment Plant, Raw S Works Park Nater Treatment Plant, Raw S Works Park Nater Treatment Plant, Raw S Works Park Nater Treatment Plant, Raw S Water Treatment Plant, Administing 170305 - WWP SCADA Network Upg Mater Treatment Plant, Administing 170305 - WWP SCADA Network Upg Stek Road Pumping Station Improver Noter Treatment Plant, Seconstruker Bu Water Treatment Plant, Raw S Works Park Nater Treatment Plant, Administing 170305 - WWP SCADA Network Upg Nater Treatment Plant, Administion 170305 - WWP SCADA Network Upg 170307 - Linear System Improver 170305 - WWP SCADA Network Upg 170305 - WWP SCADA Network Park 170305 - WWP		L	l	Ŀ
voir inspection, Design, and Constru- voir inspection, Lesign, and Constru- si Water Treatment Plant Flocculator Springwells Water Treatment Plant and, Hurlbut, Bewick Water Transmi theast Water Treatment Plant Floccu Water Treatment Plant, Low-Lift, Du- Lift, Pur leiNevada Transmission Main Rehal con Water Treatment Plant, Low-Lift, 06 - SPW SCADA PLC Network Up Water Transmission Main Relocation 111010 - Filtration Improver Water Treatment Plant, Low-Lift, 06 - SPW SCADA PLC Network Up Water Transmission Main Relocation 111010 - Filtration Improver Water Treatment Plant, Raw Si work Park kon Network Up Water Treatment Plant, Administ 170305 - WWP SCADA Network Up Mater Treatment Plant, Administ 170305 - WWP SCADA Network Up Water Treatment Plant, Yaw Si Water Treatment Plant, Yard Plpin, 170307 - NE SCADA Network Up Water Treatment Plant, Yard Plpin, 170307 - NE SCADA Network Up Water Treatment Plant, Yard Plpin, 170307 - Network Park High Lift Pumping S thoolcraft Pumping Station Improver Vorke Park High Lift Pumping Station Improver Vater Treatment Plant, Low- and 116005 - Belle Isle Seawall Rehabilitatio Adater Treatment Plant, Low- and 111011 - Lake Huron Water Treatment Plant, Archite elle Isle Intake System Rehabilitatio Adater Treatment Plant, Low- and 111011 - Lake Huron Water Treatment Plant, Archite elle Isle Intake System Rehabilitatio Adater Treatment Plant, Low- and 111011 - Lake Huron Water Treatment Plant, Archite elle Isle Intake System Rehabilitation Adater Treatment Plant, Archite iB Isle Intake System Rehabilitation Adater Treatment Plant		Γ	Γ	Ľ
Springwells Water Treatment Plant and, Hurfbut, Bewick Water Treatment Plant theast Water Treatment Plant, Low-Lift, Pur Water Treatment Plant, Low-Lift, Pur e/Nevada Transmission Main Rehal con Water Treatment Plant, Low-Lift, Pur e/Nevada Transmission Main Rehal con Water Treatment Plant, Low-Lift, Pur e/Nevada Transmission Main Rehal con Water Treatment Plant, Low-Lift, Pur Plant, Plant, Low-Lift, Pur Mater Transmission Main Rehal con Water Transmission Main Rehal con Water Transmission Main Rehal con Vater Transmission Main 111010 - Filtration Improver pringwells Water Treatment Plant, Administ 113008 - SWP Reservoir Replace Huron Water Treatment Plant, Raw S voir Inspection, Design, and Constru- wells Water Treatment Plant, Raw S Voir Inspection, Design, and Constru- uron Water Treatment Plant, Raw S voir Inspection, Design, and Constru- wells Water Treatment Plant, Raw S fick Road Vater Transmission Main 016 - Downriver Transmission Main 170305 - WWP SCADA Network Upg Stetion Improver 130005 - WWP SCADA Network Upg Station Improver Vice Center Pumping Station Improver Vice Center Plant, Vard Pipin, 170307 - NE SCADA Network Upg Station Improver Vice Center Pumping Station Improver Vice Center Pumping Station Improver Vice Center Pumping Station Improver Vice Center Pumping Station Improver Vice Center Plant, Vard Pipin, et a Works Park High Lift Pumping S Vibolcraft Road Water Treatment Plant, Low- and 111011 - Lake Huron WTP Pliot Vicater Treatment Plant, Low- and Vater Treatment Plant, Archite- Vertimen Road Water Treatment Plant Archite- Vertim				ĥ
 and, Hurlbut, Bewick Water Transmi and, Hurlbut, Bewick Water Transmi theast Water Treatment Plant High-Lift Pur le/Nevada Transmission Main Rehal 06 - SPW SCADA PLC Network Upg Works Park Water Treatment Plant, Low-Lift, 06 - SPW SCADA PLC Network Upg Water Transmission Main Relocation 11010 - Filtration Improver pringwells Water Treatment Plant, Administing 13008 - SWP Reservoir Replace Huron Water Treatment Plant, Administing 13008 - SWP Reservoir Replace 113008 - SWP Reservoir Replace Buks Park Sedimentation Basins Stru- uron Water Treatment Plant, Administing 113008 - SWP Reservoir Replace Buron Water Treatment Plant, Administion 113008 - SWP Reservoir Replace Buron Water Treatment Plant, Administion 113008 - SWP Reservoir Replace Ithron and Southwest Roof Replace Ithron and Southwest Roof Replace Lake Huron Water Treatment Plant, Yard Pipin, 170307 - NE SCADA Network Upg Station Improver Voice Center Pumping Station Improver Izolog Road Water Treatment Plant, Vard Pipin, Ithron and Southwest Roof Replace Lake Huron Water Treatment Plant, Vard Pipin, Ithron and Southwest Roof Replace Lake Huron Water Treatment Plant, Vard Pipin, Ithron and Suthwest Roof Replace Ithron Road Water Treatment Plant, Vard Pipin, Ithron Road Water Treatment Plant, Low- and Ithron Road Water Treatment Plant, Low- and Ithron Road Water Treatment Plant, Low- Swater Treatment Plant, Vard Pipin, Ithe Norks Park Site/Civil Improver Ithron Road Water Treatment Plant, Low- Ither Works Park Site/Civil Improver Ithron Road Water Treatment Plant, Low- Ither Works Park Site/Civil Improver Ithron Road Water Treatment Plant, Archite- Ithron Water Treatment Plant, Plant Plant, Plan	_			ĥ
 Mater Treatment Plant Flour Flour And the Treatment Plant Flour Mater Treatment Plant High-Lift Fle/Nevada Transmission Main Relion Water Treatment Plant, Low-L 66 - SPW SCADA PLC Network Low-L 66 - SPW SCADA PLC Network Low-L 70 Water Transmission Main Relocal 111010 - Filtration Improvors Park to Northeast Transmission Mater Transmission Mater Treatment Plant, Admin Nets Park to Northeast Transmission Main Relocal 113008 - SWP SCADA Network Low-L 70305 - WWP SCADA Network Law-U 70305 - WWP SCADA Network Law-U 70305 - WWP SCADA Network Leatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant. Raw voir Inspection, Design, and Conswells Water Treatment Plant. Raw voir Inspection, Design, and Conswells Water Treatment Plant. Raw voir Inspection, Design, and Conswells Water Treatment Plant. Raw voir Inspection, Design, and Conswells Water Treatment Plant. Plant. Raw voir Inspection, Design, and Conswells Water Treatment Plant. Plant. Plant. 170305 - WWP SCADA Network Lake Huron Water Treatment Plant. Plant. Plant. Plant. 170307 - NE SCADA Network Lake Huron Water Treatment Plant. Plant. Plant. Plant. Plant. 170307 - NE SCADA Network Lake Huron Water Treatment Plant. Jouron Water Treatment Plant. Plant. Acthiter Plant. Plant. Plant. Plant. Acthiter Plant. Plant. Plant. Plant. Jouron Water Treatment Plant. Lake Huron Water Treatment Plant. Low-at 111011 - Lake Huron Water Treatment Plant. Low-at 111011 - Lake Huron Water Treatment Plant. Low-at 111011 - Lake Huron Water Treatment Plant. Low-at It Booster Pumping Station Improviet Water Treatment Plant. Plant.	_			
Water Treatment Plant High-Lift F le/Nevada Transmission Main Rel Icon Water Treatment Plant, Low-L 06 - SPW SCADA PLC Network L Works Park Water Treatment Plant Water Transmission Main Relocal 111010 - Fittration Improv pringwells Water Transmission Ma 170601 - Linear System Integrity F Mater Treatment Plant, Admin pringwells Water Treatment Plant and Road Water Treatment Plant 113008 - SWP Reservoir Repla 113008 - SWP Reservoir Repla rice Center Pumping Station Improv voir Inspection, Design, and Cons wells Water Treatment Plant, Admin (22013 - 14 Mile Transmission Ma 016 - Downriver Transmission Ma 016 - Downriver Treatment Plant, Admin (22013 - 14 Mile Transmission Ma 016 - Wick Road Vater Treatment Plant - 113008 - SWP Reservoir Repla rice Road Pumping Station Improv voir Inspection, Design, and Cons wells Water Treatment Plant, Yauw 1000 Water Treatment Plant, Yand Pli ter Works Park High Lift Pumping thoolcraft Pumping Station Improv verburgh Road Pumping Station Improv verburgh Road Pumping Station Improv verburgh Road Pumping Station Improv verbolocraft Road Water Treatment Plant, Yard Pli ter Works Park High Lift Pumping the Norks Park High Lift Pumping the Norks Park Kite/Civil Improv st Vater Treatment Plant, Arch delle Isle Isle Seawall Rehal elle Isle Isle Station Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pli uron Water Treatment Plant, Arch if Booster Pumping Station Improv detriman Road Water Treatment Plant, Arch if Booster Pumping Station Improv Merriman Road Water Treatment Plant, Arch if Booster Pumping Station Improv dater Treatment Plant, Plant, Arch if Booster Pumping Station Improv dater Treatment Plant Plant, Arch if Booster Pumping Station Improv dater Treatment Plant Plant Plant of Water Treatment Plant				
 Ie/Nevada Transmission Main Rel Ie/Nevada Transmission Main Rel O6 - SPW SCADA PLC Network Low-L Works Park Water Treatment Plant, Low-L Franklin Pumping Station Improv Water Transmission Main Relocat 111010 - Filtration Improv System Electrical Power Improv Poingwells Water Treatment Plant Indot Vater Treatment Plant Admin I22013 - 14 Mile Transmission Ma I70601 - Linear System Integrity F III Water Treatment Plant, Admin I22013 - 14 Mile Transmission Ma I70601 - Linear System Integrity F III Water Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Yaco Pla I13008 - SWP Reservoir Repla Irooloraft Pumping Station Improv Irooloraft Pumping Station Improv Joy Road Buonping Station Improv Joy Road Bumping Station Improv Joy Road Bumping Station Improv Swater Treatment Plant, Yard Pli Iter Works Park Huron Water Treatment Plant, Yard Pli Iter Works Park Huron Water Treatment Plant, Yard Pli Iter Works Park Huron Water Treatment Plant, Admining Station Improv Swater Treatment Plant, Yard Pli Iter Works Park Huron Water Treatment Plant, Admining Iter Works Park Huron Water Treatment Plant, Admining Iter Works Park Huron Water Treatment Plant, Admining Iter Works Park Stle/Civil Improv Water Treatment Plant, Low- ar Iter Works Park Stle/Civil Improvist Water Treatment Plant, Low- ar Iter Works Park Stle/Civil Improvist Water Treatment Plant, Low- ar Itotal - Lake Huron Water Treatment Plant, Low- ar Jeffer	_			
 In Water Treatment Plant, Low-Low-Look Works Park Water Treatment Plant, Low-Works Park Water Treatment Plant, Works Park Water Treatment Plant, Works Park to Northeast Treatment Plant arks Park to Northeast Treatment Plant in Plant Bills Water Treatment Plant Adminion Road Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Plant, Plant, Plant, Plant, Plant, Plant, Plant, Plant, Raw Vorks Park High Lift Pumping Station Improvide Raw Water Treatment Plant, Acting Raw Plant Road Water Treatment Plant, Acthitect Plant Road Water Treatment Plant, Acthitect Itele Socker Plant Raw	_			
 Norks Park Water Treatment Flauturent Flauturent Plae Works Park Water Treatment Plae Franklin Pumping Station Improv Water Transmission Main Relocat Franklin Pumping Station Improv System Electrical Power Improv System Electrical Power Improv System Electrical Power Improv System Electrical Power Improv Franklin Pumping Station Improv System Electrical Power Improv System Plant, Admin (22013 - 14 Mile Transmission Maer Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Yaon Maer Transmission Maer Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Yaon Maer Transmission Maer Treatment Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Yaon Maer Transmission Maer Treatment Plant, Plant, Raw Voir Inspection, Design, and Cons Water Treatment Plant, Yaon Improv Jool So W Reservoir Replation Improv Nater Treatment Plant, Yaon Plant, Plant, Plant, Plant, Plant, Plant, Plant, Plant, Plant, Raw Huron Water Treatment Plant, Low- at 1110015 - Belle Isle Intake System Rehabilita Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at the Works Park Site/Civil Improv Mater Treatment Plant, Replacement of weal Water Treatment Plant, Architection Jefferson Main Replaced Mater Transmissi Jefferson Main Replaced Mater Transmissi Jefferson Main Replaced Mater Transmiss		Π		
 Job - SPW SCADA PLC Network U06 - SPW SCADA PLC Network Laworks Park Water Treatment Plant Varter Transmission Main Relocal 11010 - Filtration Improvors Park to Northeast Treatment Plant Areas Park to Northeast Transmission Main Relocal 110601 - Linear System Integrity Filts Water Treatment Plant, Admin Nater Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Admin 122013 - 14 Mile Transmission Main Relocal Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Plant 1958 (K Road Pumping Station Improvice Center Pumping Station Improvuled Context Plant Nater Treatment Plant, Yard Plant 170307 - NE SCADA Network Lake Huron Water Treatment Plant, Yard Plant 170307 - NE SCADA Network Lake Huron Water Treatment Plant, Yard Plant 170307 - NE SCADA Network Lake Huron Water Treatment Plant, Yard Plant 170307 - NE SCADA Network Lake Huron Water Treatment Plant, Yard Plant 170005 - Belle Isle Isle Intake System Rehabilitat ther Works Park High Lift Pumping Station Improvis Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 11000 Station Improvise Water Treatment Plant, Plant Plant, Plant Plant Nater Treatment Pla				
 Works Park Water Treatment Pla Works Park Water Transmission Main Relocal Franklin Pumping Station Improvoringwells Water Treatment Plant System Electrical Power Improvorities Water Treatment Plant Adminission Main Road Water Transmission Main Mater Treatment Plant, Admini Mater Treatment Plant, Admini Mater Treatment Plant, Admini Mater Treatment Plant, Raw Voir Inspection, Design, and Consisting Water Treatment Plant, Raw Voir Inspection, Design, and Consisting Water Treatment Plant, Raw Voir Inspection, Design, and Consisting Water Treatment Plant, Raw Voir Inspection, Design, and Consisting Water Treatment Plant, Yau Unon Water Treatment Plant, Admini Mater Treatment Plant, Yard Pji Mater Treatment Plant, Vard Pji Mater Treatment Plant, Lift Pumping Mater Treatment Plant, Low- ar Mater Treatment Plant, Low- ar Mater Works Park Aljeh Lift, Pumping Mater Works Park Site/Civil Improvist Water Treatment Plant, Architect Mater Treatment Plant Architect Management: Freeze Protection 	_			
 Franklin Pumping Station Improv Water Transmission Main Reloca 111010 - Filtration Improv System Electrical Power Improv pringwells Water Treatment Plant pringwells Water Treatment Plant pringwells Water Transmission Main IT0601 - Linear System Integrity F Ills Water Transmission Main IZ2013 - 14 Mile Transmission Main I22013 - 14 Mile Transmission Main I13008 - SWP Reservoir Replant - I 113008 - SWP Reservoir Replant - I I13005 - WWP SCADA Network L Mater Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Yaw Voir Inspection, Design, and Conswells Water Treatment Plant, Yaw Voir Inspection, Design, and Conswells Water Treatment Plant, Yard Pj5 Mick Road Pumping Station Improvolory Road Pumping Station Improvolor Road Road Water Treatment Plant, Yard Pj5 Mater Works Park High Lift Pumping Huron Water Treatment Plant, Arching ter Works Park Sile/Civil Improvolorat Road Water Treatment Plant, Archinger Mater Treatment Plant, Archinguron Water Treatment Plant Road Water Treatment Plant Plant, Archinguron Water Treatment Plant Road		L	ľ	
Water Transmission Main Reloca 111010 - Filtration Improv - System Electrical Power Improv pringwells Water Treatment Plant ir70601 - Linear System Integrity F dils Water Treatment Plant, Admini (22013 - 14 Mile Transmission Ma 016 - Downriver Transmission Ma 016 - Downriver Transmission Ma 113008 - SWP Reservoir Repla rks Park Sedimentation Basins St uron Water Treatment Plant - N 113008 - SWP Reservoir Repla rks Park Sedimentation Improv Voir Inspection, Design, and Cons wells Water Treatment Plant, Yaurd Plant 170307 - NE SCADA Network L 170307 - NE SCADA Network L 11000 - Selle Isle Isle Station Improv st Water Treatment Plant, Yard Pji dater Works Park Site/Civil Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pl uron Water Treatment Plant, Arch if Booster Pumping Station Improv Merriman Road Water Transmissi uron Water Treatment Plant, Arch if Booster Pumping Station Improv Werriman Road Water Treatment Plant, Arch if Booster Pumping Station Improv Werriman Road Water Treatment Plant, Arch uron Water Treatment Plant, Arch if 900518 Water Treatment Plant, Plant		L	ľ	
111010 - Filtration Improvor system Electrical Power Improvor pringwells Water Treatment Plant orks Park to Northeast Transmission Ma iT/0601 - Linear System Integrity F ills Water Treatment Plant, Admin iZ2013 - 14 Mile Transmission Ma integrity F ills Water Treatment Plant, Admin iZ2013 - 14 Mile Transmission Ma integrity F atron Water Treatment Plant - F 113008 - SWP Reservoir Repla integrity F attron Water Treatment Plant - Raw voir Inspection, Design, and Cons wells Water Treatment Plant, Yate Huron and Southwest Roof Repla Lake Huron Water Treatment Plant, Plant 170305 - WWP SCADA Network L 170305 - WWP SCADA Network L 170305 - WWP SCADA Network L 21 - Imlay Pumping Station Improv Scoolcraft Pumping Station Improv verter Treatment Plant, Yard Pji ter Works Park High Lift Pumping ther Works Park High Lift Pumping ther Works Park Station Improv verter Treatment Plant, Yard Pji 116005 - Belle Isle Seaewall Rehal elle Isle Intake System Rehabilital schoolcraft Road Water Transmissi dater Works Park Stele/Civil Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Plant, Arch uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Plant, Arch uron Water Treatment Plant, Cow- ar 111011 - Lake Huron WTP Plant, Cow- uron Water Treatment Plant, Cow- uron Water Treatment Plant, Plant, Cow- uron Water Treatment Plant, Plant Plant, O Werriman Road Water Treatment Plant Plant Plant ut Water Treatment Plant Plant Plant Plant ut Water Treatment Plant Plant Plant Plant ut Plant Road Water Treatment Plant Plant Plant ut Plant Road Plant Plant Plant Plant Plant ut Plant Plant Plant Plant Plant Plant Plant Plant P		I	I	
 System Electrical Power Improver indexels Water Treatment Plant pringwells Water Treatment Plant anan Road Water Treatment Plant, Adminican Road Water Treatment Plant, Admini (22013 - 14 Mile Transmission Mater Treatment Plant - 113008 - SWP Reservoir Replarks Park Sedimentation Basins Station Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Yaawater Treatment Plant, Yaard Pli, Water Treatment Plant, Yaard Pli, 170305 - WWP SCADA Network Lands Voir Inspection, Design, and Conswells Water Treatment Plant, Yaard Pli, Water Treatment Plant, Yaard Pli, Voir Inspection, Design, and Conswells Water Treatment Plant, Yaard Pli, Voir Inspection, Design, and Conswells Water Treatment Plant, Yaard Pli, 170305 - WWP SCADA Network Lands Puron Mater Treatment Plant, Yaard Pli, Nater Treatment Plant, Yaard Pli, Mater Treatment Plant, Yaard Pli, Itten Works Park High Lift Pumping 116005 - Belle Isle Seawall Rehal elle Isle Intake System Rehabilitation of Ader Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 111011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Low- ar 110011 - Lake Huron Water Treatment Plant, Cow Merriman Road Water Treatment Plant Plant, Low- ar 110011 - Jafferson Main Replacement ngwells Water Treatment Plant Plant Plant Plant Plant Road Wertion Mater Treatment Plant Plant Plant Plant Road Wertion Mater Treatment Plant Plant Plant Plant Road Wertion Mater Treatment Plant Plant Plant Plant Road Wertion Mater	l	I	I	
pringwells Water Treatment Plant brks Park to Northeast Transmission Ma 170601 - Linear System Integrity F IIs Water Treatment Plant, Admin IIs Water Treatment Plant, Admin 122013 - 14 Mile Transmission Ma 016 - Downriver Transmission Ma e Huron Water Treatment Plant - I 113008 - SWP Reservoir Repla rrks Park Sedimentation Basins St uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant, Yard Pla 170305 - WWP SCADA Network L 170305 - Selele Isle Scawall Rehal elle Isle Intake System Plant, Yard Pli ter Works Park High Lift Pumping the Intake System Rehabilitat alle Isle Intake System Rehabilitat alloolcraft Road Water Transmissi Vater Treatment Plant, Low- ar 111011 - Lake Huron WTP Pl uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pl uron Water Treatment Plant, Architecti it Booster Pumping Station Improv Metriman Road Water Treatment Plant, Arch uron Water Treatment Plant, Architecti of Water Treatment Plant Architecti of Water Treatment Plant Architecti of Water Treatment Plant Station Improv Metrima Road Water Treatment Plant Contection gy Management: Freeze Protectio		I		
Area Northeast Transmission Manan Road Water Transmission Ma 170601 - Linear System Integrity F 170601 - Linear System Integrity F 2016 - Downriver Transmission Ma 2016 - Downriver Transmission Ma 2016 - Downriver Transmission Ma 113008 - SWP Reservoir Replarks Park Sedimentation Basins S uron Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Plant 1958 fick Road Pumping Station Improvisor Center Pumping Station Improvisor Center Pumping Station Improvise Nater Treatment Plant, Yard Pig Pumping Station Improvise Nater Treatment Plant, Yard Pig Pumping Station Improvise Nater Treatment Plant, Yard Pig Pumping Station Improvise Nater Treatment Plant, Vard Pig Pumping Station Improvise Nater Treatment Plant, Yard Pig Pumping Station Improvise Nater Treatment Plant, Vard Pig Pumping Station Improvise Nater Treatment Plant, Yard Pig Pumping Station Improvise Nater Treatment Plant, Low- at 17005 - Belle Isle Isle Isle Nater Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Low- at 111011 - Lake Huron Water Treatment Plant, Architectio Water Treatment Plant, Replacement Plant, Stelerson Main Replacement Plant, Replacement Plant, Replacement Plant, Stelerson Main Replacement Plant, Replacement Plant, Freeze Protectio Plant, Replacement Plant, Freeze Protectio	_		1	
nan Road Water Transmission Manin Road Water Transmission Ma IT0601 - Linear System Integrity F III Water Treatment Plant, Admin I22013 - 14 Mile Transmission Ma O16 - Downriver Transmission Ma O16 - Downriver Transmission Ma I13008 - SWP Reservoir Repla rks Park Sedimentation Basins St uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant 1958 Ick Road Pumping Station Improv Voir Inspection, Design, and Cons wells Water Treatment Plant 1958 Ick Road Pumping Station Improv Voir Inspection Mater Treatment Plant 170305 - WWP SCADA Network L 170305 - WWP SCADA Network L 170307 - NE SCADA Network L 110005 - Belle Isle Station Improv Schoolcraft Pumping Station Improv Newburgh Road Booster Pumping ther Works Park High Lift Pumping ther Works Park Site/Civil Improv at Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pil uron Water Treatment Plant, Arch it Booster Pumping Station Improv Merriman Road Water Treatment Plant, Arch it Booster Pumping Station Improv Merriman Road Water Treatment Plant Architectt uron Water Treatment Plant Architectt ungwells Water Treatment Plant Architectt ungwells Water Treatment Plant Architectt ungwells Water Treatment Plant Architectt ungwells Water Treatment Plant Plant Pc ungwells Water Treatment Plant Pc	_			
170601 - Linear System Integrity F IIS Water Treatment Plant, Admini IIS Water Treatment Plant, Admini IIS Water Treatment Plant, Admini IIS 016 - Downriver Transmission Ma 016 - Downriver Transmission Ma 016 - Downriver Transmission Ma II 3008 - SWP Reservoir Repla rks Park Sedimentation Basins Sl uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant, 1958 lick Road Pumping Station Improv Voir Inspection, Design, and Cons wells Water Treatment Plant 1958 lick Road Pumping Station Improv Voir Inspection, Design, and Cons wells Water Treatment Plant, Yard Pij Uron and Southwest Roof Repla Lake Huron water Treatment Plant, Yard Pij Uston and Southwest Roof Repla Lake Huron Water Treatment Plant, Yard Pij ter Works Park High Lift Pumping theolocraft Road Water Transmissi dater Works Park Site/Civil Improv at Water Treatment Plant, Low- ar 110011 - Lake Huron WTP Pli uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pli uron Water Treatment Plant, Low- ar 111011 - Lake Huron Water Transmissi dater Works Park Site/Civil Improv Mater Treatment Plant, Architecti t Water Treatment Plant, Architecti t Water Treatment Plant, Architecti t Water Treatment Plant Architecti t Water Treatment Plant Architecti orgwells Water Treatment Plant Architecti orgwells Water Treatment Plant Architecti orgwells Water Treatment Plant Plan				
 I/10601 - Linear System Integrity FI/20013 - 14 Mile Transmission Mails Water Treatment Plant, Admini (22013 - 14 Mile Transmission Mails Water Treatment Plant, Raw uron Water Treatment Plant, Raw uron Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant, Ray uron Water Treatment Plant - Service Huron Water Treatment Plant - Secola Network Lake Huron Water Treatment Plant, Yard Plick Road Pumping Station Improvice Center Pumping Station Improvise Center Pumping Station Improvise Center Pumping Station Improvise Vater Treatment Plant, Yard Plick Road Pumping Station Improvise Vorks Park High Lift Pumping ther Works Park High Lift Pumping (116005 - Belle Isle Isle Seawall Rehal elle Isle Intake System Rehabilitation Improvist Water Treatment Plant, Yard Plick Poolocraft Road Water Transmissi (Vater Treatment Plant, Low- at 11011 - Lake Huron WTP Pli Uron Water Treatment Plant, Low- at Water Treatment Plant, Low- at Water Treatment Plant, Low- at Unstear Treatment Plant, Low- at Use Norks Park Site/Civil Improvist Water Treatment Plant, Low- at User Works Park Site/Civil Improvist Water Treatment Plant, Low- at User Treatment Plant, Low- at User Works Park Site/Civil Improvist Water Treatment Plant, Low- at User Treatment Plant, Kater Treatment Plant, Architecti Uswells Water Treatment Plant, Architecti Uswells Water Treatment Plant, Architecti Uswells Water Treatment Plant, Low- at Uswells Water Treatment Plant, Architecti Uswells Water Treatment Plant Architect	_			
IIIS Water Treatment Plant, Admin IIIS Water Treatment Plant, Admin I22013 - 14 Mile Transmission Ma e Huron Water Treatment Plant - I 113008 - SWP Reservoir Repla rks Park Sedimentation Basins Si uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant, Raw wolls Water Treatment Plant 1958 Mick Road Pumping Station Improv I70305 - WWP SCADA Network L 06 - Wick Road Water Transmissi Water Treatment Plant - Service I vice Center Pumping Station Improv Joy Road Pumping Station Improv Joy Road Pumping Station Improv advels Water Treatment Plant Adver Treatment Plant - Service I vice Center Pumping Station Improv Joy Road Pumping Station Improv Stoolcraft Road Booster Pumping the Works Park High Lift Pumping the Works Park High Lift Pumping the Norks Park Righ Lift Pumping the Intake System Rehabilitat achoolcraft Road Water Transmissi vater Treatment Plant, Arch actor Works Park Site/Civil Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron Water Transmissi vater Works Park Site/Civil Improv the Intake System Rehabilitat the Norks Park Site/Civil Improv st Water Treatment Plant, Arch uron Water Treatment Plant Architecti t Water Treatment Plant Architecti of 91 - Jefferson Main Replacement ngwells Water Treatment Plant Plant Pcotectio gy Management: Freeze Protectio			I	
(22013 - 14 Mile Transmission Ma 016 - Downriver Transmission Ma e Huron Water Treatment Plant - I 113008 - SWP Reservoir Repla rks Park Sedimentation Basins Sl uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant 1958 (ick Road Pumping Station Improv IT0305 - WWP SCADA Network L 06 - Wick Road Water Transmissi Water Treatment Plant - Service I Water Treatment Plant - Service I Vice Center Pumping Station Improv UD307 - NE SCADA Network L 170307 - NE SCADA Network L 170307 - NE SCADA Network L 170305 - WWP SCADA Network L Water Treatment Plant, Yard Pla Lake Huron Water Treatment Plan 170307 - NE SCADA Network L Water Treatment Plant, Yard Pla Lake Huron Water Treatment Plant (Vice Center Pumping Station Improv Joy Road Pumping Station Improv Joy Road Pumping Station Improv Newburgh Road Booster Pumping the Works Park High Lift Pumping the Norks Park High Lift Pumping the Ilf Lift Pumping the Norks Park Site/Civil Improv st Water Treatment Plant, Low- ar 110101 - Lake Huron WTP Pi uron Water Treatment Plant, Arch uron Water Treatment Plant, Arch i Booster Pumping Station Improv Merriman Road Water Transmissi (Afferson Main Replacement ngwells Water Treatment Plant Architecti t Water Treatment Plant Replacement ngwells Water Treatment Plant Plant Poncy of Management: Freeze Protectio y Management: Freeze Protectio		l	I	
016 - Downriver Transmission Ma e Huron Water Treatment Plant - I 113008 - SWP Reservoir Repla rks Park Sedimentation Basins Si uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant 1958 fick Road Pumping Station Improv 170305 - WWP SCADA Network L 56 - Wick Road Water Transmissi Water Treatment Plant - Service I vice Center Pumping Station Improv Vetter Huron Water Transmissi Water Treatment Plant - Service I 170307 - NE SCADA Network L 170307 - NE SCADA Network L 170307 - NE SCADA Network L 21 - Imlay Pumping Station Improv Vetwburgh Road Booster Pumping the Huron and Southwest Roof Repla 170307 - NE SCADA Network L 1170307 - NE SCADA Network L 21 - Imlay Pumping Station Improv Vetwburgh Road Booster Pumping the Works Park High Lift Pumping the Works Park High Lift Pumping the Ilfe Isle Isle Seawall Rehal elle Isle Intake System Rehabilita the Works Park Site/Civil Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pi 11001 - Lake Huron WTP Pi 1100 Water Treatment Plant, Archi uron Water Treatment Plant Architectu uron Water Treatment Plant Architectu uron Water Treatment Plant Architectu uron Water Treatment Plant Plant Pool uron Water Treatment Plant Plant Plant Pool uron Water Treatment Plant		I	Ī	
 Huron Water Treatment Plant - I 113008 - SWP Reservoir Replarks Park Sedimentation Basins Sluron Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant 1958 Vick Road Pumping Station Improving Ration Improvior Canter Pumping Station Improvior Canter Pumping Station Improvise Eake Huron and Southwest Roof Replated Huron and Southwest Roof Replated to Nater Treatment Plant - Service Introduced Purce Canter Pumping Station Improvise Canter Pumping Station Improvise Canter Pumping Station Improvise Canter Pumping Station Improvise Lake Huron and Southwest Roof Replated to Nater Treatment Plant - Service Introduced Purce Canter Pumping Station Improvise Canter Pumping Station Improvise Water Treatment Plant, Yard Pip Schoolcraft Pumping Station Improvise Water Treatment Plant, Vard Pip Station Improvise Water Treatment Plant, Vard Pip Schoolcraft Road Pumping Station Improvise Water Treatment Plant, Vard Pip Schoolcraft Road Water Transmissi dater Works Park High Lift Pumping Iter Works Park Iter Treatment Plant, Vard Pip Iter Works Park Site/Civil Improviae Intololocraft Road Water Treatment Plant, Architectt Iter Works Park Site/Civil Improviae Intol Intol - Lake Huron Water Treatment Plant, Architectt Iter Works Park Plant Replacement Plant, Architectt Iter Works Park Plant Replacement Pla		I	l	
113008 - SWP Reservoir Repla rks Park Sedimentation Basins Sl uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant 1958 fick Road Pumping Station Improv 170305 - WWP SCADA Network L 170305 - WWP SCADA Network L Huron and Southwest Roof Repla Huron and Southwest Roof Repla Lake Huron Water Treatment Plant 170307 - NE SCADA Network L 170307 - Settion Improv Station Improv Joy Road Pumping Station Improv Swater Treatment Plant, Yard Pij ther Works Park High Lift Pumping ther Works Park High Lift Pumping ther Works Park High Lift Pumping ther Works Park Kite/Civil Improv st Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pil uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pil uron Water Treatment Plant, Archi ti Booster Pumping Station Improv Merriman Road Water Transmissi vater Treatment Plant, Architectt 19 - Jefferson Main Replacement ngwells Water Treatment Plant Architectti ogy Management: Freeze Protectio gy Management: Freeze Protectio				
 writes Park Sedimentation Basins Sluron Water Treatment Plant, Raw voir Inspection, Design, and Conswells Water Treatment Plant 1958 write Road Pumping Station Improvior In0305 - WWP SCADA Network L b6 - Wick Road Water Transmissi Water Treatment Plant - Service I Huron and Southwest Roof Replated Huron Water Treatment Plant - Service Center Pumping Station Improvice Center Pumping Station Improvis Vater Treatment Plant, Yard Plant 170307 - NE SCADA Network L 170307 - NE SCADA Network L 116005 - Belle Isle Intake System Rehabilitated I 116005 - Belle Isle Seawall Rehabilitated I 116005 - Belle Isle Seawall Rehabilitater Works Park Site/Civil Improvious Vater Treatment Plant, Vard Pipurov Vater Treatment Plant, Low - ar 111011 - Lake Huron WTP Plant, Architection Improvious Vater Treatment Plant, Architection Vater Treatment Plant Architection Vater Treatment Plant Architection Vater Treatment Plant Architection Vater Treatment Plant Architection Nater Treatment Plant Architection Nater Treatment Plant Replacement Plant Plant Plant Plant Point Plant Plan	_			
uron Water Treatment Plant, Raw voir Inspection, Design, and Cons wells Water Treatment Plant 1958 wells Water Treatment Plant 1958 iick Road Pumping Station Improv 170305 - Wick Road Water Transmissi Water Treatment Plant - Service I with Road Water Transmissi Water Treatment Plant - Service I vice Center Pumping Station Improv Lake Huron Water Treatment Plan 170307 - NE SCADA Network L 170307 - Service I kuron and Southwest Roof Repla Lake Huron Water Treatment Plant, Yard Pij the Works Park High Lift Pumping the Works Park High Lift Pumping the Works Park High Lift Pumping the Works Park Site/Civil Improv vater Treatment Plant, Low- ar 111011 - Lake Huron WTP Pi uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pi uron Water Treatment Plant, Archi ti Booster Pumping Station Improv Merriman Road Water Transmissi t Water Treatment Plant, Archi towater Treatment Plant, Low- ar 119 - Jefferson Main Replacement ngwells Water Treatment Plant Architectti ogy Management: Freeze Protectio	_			
woir water Treatment Flant 1958 wells Water Treatment Plant 1958 lick Road Pumping Station Improv 170305 - WWP SCADA Network L 06 - Wick Road Water Transmissi Water Treatment Plant - Service I wice Center Pumping Station - Re Huron and Southwest Roof Repla Lake Huron Water Treatment Plan 170307 - NE SCADA Network L 170307 - Settion Improv Station Improv Station Improv Station Improv Station Improv Station Improv Station Improv Station Improv Static Road Pumping Station Improv Joy Road Pumping Station Improv Schoolcraft Pumping Station Improv Joy Road Pumping Station Improv Stater Treatment Plant, Yard Pij diter Works Park Site/Civil Improv Atter Works Park Site/Civil Improv Atter Works Park Site/Civil Improv Mater Treatment Plant, Low- ar 111011 - Lake Huron WTP Pil uron Water Treatment Plant, Low- ar 111011 - Lake Huron WTP Pil uron Water Treatment Plant, Arch if Booster Pumping Station Improv Merriman Road Water Transmissi t Water Treatment Plant Architectti 19 - Jefferson Main Replacement ngwells Water Treatment Plant Pla	_			
voir inspe wells Wati wells Wate Water Tri Water Tri Water Tri Huron an Huron an 170307 170307 21 - Imlay Vater Huru 170307 116005 - I elle Isle Ir vater Vorks ter Works elle Isle Ir vater Vor ter Works ti Booster 11101 11101 1101 - Jeffe ngwells W	_			
wells Watu wells Watu Jick Road Job - Wick Water Try Water Try Lake Hurn 170307 170307 170307 21 - Imlay s Water Tro Heroloraft vater Works elle Isle Ir elle Isle Ir vater Wor vater Tro 11101 11101 1101 - Jeffe ngwells W				
 /ick Road /ick Road /ick Road // Water Tr Water Tr // Water Tr // 170307 // 110055 // 11104 // 1		F		
170305 - Vick Water Trr Water Trr Huron an Huron an Lake Huru 170307 170307 21 - Imlay Vewburgh Swater Tr Hervorks ter Works elle Isle Ir elle Isle Ir elle Isle Ir vater Wor vater Wor toolcraft 11101 11010 - Jeffe ngwells W		L		
06 - Wick Water Tri Huron an Lake Hurr 170307 170307 21 - Imlay Newburgh Shoolcraft Shoolcraft I16005 - I elle Isle Ir Vater Wor Vater Vor St Water T 11101 11101 Uron Wate I Booster I Booster I Booster I Booster Vater Tr Merriman Uron Wate Merriman		E		
Water Trr Vice Cent Huron an Lake Hurr 170307 170307 Vewburgh Vewburgh Shoolcraft Shoolcraft ther Works Iter Works elle Isle Ir Shoolcraft Aater Wor Vater Wor 11101 11101 1101 - Jeffe Nanag Sy Manag		L		
rvice Cent Huron an Lake Huro 170307 21 - Imlay Newburgh Choolcraft choolcraft s Water Ti 8elle Isle Ir 116005 - I 11101 vater Works st Water T 11101 uron Wate Merriman t Water Ti 1919 - Jeffe gy Manag		I		
Huron an Lake Huro 170307 Newburgh Newburgh Joy Road s Water T 116005 - I 116005 - I selle Isle Ir choolcraft choolcraft thater Wor vater Wor vater Wor vater T 11101 uron Wate ti Booster ti Booster ti Water Tr 11019 - Jeffe gy Manag	l	I	l.	
Lake Hurr 170307 21 - Imlay Newburgh Newburgh Suder Ti Joy Road s Water Ti 116005 - I selle Isle Ir choolcraft choolcraft Vater Wor vater Wor vater Ti 11101 uron Wate uron Wate ti Booster ti Booster Ti 11101 uron Wate gy Manag		I		
170307 170307 Newburgh Newburgh Choolcraft Joy Road ater TI 116005 - I 116005 - I the Ir belle Isle Ir vater Wor vater Vvor vater Vvor ti Booster I 11101 uron Wate TI 11010 - Jeffe gy Manag		I		
21 - Imlay Newburgh Joy Road s Water T s Water T selle Isle Ir selle Isle Ir choolcraft vater Vor st Water T 11101 uron Wate uron Wate uron Wate ti Booster ti Booster ti Water Tr gy Manag		l		
Newburgh choolcraft Joy Road s Water Ti ater Works ater Works belle Isle Ir belle Isle Ir belle Isle Ir 11101 uron Water 11101 uron Water ti Booster ti Booster ti Water Ti ngwells W gy Manag	_	1		
 Newourgin viewourgin Joy Road Joy Road S Water Ti Selle Isle Ir Selle Isle Ir Selle Isle Ir Selle Isle Vorks Selle Isle Vorks Selle Isle Vorks Selle Isle Ir Selle Isle Isle Ir Selle Isle Isle Ir Selle Isle Isle Isle Ir Selle Isle Isle Isle Isle Ir Selle Isle Isle Ir Selle Isle Isle Isle Isle Isle Ir Selle Isle Isle Isle Ir Selle Isle Isle Isle Ir Selle Isle Isle Isle Isle Ir Selle Isle Isle Isle Isle Isle Isle Isle				
choolcraft Joy Road s Water T ater Works 116005 - I 116005 - I the Nor belle Isle Ir vater Wor vater Vor vater Vor vater To 1101 - Jeffe ngwells W gy Manag	_			
Joy Road s Water Tr ater Works ater Works belle Isle Ir belle Isle Ir choolcraft vater Work uron Wate uron Wate uron Wate ti Booster ti Booster ti Water Tr ti Water Tr gy Manag	ŀ	ſ		
s Water Ti ater Works 116005 - I belle Isle Ir belle Isle Ir belle Isle Ir vater Wor 11101 11101 uron Wate ti Booster ti Booster Tr Merriman t Water Tr 19 - Jeffe gy Manag	l	ľ		
ater Works 116005 - I selle Isle Ir choolcraft vater Wor vater Wor 11101 uron Wate uron Wate uron Wate ti Booster ti Booster ti Water Tr 19 - Jeffe gy Manag	l	ľ		
116005 - I belle Isle Ir choolcraft Vater Wor 11101 uron Wate uron Wate ti Booster ti Water Tr t Water Tr ngwells W gy Manag				
belle Isle Ir choolcraft Vater Wor st Water T 11101 uron Wate uron Water ti Booster ti Water Tr 19 - Jeffe gy Manag	_			
choolcraft vater Wor st Water T 11101 uron Wate Merriman Merriman 19 - Jeffe gy Manag	_			
vater Wor Vater Wor st Water 7 1100 uron Wate uron Water Merriman t Water Tr 19 - Jeffe gy Manag		ĥ		
Vater Wor st Water T 11101 uron Wate ti Booster Merriman t. Water Tr 199 - Jeffe gy Manag				
st Water T 11101 uron Wate uron Water ti Booster Merriman t Water Tr 19 - Jeffe ngwells W		i.		
11101 uron Wate ti Booster Merriman t Water Tr 19 - Jeffe ngwells W gy Manag				
uron Wate ti Booster Merriman t Water Tr 19 - Jeffe ngwells W gy Manag		I.		
ti Booster Merriman t Water Tr 119 - Jeffe ngwells W gy Manag				
Park-Merriman Road Water Transmission Main thwest Water Treatment Plant Architectural and 122019 - Jefferson Main Replacement Project - Springwells Water Treatment Plant Powdered Energy Management: Freeze Protection Pump		t		
thwest Water Treatment Plant Architectural and 122019 - Jefferson Main Replacement Project - Springwells Water Treatment Plant Powdered Energy Management: Freeze Protection Pump				
122019 - Jefferson Main Replacement Project - Springwells Water Treatment Plant Powdered				
- Springwells Water Treatment Plant Powdered Energy Management: Freeze Protection Pump				
Energy Management: Freeze Protection Pump.				
Energy Management: Freeze Protection Pump.				
 Transmission Mains Valves and 				
170504 - Transmission Mains Valves and Urgent				

PM SCORE RC SCORE

WATER PROJECT MANAGER AND REVIEW COMMITTEE SCORES

58 GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1



59

WASTEWATER PROJECT MANAGER & REVIEW COMMITTEE SCORES

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
211005	WRRF PS No. 2 Improvements Phase II	77.4	5	4	4	3	4	3	2	2	77.4	5	4	4	3	4	3	2	2
211006	WRRF PS No. 1 Improvements	79.2	5	4	4	4	4	3	3	3	78.6	5	4	4	4	4	3	2	3
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements	76.6	3	4	4	4	3	3	3	3	75.7	3	4	4	4	3	3	3	1
211008	WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines	78.3	4	4	4	3	4	3	3	4	78.3	4	4	4	3	4	3	3	4
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System	76.6	4	5	3	2	2	2	3	3	76.6	4	5	3	2	2	2	3	3
211010	Rehabilitation of Sludge Processing Complexes A and B	89.7	2	2	4	4	5	4	2	2	89.7	2	2	4	4	5	4	2	2
211011	WRRF PS1 Screening and Grit Improvements	77.5	4	5	2	4	2	2	4	3	77.5	4	5	2	4	2	2	4	3
212008	WRRF Aeration Improvements 1 and 2	76.3	4	3	4	3	3	3	3	4	76.3	4	3	4	3	3	3	3	4
212009	WRRF Aeration Improvements 3 and 4	76.3	4	3	4	3	3	3	3	4	76.3	4	3	4	3	3	3	3	4
212010	WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite	89.7	2	2	4	4	5	4	2	2	89.7	2	2	4	4	5	4	2	2
213006	WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities	75.3	3	3	4	4	2	2	4	4	76.6	4	3	4	5	2	2	4	4
213007	WRRF Modification to Incinerator Sludge Feed Systems at Complex -II	96.7	5	5	5	4	4	4	4	4	96.2	5	5	5	4	4	4	4	3
213008	WRRF Rehabilitation of the Ash Handling Sys- tems	57.8	3	2	3	4	3	1	3	1	59.5	4	3	3	4	3	1	3	1
213009	WRRF Biosolids Processing Improvements	79.6	4	4	4	5	4	3	3	4	79.6	4	4	4	5	4	3	3	4
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF	94.7	5	5	5	4	3	3	4	3	94.7	5	5	5	4	3	3	4	3
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities	49.1	3	3	2	2	2	2	2	3	79	5	4	4	3	4	4	3	3
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station	64.7	5	2	2	4	1	5	4	4	63.2	5	2	2	4	1	2	4	4
216011	WRRF Structural Improvements	63.3	4	4	3	4	1	2	3	1	64.4	4	4	3	4	2	2	3	1
222001	Oakwood District Intercommunity Relief Sewer Modification at Oakwood District	74.8	1	4	4	1	4	4	3	3	62.7	1	4	2	1	3	4	3	4
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	78.3	4	4	4	3	3	4	4	4	66.4	5	4	3	1	3	4	5	1
222008	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure	63.9	3	4	1	4	3	3	2	4	63.9	3	4	1	4	3	3	2	4
232001	Fairview Pumping Station - Replace Four Sani- tary Pumps	63.6	4	4	2	4	2	4	1	2	63.6	4	4	2	4	2	4	1	2
232002	Freud & Conner Creek Pump Station Improve- ments	97.4	5	5	5	5	4	4	4	4	94.1	4	4	5	3	4	5	5	1

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
232004	CONDITION ASSESSMENT AT BLUE HILL PUMP STATION	60.6	3	3	3	3	3	4	4	2	60.6	3	3	3	3	3	4	4	2
233003	Rouge River In-system Storage Devices	88.8	1	3	5	1	4	4	2	4	88.2	1	3	5	1	4	4	1	4
260201	CON-149, Emergency Sewer Repair	76.9	4	4	3	4	4	3	3	2	76.9	4	4	3	4	4	3	3	2
260204	Conveyance System Engineering Ser- vices-1802575	77.4	4	4	4	4	3	4	3	2	78.3	4	4	4	4	3	4	3	4
260205	NWI Rehabilitation	67.1	4	4	3	4	3	3	4	2	60.3	4	3	3	4	3	4	2	1
260206	Conveyance System Repairs (Sewers)	63.2	4	4	3	3	2	2	2	1	57.6	4	3	3	3	2	2	2	1
260207	Rehabilitation of Woodward Sewer Systems	75.6	4	4	4	3	3	3	2	2	76.8	4	4	4	3	3	3	4	2
260209	Sewer Rehabilitation and Repair	76.4	4	4	3	4	4	3	3	1	61.3	4	3	3	3	3	4	4	2
260508	B-39 Outfall Rehabilitation	75.3	5	4	4	3	3	3	1	1	75.3	5	4	4	3	3	3	1	1
260510	Conveyance System Repairs (Outfalls)	74.2	4	3	4	3	3	3	2	1	73.8	4	3	4	3	3	2	2	1
260614	Structural Inspection & Structural Improvements	53.4	3	3	1	1	3	1	1	1	53.4	3	3	1	1	3	1	1	1
260618	Oakwood HVAC Project	20	1	1	1	1	1	1	1	1	20	1	1	1	1	1	1	1	1
260619	Control System Upgrade - St Aubin, Lieb & Mile	95.1	5	5	5	3	4	4	4	2	95.1	5	5	5	3	4	4	4	2
260620	Baby Creek Roof Replacement	82.8	5	5	4	5	4	1	5	2	78.8	5	4	4	4	4	2	4	2
260621	Conner Creek Dike Improvements	97.4	4	5	5	5	5	5	5	1	95.2	4	4	5	4	5	5	4	1
260622	CSO Emergency Generator Improvements	93.6	5	5	5	5	3	3	2	2	77.5	5	4	4	4	3	4	2	2
260623	CSO Baby Creek Screen Rehabilitation	94.4	4	3	5	4	5	4	5	1	93.2	4	3	5	4	5	4	3	1
260701	Conveyance System Infrastructure Improve- ments	93.5	4	4	5	3	4	4	4	2	60.1	3	3	3	3	3	4	4	1
260702	Pump Station Assets Updates	57.5	3	3	3	4	2	2	2	1	59.6	4	3	3	3	3	4	2	1
260802	2022 WRRF Roof Improvements Project	78.1	4	4	4	4	4	3	4	1	77.9	4	4	4	3	4	4	4	1
260901	Rehabilitation of HAZMAT Facility at WRRF	52.9	4	3	2	3	2	2	3	2	52.1	4	2	2	4	2	2	2	2
260902	WRRF 4th Floor Renovation	41	2	2	1	1	1	1	4	2	59.5	4	3	2	3	3	3	2	4
260903	WRRF Front Entrance Rehabilitation	52.4	4	2	2	3	2	2	2	4	52.4	4	2	2	3	2	2	2	4
260904	WRRF 3rd Floor Renovation	39.4	3	2	1	2	1	3	1	4	40.5	3	2	1	3	1	4	1	4
261001	WRRF Rehabilitation of the Secondary Clarifiers Phase 1	72	4	3	4	3	1	4	1	1	72	4	3	4	3	1	4	1	1
270001	Pilot CSO Netting Facility	89.6	1	5	5	1	4	4	1	3	89.6	1	5	5	1	4	4	1	3
270002	Meldrum Sewer Diversion and VR-15 Improve- ments	86.9	1	1	5	1	4	5	1	4	88.7	1	3	5	1	4	5	1	4
270003	Long Term CSO Control Plan	88	1	3	5	1	4	3	3	2	88	1	3	5	1	4	3	3	2
270004	Oakwood and Leib CSO Facilities Improvement Project	79.4	4	4	3	4	4	5	4	4	79.4	4	4	4	4	3	5	4	4
270006	CSO Facilities Improvements II	79.3	5	4	4	4	4	4	4	1	61	4	3	3	4	3	3	4	1

CIPNumber	Title	PM SCORE	PM_1	PM_2	PM_3	PM_4	PM_5	PM_6	PM_7	PM_8	RC SCORE	RC_1	RC_2	RC_3	RC_4	RC_5	RC_6	RC_7	RC_8
270007	Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CSO Facilities	59.3	3	3	3	4	2	1	5	2	57	1	2	3	4	2	1	5	2
270008	Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities	73.5	1	3	2	4	4	1	5	3	74.4	3	3	2	4	4	1	5	2
270009	Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities	56.7	3	2	2	3	3	1	4	1	54.6	1	2	2	2	3	1	4	1
270010	HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities	73.2	4	2	2	4	4	1	4	1	57.8	3	2	2	4	3	2	4	1
270011	HVAC Improvements at Conner Creek and Belle Isle CSO Facilities	71.8	3	2	2	4	4	1	3	1	70.5	2	2	2	3	4	1	3	1
270012	Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities	73.2	2	3	2	4	4	1	5	1	59	4	3	2	4	3	1	4	1
270013	Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities	71.9	1	3	2	4	4	1	4	1	56.8	1	3	2	4	3	1	4	1
270014	Conversion to Complete Capture Basin at Puri- tan Fenkell and Seven Mile CSO Facilities	73.3	2	2	2	4	4	1	5	3	72	1	2	2	4	4	1	4	3
273001	Hubbell Southfield CSO Facility Improvements	79.5	5	4	3	5	4	1	5	4	75.7	2	4	3	4	4	1	5	2
273002	CSO Hubbell Southfield VR-8 Gate Improve- ments	49.5	2	3	2	4	2	1	4	1	50.2	3	3	2	4	2	1	4	1
276002	Replacement of Make-up Air Unit No. 2 at Con- ner Creek CSO Facility	92.5	5	5	2	4	5	1	3	4	92.5	5	5	2	4	5	1	3	4
277001	Baby Creek Outfall Improvements Project	79.7	2	5	3	5	3	4	3	4	80.1	2	5	4	4	3	4	3	4
277002	Baby Creek CSO Facility Influent Flushing Sys- tem	73.6	2	3	2	4	4	1	4	3	72.3	1	3	2	4	4	1	3	3

120														
100	_													
80 60 40														
20	Ħ	t	HH	П	П	П	H	H	l	ш	Ш		Ш	ш
0	260621 - Conner Creek Dike Improvements 260619 - Control System Upgrade - St Aubin, Lieb & Mile	232002 - Freud & Conner Creek Pump Station Improvements	260623 - CSO Baby Creek Screen Rehabilitation 211010 - Rehabilitation of Sludge Processing Complexes A and B 212010 - WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite 270001 - Pilot CSO Netting Facility	270002 - Meldrum Sewer Diversion and VR-15 Improvements 233003 - Rouge River In-system Storage Devices	277001 - Baby Creek Outfall Improvements Project		200204 - Conveyance System Engineering Services-1802575 260802 - 2022 WRRF Roof Improvements Project	211011 - WRRF PS1 Screening and Grit Improvements 260622 - CSO Emergency Generator Improvements	<u><u></u></u>	 260207 - Rehabilitation of Woodward Sewer Systems 211009 - WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System 212009 - WRRF Aeration Improvements 3 and 4 	 211007 - WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements 273001 - Hubbell Southfield CSO Facility Improvements 270008 - Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities 260510 - Conveyance System Repairs (Outfalls) 	й	222001 - Oakwood District Intercommunity Relief Sewer Modification at Oakwood District 260209 - Sewer Rehabilitation and Repair	270006 - CSO Facilities Improvements II 260205 - NWI Rehabilitation 260701 - Convevance System Infrastructure Improvements

WASTEWATER PROJECT MANAGER AND REVIEW COMMITTEE SCORES

GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1 66

270012 - Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities 270010 - HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities 270007 - Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CSO Facilities 270013 - Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities - Conveyance System Infrastructure Improvements 260902 - WRRF 4th Floor Renovation 260206 - Conveyance System Repairs (Sewers) 270009 - Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities 260901 - Rehabilitation of HAZMAT Facility at WRRF 273002 - CSO Hubbell Southfield VR-8 Gate Improvements 260904 - WRRF 3rd Floor Renovation 213008 - WRRF Rehabilitation of the Ash Handling Systems 260702 - Pump Station Assets Updates 260701 -



O3 CIP PROJECTS BY CATEGORY

3.1. LARGEST CIP PROJECTS

The water and wastewater projects included in the FY2024-2028 CIP with the largest projected lifetime spend (the top five for each) are listed below. Programs are excluded from the tables below.

WATER

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Plan Spend
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	\$303,261
122003	Water Works Park to Northeast Transmission Main	\$290,882
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	\$262,220
114010	Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements	\$218,799
113003	Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements	\$184,285

WASTEWATER

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Plan Spend
260600	CSO FACILITIES IMPROVEMENT PROGRAM	\$1,030,191
232002	Freud & Conner Creek Pump Station Improvements	\$558,498
213009	WRRF Biosolids Processing Improvements	\$199,423
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	\$113,560
211011	WRRF PS1 Screening and Grit Improvements	\$98,092

CIP PROJECTS BY CATEGORY 3.1. LARGEST CIP PROJECTS

3.2. LARGEST DOLLAR PROJECTS (GREATER THAN \$30M)

Water and wastewater projects continue to be scored based on the eight criteria shown in Table 1 of Section 2.7. For each project, a criteria score of 1 to 5 has been assigned, with a score of 1 representing minimal value or benefit, and 5 representing high value or benefit based on established definitions and scoring guidelines for each criteria.

WATER PROJECTS WITH 5-YEAR TOTAL GREATER THAN \$30M

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 Total	Project Total
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	\$16,221	\$38,052	\$78,841	\$59,315	\$20,773	\$20,773	\$23,888	\$203,589	\$262,220
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	\$22,468	\$4,819	\$17,896	\$27,906	\$27,421	\$36,116	\$28,505	\$137,843	\$303,261
122016	Downriver Transmission Main Loop	\$2,451	\$287	\$10,814	\$10,784	\$10,784	\$10,784	\$10,814	\$53,980	\$67,502
111012	LHWTP-Flocculation Improvements	\$464	\$1,700	\$6,702	\$12,006	\$12,006	\$12,006	\$6,447	\$49,168	\$51,331
111001	Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements	\$2,918	\$2,966	\$618	\$2,910	\$6,291	\$24,242	\$13,770	\$47,831	\$141,373
132016	North Service Center Pumping Station Improvements	\$372	\$109	\$222	\$222	\$8,594	\$19,141	\$19,193	\$47,372	\$76,013
170802	Reservoir Inspection, Design, and Construction Management Services Phase II	\$0	\$3,067	\$12,333	\$12,299	\$12,299	\$7,177	\$0	\$44,108	\$47,175
122019	Jefferson Main Replacement Project	\$0	\$534	\$96	\$19,753	\$19,753	\$0	\$0	\$39,602	\$40,136
111006	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements	\$1,282	\$1,018	\$1,237	\$9,567	\$9,590	\$9,590	\$8,066	\$38,050	\$40,350
112003	Northeast Water Treatment Plant High-Lift Pumping Station Improvements	\$536	\$613	\$2,764	\$2,756	\$11,654	\$10,415	\$10,443	\$38,032	\$172,269
122013	14 Mile Transmission Main Loop	\$28,680	\$52,234	\$34,589	\$0	\$0	\$0	\$0	\$34,589	\$115,502
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	\$12,037	\$10,275	\$9,019	\$8,995	\$8,995	\$6,752	\$0	\$33,761	\$56,073

CIP PROJECTS BY CATEGORY 3.2. LARGEST DOLLAR CIP PROJECTS

WASTEWATER PROJECTS WITH 5-YEAR TOTAL GREATER THAN \$30M

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 CIP Total	Project Total
232002	Freud & Conner Creek Pump Station Improvements	\$16,571	\$3,563	\$21,814	\$26,206	\$29,461	\$29,461	\$17,433	\$124,375	\$558,498
211006	WRRF PS No. 1 Improvements	\$6,015	\$5,495	\$16,017	\$13,722	\$13,722	\$13,722	\$13,760	\$70,943	\$92,065
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements	\$5,318	\$2,606	\$4,793	\$14,363	\$14,363	\$14,363	\$14,402	\$62,283	\$94,250
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station	\$1,665	\$3,509	\$2,707	\$19,518	\$19,518	\$17,058	\$0	\$58,801	\$63,975
212008	WRRF Aeration Improvements 1 and 2	\$968	\$2,374	\$10,877	\$10,848	\$10,848	\$10,848	\$10,877	\$54,297	\$77,582
260701	Conveyance System Infrastructure Improvements	\$2,241	\$11,237	\$16,997	\$13,829	\$9,829	\$3,797	\$0	\$44,451	\$57,929
260204	Conveyance System Engineering Services-1802575	\$1,923	\$13,573	\$16,380	\$16,335	\$7,340	\$0	\$0	\$40,054	\$55,551
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	\$42,279	\$12,711	\$12,623	\$12,589	\$11,261	\$164	\$2,225	\$38,863	\$113,560
260510	Conveyance System Repairs (Outfalls)	\$903	\$1,178	\$4,876	\$9,297	\$11,797	\$6,699	\$912	\$33,581	\$35,662

CIP PROJECTS BY CATEGORY 3.2. LARGEST DOLLAR CIP PROJECTS

3.3. LARGEST 2024 PROJECTED SPEND (GREATER THAN \$5M)

The water and wastewater projects with the largest projected spend for 2024 are listed below. These projects are planned for greater than \$5 Million in FY 2024. There are twelve (12) projects in the water category and ten (10) projects in the wastewater category.

WATER PROJECTS WITH FY 2024 PROJECTED SPEND GREATER THAN \$5M

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 CIP Total	Project Total
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	\$16,221	\$38,052	\$78,841	\$59,315	\$20,773	\$20,773	\$23,888	\$203,589	\$262,220
122013	14 Mile Transmission Main Loop	\$28,680	\$52,234	\$34,589	\$0	\$0	\$0	\$0	\$34,589	\$115,502
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	\$22,468	\$4,819	\$17,896	\$27,906	\$27,421	\$36,116	\$28,505	\$137,843	\$303,261
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements	\$56,113	\$15,013	\$16,052	\$11,885	\$0	\$0	\$0	\$27,937	\$99,063
170802	Reservoir Inspection, Design, and Construction Management Services Phase II	\$0	\$3,067	\$12,333	\$12,299	\$12,299	\$7,177	\$0	\$44,108	\$47,175
111009	Lake Huron Water Treatment Plant - High Lift Pumping, Water Production Flow Metering and Yard Piping Improvements	\$3,035	\$9,526	\$12,243	\$6,325	\$25	\$0	\$0	\$18,593	\$31,153
122016	Downriver Transmission Main Loop	\$2,451	\$287	\$10,814	\$10,784	\$10,784	\$10,784	\$10,814	\$53,980	\$67,502
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	\$12,037	\$10,275	\$9,019	\$8,995	\$8,995	\$6,752	\$0	\$33,761	\$56,073
114017	Springwells Water Treatment Plant Flocculator Drive Replacements	\$896	\$3,280	\$7,910	\$7,888	\$5,381	\$0	\$0	\$21,179	\$25,355
111012	LHWTP-Flocculation Improvements	\$464	\$1,700	\$6,702	\$12,006	\$12,006	\$12,006	\$6,447	\$49,168	\$51,331
132010	West Service Center Pumping Station - Reservoir, Reservoir Pumping, and Division Valve Upgrades	\$28,176	\$10,684	\$6,547	\$215	\$0	\$0	\$0	\$6,762	\$45,621
115005	WWP WTP Building Ventilation Improvements	\$765	\$4,379	\$5,274	\$5,259	\$865	\$0	\$0	\$11,398	\$16,541

WASTEWATER PROJECTS WITH FY 2024 PROJECTED SPEND GREATER THAN \$5M

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	2024-2028 CIP Total	Project Total
232002	Freud & Conner Creek Pump Station Improvements	\$16,571	\$3,563	\$21,814	\$26,206	\$29,461	\$29,461	\$17,433	\$124,375	\$558,498
260701	Conveyance System Infrastructure Improvements	\$2,241	\$11,237	\$16,997	\$13,829	\$9,829	\$3,797	\$0	\$44,451	\$57,929
260204	Conveyance System Engineering Services-1802575	\$1,923	\$13,573	\$16,380	\$16,335	\$7,340	\$0	\$0	\$40,054	\$55,551
211006	WRRF PS No. 1 Improvements	\$6,015	\$5,495	\$16,017	\$13,722	\$13,722	\$13,722	\$13,760	\$70,943	\$92,065
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	\$42,279	\$12,711	\$12,623	\$12,589	\$11,261	\$164	\$2,225	\$38,863	\$113,560
212008	WRRF Aeration Improvements 1 and 2	\$968	\$2,374	\$10,877	\$10,848	\$10,848	\$10,848	\$10,877	\$54,297	\$77,582
260206	Conveyance System Repairs (Sewers)	\$396	\$2,102	\$8,167	\$7,480	\$3,004	\$4,707	\$4,627	\$27,985	\$34,516
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities	\$3,762	\$6,958	\$7,804	\$7,782	\$0	\$0	\$0	\$15,586	\$26,305
260209	Sewer Rehabilitation and Repair	\$4	\$5,671	\$6,850	\$6,266	\$6,234	\$0	\$0	\$19,350	\$25,025
260207	Rehabilitation of Woodward Sewer Systems	\$3,577	\$10,942	\$5,784	\$0	\$0	\$0	\$0	\$5,784	\$20,303
76 GLWA 0	CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1				GLWA	CAPITAL I	MPROVEN	IENT PLAN	2024-2028 DRAFT	1 77

CIP PROJECTS BY CATEGORY 3.3. LARGEST 2024 PROJECTED SPEND

3.4. WATER PROJECTS BY STATUS

All financial figures are in thousands of dollars (\$1,000's). Projects that have been Reclassified to a different number, Closed, or Cancelled are not shown in this list; a list of Closed projects can be found in Section 2.2. For projects in the "Centralized Services" category (CIP number begins with 3), only portions of projects funded by the water planned spend are included in this section.

WATER CIP PROJECTS: ACTIVE, RANKED BY 5-YEAR CIP TOTAL

Financial figures are in thousands of dollars (\$1,000's)

Score Note: * Denotes a CIP project that is a Program. For projects with no score, see Appendices for PM Scores

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	Project Execution - Construction	2016	\$16,221	\$38,052	\$78,841	\$59,315	\$20,773	\$20,773	\$23,888	\$4,358	\$203,589	\$262,220	7.3%	77.5
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	Project Execution - Design	2004	\$22,468	\$4,819	\$17,896	\$27,906	\$27,421	\$36,116	\$28,505	\$138,132	\$137,843	\$303,261	8.5%	90.9
122016	Downriver Transmission Main Loop	Project Execution - Design	2017	\$2,451	\$287	\$10,814	\$10,784	\$10,784	\$10,784	\$10,814	\$10,784	\$53,980	\$67,502	1.9%	76
111012	LHWTP-Flocculation Improvements	Project Execution - Design	2021	\$464	\$1,700	\$6,702	\$12,006	\$12,006	\$12,006	\$6,447	\$0	\$49,168	\$51,331	1.4%	91.5
111001	Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements	Project Execution - Design	2010	\$2,918	\$2,966	\$618	\$2,910	\$6,291	\$24,242	\$13,770	\$87,657	\$47,831	\$141,373	3.9%	79.7
132016	North Service Center Pumping Station Improvements	Active - Procurement - Design	2017	\$372	\$109	\$222	\$222	\$8,594	\$19,141	\$19,193	\$28,160	\$47,372	\$76,013	2.1%	98.7
170802*	Reservoir Inspection, Design, and Construction Management Services Phase II	Active - Procurement - Design	2021	\$0	\$3,067	\$12,333	\$12,299	\$12,299	\$7,177	\$0	\$0	\$44,108	\$47,175	1.3%	N/A
122019	Jefferson Main Replacement Project	Project Execution - Design	2021	\$0	\$534	\$96	\$19,753	\$19,753	\$0	\$0	\$0	\$39,602	\$40,136	1.1%	37.2
111006	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements	Active - Procurement - Construction	2014	\$1,282	\$1,018	\$1,237	\$9,567	\$9,590	\$9,590	\$8,066	\$0	\$38,050	\$40,350	1.1%	60.5
122013	14 Mile Transmission Main Loop	Project Execution - Construction	2017	\$28,680	\$52,234	\$34,589	\$0	\$0	\$0	\$0	\$0	\$34,589	\$115,502	3.2%	76
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	Project Execution - Construction	2007	\$12,037	\$10,275	\$9,019	\$8,995	\$8,995	\$6,752	\$0	\$0	\$33,761	\$56,073	1.6%	77.9

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements	Project Execution - Construction	2016	\$56,113	\$15,013	\$16,052	\$11,885	\$0	\$0	\$0	\$0	\$27,937	\$99,063	2.8%	94.3
114017	Springwells Water Treatment Plant Flocculator Drive Replacements	Active - Procurement - Construction	2018	\$896	\$3,280	\$7,910	\$7,888	\$5,381	\$0	\$0	\$0	\$21,179	\$25,355	0.71%	89.7
111009	Lake Huron Water Treatment Plant - High Lift Pumping, Water Production Flow Metering and Yard Piping Improvements	Project Execution - Design	2018	\$3,035	\$9,526	\$12,243	\$6,325	\$25	\$0	\$0	\$0	\$18,593	\$31,153	0.87%	75.7
170904*	Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II	Active - Procurement - Construction	2002	\$0	\$0	\$3,205	\$3,196	\$3,196	\$3,196	\$3,205	\$0	\$16,000	\$16,000	0.45%	N/A
122003	Water Works Park to Northeast Transmission Main	Project Execution - Construction	2014	\$34,956	\$16,747	\$2,812	\$2,804	\$2,804	\$2,804	\$2,812	\$225,142	\$14,037	\$290,882	8.1%	76.8
115005	WWP WTP Building Ventilation Improvements	Project Execution - Design	2018	\$765	\$4,379	\$5,274	\$5,259	\$865	\$0	\$0	\$0	\$11,398	\$16,541	0.46%	93
170500	Transmission System Valve Rehabilitation and Replacement Program	Project Execution - Construction	2017	\$0	\$0	\$1,617	\$1,612	\$1,612	\$3,261	\$3,270	\$21,598	\$11,371	\$32,969	0.92%	N/A
112006	Northeast Water Treatment Plant Flocculator Replacements	Project Execution - Construction	2018	\$334	\$2,389	\$2,876	\$2,868	\$2,868	\$2,048	\$0	\$0	\$10,660	\$13,382	0.37%	82.4
170601*	Linear System Integrity Program	Project Execution - Design	2021	\$0	\$482	\$109	\$109	\$5,849	\$3,301	\$0	\$0	\$9,368	\$9,850	0.27%	N/A
132010	West Service Center Pumping Station - Reservoir, Reservoir Pumping, and Division Valve Upgrades	Project Execution - Construction	2017	\$28,176	\$10,684	\$6,547	\$215	\$0	\$0	\$0	\$0	\$6,762	\$45,621	1.3%	62.6
170600	Linear System Integrity Program	Project Execution - Design	2017	\$0	\$3	\$31	\$31	\$31	\$31	\$4,539	\$22,646	\$4,663	\$27,312	0.76%	N/A
170801*	Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, Springwells Water Treatment Plant, And Southwest Water Treatment Plant	Project Execution - Design	2022	\$18,079	\$6,313	\$3,550	\$0	\$0	\$0	\$0	\$0	\$3,550	\$27,942	0.78%	N/A
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation	Project Execution - Design	2019	\$1,381	\$3,270	\$3,118	\$34	\$34	\$34	\$34	\$27,517	\$3,253	\$35,422	0.99%	85
381000	Power Quality: Electric Metering Improvement Program	Active - Pre- Procurement - Design	2016	\$0	\$489	\$1,069	\$1,066	\$0	\$0	\$0	\$0	\$2,135	\$2,624	0.073%	N/A
116007	System Electrical Power Improvements	Active - Pre- Procurement - Design	2021	\$0	\$1,978	\$2,032	\$0	\$0	\$0	\$0	\$0	\$2,032	\$4,010	0.11%	77.1

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
113009	SW Flight and Chain Upgrades	Project Execution - Construction		\$0	\$1,435	\$1,592	\$0	\$0	\$0	\$0	\$0	\$1,592	\$3,027	0.084%	68.7
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station	Project Execution - Design	2019	\$6,046	\$2,207	\$1,280	\$33	\$33	\$33	\$33	\$55,886	\$1,412	\$65,552	1.8%	81.2
114011	Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements	Project Execution - Construction	2012	\$24,222	\$2,632	\$1,133	\$0	\$0	\$0	\$0	\$0	\$1,133	\$27,987	0.78%	77
132007	Energy Management: Freeze Protection Pump Installation at Imlay Pump Station	Project Execution - Design	2014	\$1,105	\$3,783	\$859	\$0	\$0	\$0	\$0	\$0	\$859	\$5,747	0.16%	35.1
170503*	Transmission System Valve Replacement	Project Execution - Construction	2017	\$3,163	\$14,597	\$730	\$0	\$0	\$0	\$0	\$0	\$730	\$18,490	0.52%	N/A
116005	Belle Isle Seawall Rehabilitation	Active - Procurement - Design	2020	\$1	\$455	\$719	\$0	\$0	\$0	\$0	\$0	\$719	\$1,175	0.033%	57.5
114018	Springwells Water Treatment Plant - Service Building Electrical Substation and Miscellaneous Improvements	Active - Pre- Procurement - Design	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$133	\$2,207	\$133	\$2,341	0.065%	62.7
132012	Ypsilanti Booster Pumping Station Improvements	Project Execution - Design	2017	\$659	\$1,738	\$25	\$25	\$25	\$25	\$25	\$39,633	\$124	\$42,154	1.2%	47.6
170502*	Transmission System Valve Rehabilitation and Replacement Program	Project Execution - Construction	2017	\$5,609	\$8	\$9	\$9	\$9	\$9	\$0	\$0	\$37	\$5,654	0.16%	N/A
113006	Southwest Water Treatment Plant Chlorine Scrubber, Raw Water Screens & Related Improvements	Project Execution - Construction	2017	\$2,483	\$5,132	\$14	\$0	\$0	\$0	\$0	\$0	\$14	\$7,628	0.21%	90.6
111011	Lake Huron WTP Pilot Plant	Project Execution - Design	2019	\$2,237	\$1,031	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,268	0.091%	50.7
114008	Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements	Project Execution - Construction	2014	\$11,777	\$2,339	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$14,116	0.39%	86.1
114016	Springwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete Pavement Replacement	Project Execution - Construction	2018	\$1,582	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,590	0.044%	71.7
122005	Schoolcraft Road Water Transmission Main	Project Execution - Construction	2016	\$14,732	\$2,313	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$17,045	0.48%	54.7
122006	Wick Road Water Transmission Main	Project Execution - Construction	2016	\$22,507	\$3,362	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$25,870	0.72%	62.9
122011	Park-Merriman Road Water Transmission Main	Project Execution - Construction	2015	\$8,368	\$3,195	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$11,564	0.32%	44.1
170109	GLWA-CS-187: FK Eng: Raw Water Intake	Pending Closeout	2012	\$1,656	\$244	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,900	0.053%	N/A

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
170302*	SW SCADA System Upgrade	Project Execution - Design	2017	\$1,141	\$7,170	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$8,311	0.23%	N/A
170303*	Power Monitoring Installation for Water Treatment Plants	Project Execution - Design	2020	\$1,717	\$190	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,906	0.053%	N/A
170901*	Suburban Water Meter Pit Rehabilitation and Meter Replacement	Project Execution - Construction	2014	\$10,015	\$2,506	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$12,522	0.35%	N/A
170902*	Brownstown Meter Pit	Active - Pre- Procurement - Construction	2020	\$87	\$136	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$222	0.0062%	N/A
380700	As-Needed Geotechnical and Related Engineering Services	Project Execution - Design	2006	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	0%	N/A

WATER CIP PROJECTS: FUTURE PLANNED, RANKED BY PRIORITIZATION SCORE

Financial figures are in thousands of dollars (\$1,000's)

Score Note: * Denotes a CIP project that is a Program. For projects with no score, see Appendices for PM Scores

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024- 2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
132014	Adams Road Pumping Station Improvements	Future Planned - Ten-Year CIP	2017	\$83	\$0	\$0	\$0	\$0	\$0	\$1,264	\$60,411	\$1,264	\$61,759	1.7%	97.8
112007	NEWTP-Header Galleries and Washwater Building Structural Repair	Future Planned - Within 5 Year Plan	2022	\$0	\$0	\$140	\$2,178	\$2,178	\$2,178	\$12	\$0	\$6,685	\$6,685	0.19%	95.2
112003	Northeast Water Treatment Plant High-Lift Pumping Station Improvements	Future Planned - Within 5 Year Plan	2017	\$536	\$613	\$2,764	\$2,756	\$11,654	\$10,415	\$10,443	\$133,087	\$38,032	\$172,269	4.8%	82.2
132020	Franklin Pumping Station Improvements	Future Planned - Ten-Year CIP	2018	\$93	\$0	\$0	\$0	\$0	\$0	\$723	\$4,102	\$723	\$4,918	0.14%	77.7
111010	Filtration Improvements	Future Planned - Within 5 Year Plan	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$1,217	\$57,422	\$1,217	\$58,639	1.6%	77.4
122007	Merriman Road Water Transmission Main Loop	Future Planned - Ten-Year CIP	2016	\$0	\$0	\$0	\$0	\$0	\$0	\$1,008	\$25,201	\$1,008	\$26,209	0.73%	76.8
114005	Springwells Water Treatment Plant, Administration Building Improvements & Underground Fire Protection Loop	Future Planned - Ten-Year CIP	2014	\$1,212	\$21	\$20	\$20	\$20	\$20	\$20	\$5,359	\$102	\$6,694	0.19%	76.4
115009	Water Works Park Sedimentation Basins Structural Upgrades	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$1,664	\$15,182	\$1,664	\$16,846	0.47%	75.3
132019	Wick Road Pumping Station Improvements	Future Planned - Ten-Year CIP	2018	\$57	\$0	\$0	\$0	\$0	\$0	\$6	\$24,717	\$6	\$24,780	0.69%	67.2
132021	Imlay Pumping Station Improvements	Future Planned - Ten-Year CIP	2018	\$227	\$0	\$0	\$0	\$0	\$0	\$0	\$137,741	\$0	\$137,968	3.8%	59.4
132015	Newburgh Road Booster Pumping Station Improvements	Future Planned - Ten-Year CIP		\$494	\$60	\$36	\$36	\$36	\$36	\$36	\$44,954	\$182	\$45,690	1.3%	58.9
132018	Schoolcraft Pumping Station Improvements	Future Planned - Ten-Year CIP	2018	\$47	\$0	\$0	\$0	\$0	\$0	\$0	\$24,643	\$0	\$24,691	0.69%	58.9
132022	Joy Road Pumping Station Improvements	Future Planned - Ten-Year CIP	2018	\$71	\$0	\$0	\$0	\$0	\$0	\$0	\$39,786	\$0	\$39,857	1.1%	58.9
114010	Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements	Future Planned - Ten-Year CIP	2012	\$1,705	\$286	\$0	\$0	\$0	\$0	\$0	\$216,807	\$0	\$218,799	6.1%	58.3
115007	Water Works Park High Lift Pumping Station Modernization	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$2,012	\$113,078	\$2,012	\$115,090	3.2%	58.3
116006	Belle Isle Intake System Rehabilitation and Improvements	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$712	\$1,510	\$712	\$2,222	0.062%	55.8
115006	Water Works Park Site/Civil Improvements	Future Planned - Ten-Year CIP	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$382	\$5,514	\$382	\$5,896	0.16%	53.9
113003	Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements	Future Planned - Ten-Year CIP	2014	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$184,285	\$0	\$184,285	5.1%	52.4

87

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024- 2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
111008	Lake Huron Water Treatment Plant, Architectural Programming for Laboratory and Admin Building Improvements	Future Planned - Ten-Year CIP	2017	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$782	\$0	\$782	0.022%	49.5
113007	Southwest Water Treatment Plant Architectural and Building Mechanical Improvements	Future Planned - Ten-Year CIP	2017	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$8,641	\$0	\$8,641	0.24%	38.7
114007	Springwells Water Treatment Plant Powdered Activated Carbon System Improvements	Future Planned - Ten-Year CIP	2014	\$0	\$0	\$0	\$0	\$0	\$0	\$6	\$4,028	\$6	\$4,034	0.11%	36.8
170300	Water Treatment Plant Automation Program	Future Planned - Ten-Year CIP	2017	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$23,317	\$0	\$23,317	0.65%	N/A
170304*	WWP Scada Infrastructure Upgrade	Future Planned - Within 5 Year Plan		\$261	\$320	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$581	0.016%	N/A
170305*	WWP SCADA Network Upgrade	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,542	\$0	\$7,542	0.21%	N/A
170306*	SPW SCADA PLC Network Upgrade	Future Planned - Within 5 Year Plan	2021	\$0	\$963	\$2,379	\$0	\$0	\$0	\$0	\$0	\$2,379	\$3,341	0.093%	N/A
170307*	NE SCADA Network Upgrade	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,112	\$0	\$3,112	0.087%	N/A
170400	Water Transmission Improvement Program	Future Planned - Ten-Year CIP	2010	\$0	\$0	\$0	\$0	\$0	\$0	\$557	\$31,618	\$557	\$32,175	0.9%	N/A
170504*	Transmission Mains Valves and Urgent	Future Planned - Within 5 Year Plan		\$8,514	\$1,021	\$448	\$447	\$447	\$122	\$0	\$0	\$1,465	\$11,000	0.31%	N/A
170800	System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation	Future Planned - Ten-Year CIP	2016	\$0	\$12	\$14	\$14	\$14	\$14	\$14	\$43	\$72	\$127	0.0036%	N/A
170803*	Reservoir Inspection, Design, and Construction Management Services Phase III	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$0	\$897	\$3,695	\$11,940	\$77,901	\$16,531	\$94,432	2.6%	N/A
170900	Suburban Water Meter Pit Rehabilitation and Meter Replacement	Future Planned - Ten-Year CIP	2014	\$0	\$0	\$0	\$0	\$0	\$2,027	\$4,027	\$22,053	\$6,055	\$28,108	0.78%	N/A
171500	Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities	Future Planned - Ten-Year CIP	2018	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$15,948	\$0	\$15,948	0.44%	N/A
171502*	Lake Huron and Southwest Roof Replacement	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,710	\$0	\$2,710	0.076%	N/A
383300	Masonry Replacement and Rehabilitation Program	Future Planned - Ten-Year CIP	2020	\$0	\$0	\$0	\$0	\$0	\$0	\$23	\$24,977	\$23	\$25,000	0.7%	N/A

WATER CIP PROJECT TOTALS

Financial figures are in thousands of dollars (\$1,000's)

Title	Lifetime Actual Thru FY 2022		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Percent of Total W/S CIP
Active Water Projects Total	\$348,078	\$243,850	\$247,171	\$207,116	\$159,238	\$161,323	\$124,734	\$663,722	\$899,582	\$2,155,232 60%
Future Planned Water Projects Total	\$13,302	\$3,296	\$5,802	\$5,452	\$15,246	\$18,508	\$36,068	\$1,316,471	\$81,077	\$1,414,145 39%
Listed as Cancelled/Closed/Reclassified	\$14,125	\$55	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$14,180 0.4%
Pending Closeout Water Projects Total	\$1,656	\$244	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,900 0.053%
Total	\$377,161	\$247,446	\$252,973	\$212,568	\$174,484	\$179,831	\$160,802	\$1,980,193	\$980,659	\$3,585,458 100%

3.5 WASTEWATER PROJECTS BY STATUS

All financial figures are in thousands of dollars (\$1,000's). The Project Status column shows which projects are Active (A), Future Planned (FP), or Pending Closeout (PC). Projects that have been Reclassified to a different number, Closed, or Cancelled are not shown in this list; a list of Closed projects can be found in Section 2.2. For projects in the "Centralized Services" category (CIP number begins with 3), only portions of projects funded by the wastewater planned spend are included in this section.

WASTEWATER CIP PROJECTS: ACTIVE, RANKED BY 5-YEAR CIP TOTAL

Financial figures are in thousands of dollars (\$1,000's)

Score Note: * Denotes a CIP project that is a Program. For projects with no score, see Appendices for PM Scores

CIPNumber	Title	Project_ Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
232002	Freud & Conner Creek Pump Station Improvements	Project Execution - Design	2016	\$16,571	\$3,563	\$21,814	\$26,206	\$29,461	\$29,461	\$17,433	\$413,989	\$124,375	\$558,498	15%	94.1
211006	WRRF PS No. 1 Improvements	Active - Pre- Procurement - Construction	2016	\$6,015	\$5,495	\$16,017	\$13,722	\$13,722	\$13,722	\$13,760	\$9,612	\$70,943	\$92,065	2.5%	78.6
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements	Project Execution - Design	2016	\$5,318	\$2,606	\$4,793	\$14,363	\$14,363	\$14,363	\$14,402	\$24,043	\$62,283	\$94,250	2.6%	75.7
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station	Project Execution - Design	2018	\$1,665	\$3,509	\$2,707	\$19,518	\$19,518	\$17,058	\$0	\$0	\$58,801	\$63,975	1.7%	63.2
212008	WRRF Aeration Improvements 1 and 2	Active - Procurement - Design	2017	\$968	\$2,374	\$10,877	\$10,848	\$10,848	\$10,848	\$10,877	\$19,942	\$54,297	\$77,582	2.1%	76.3
260701*	Conveyance System Infrastructure Improvements	Active - Procurement - Construction	2021	\$2,241	\$11,237	\$16,997	\$13,829	\$9,829	\$3,797	\$0	\$0	\$44,451	\$57,929	1.6%	N/A
260204*	Conveyance System Engineering Services-1802575	Active - Procurement - Construction	2013	\$1,923	\$13,573	\$16,380	\$16,335	\$7,340	\$0	\$0	\$0	\$40,054	\$55,551	1.5%	N/A
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	Project Execution - Construction	2016	\$42,279	\$12,711	\$12,623	\$12,589	\$11,261	\$164	\$2,225	\$19,707	\$38,863	\$113,560	3.1%	66.4
260510*	Conveyance System Repairs (Outfalls)	Project Execution - Design	2020	\$903	\$1,178	\$4,876	\$9,297	\$11,797	\$6,699	\$912	\$0	\$33,581	\$35,662	0.97%	N/A

CIP PROJECTS BY CATEGORY 3.5. WASTEWATER PROJECTS BY STATUS

CIPNumber	Title	Project_ Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
260206*	Conveyance System Repairs (Sewers)	Project Execution - Design	2020	\$396	\$2,102	\$8,167	\$7,480	\$3,004	\$4,707	\$4,627	\$4,033	\$27,985	\$34,516	0.94%	N/A
273001	Hubbell Southfield CSO Facility Improvements	Active - Procurement - Design	2021	\$425	\$104	\$228	\$2,971	\$2,521	\$3,082	\$10,712	\$32,896	\$19,514	\$52,939	1.4%	75.7
260209*	Sewer Rehabilitation and Repair	Project Execution - Construction	2021	\$4	\$5,671	\$6,850	\$6,266	\$6,234	\$0	\$0	\$0	\$19,350	\$25,025	0.68%	N/A
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities	Project Execution - Construction	2017	\$3,762	\$6,958	\$7,804	\$7,782	\$0	\$0	\$0	\$0	\$15,586	\$26,305	0.72%	79
216011	WRRF Structural Improvements	Active - Procurement - Negotiation Phase - Design	2020	\$25	\$2,614	\$3,168	\$3,159	\$3,159	\$3,030	\$0	\$0	\$12,517	\$15,156	0.41%	64.4
270004	Oakwood and Leib CSO Facilities Improvement Project	Active - Procurement - Board Approved - Design	2020	\$70	\$1,757	\$2,183	\$1,316	\$2,675	\$3,066	\$3,074	\$2,411	\$12,314	\$16,552	0.45%	79.4
277001	Baby Creek Outfall Improvements Project	Active - Procurement - Negotiation Phase - Construction	2019	\$1,552	\$2,510	\$3,199	\$3,190	\$3,190	\$2,194	\$0	\$0	\$11,772	\$15,835	0.43%	80.1
270006	CSO Facilities Improvements II	Active - Procurement - Design	2021	\$60	\$453	\$886	\$562	\$19	\$2,398	\$5,139	\$5,280	\$9,005	\$14,797	0.4%	61
260600	CSO FACILITIES IMPROVEMENT PROGRAM	Project Execution - Design	2017	\$0	\$916	\$2,111	\$1,604	\$1,604	\$1,604	\$1,609	\$1,020,742	\$8,533	\$1,030,191	28%	N/A
213006	WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities	Active - Procurement - Design	2016	\$297	\$192	\$1,050	\$413	\$1,604	\$2,182	\$1,919	\$0	\$7,168	\$7,657	0.21%	76.6
260200	Sewer and Interceptor Rehabilitation Program	Project Execution - Construction	2013	\$0	\$0	\$17	\$17	\$17	\$1,972	\$4,910	\$12,184	\$6,933	\$19,117	0.52%	N/A

CIPNumber	Title	Project_ Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
260210*	Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee	Active - Procurement - Design	2022	\$0	\$1,217	\$1,470	\$1,466	\$1,466	\$1,466	\$38	\$30,113	\$5,904	\$37,235	1%	N/A
260207*	Rehabilitation of Woodward Sewer Systems	Project Execution - Construction	2021	\$3,577	\$10,942	\$5,784	\$0	\$0	\$0	\$0	\$0	\$5,784	\$20,303	0.55%	N/A
260802*	2022 WRRF Roof Improvements Project	Project Execution - Design	2023	\$45	\$174	\$2,338	\$2,289	\$0	\$0	\$0	\$0	\$4,627	\$4,845	0.13%	N/A
260619*	Control System Upgrade - St Aubin, Lieb & Mile	Active - Procurement - Board Approved - Design	2017	\$63	\$2,949	\$3,562	\$998	\$0	\$0	\$0	\$0	\$4,561	\$7,573	0.21%	N/A
260508*	B-39 Outfall Rehabilitation	Project Execution - Construction	2021	\$873	\$5,094	\$4,370	\$0	\$0	\$0	\$0	\$0	\$4,370	\$10,337	0.28%	N/A
260205*	NWI Rehabilitation	Project Execution - Construction	2021	\$335	\$3,348	\$4,041	\$11	\$0	\$0	\$0	\$0	\$4,052	\$7,734	0.21%	N/A
260614*	Structural Inspection & Structural Improvements	Project Execution - Construction	2017	\$7,202	\$3,088	\$2,433	\$1,245	\$0	\$0	\$0	\$0	\$3,678	\$13,967	0.38%	N/A
260903*	WRRF Front Entrance Rehabilitation	Project Execution - Design	2021	\$137	\$405	\$2,467	\$991	\$0	\$0	\$0	\$0	\$3,458	\$4,000	0.11%	N/A
270003	Long Term CSO Control Plan	Project Execution - Design	2019	\$4,818	\$4,497	\$2,345	\$947	\$0	\$0	\$0	\$0	\$3,292	\$12,607	0.34%	88
260904*	WRRF 3rd Floor Renovation	Active - Procurement - Design	2022	\$3	\$174	\$13	\$409	\$2,139	\$682	\$0	\$0	\$3,243	\$3,421	0.093%	N/A
260800	WRRF ROOF REPLACEMENT FOR MULTIPLE FACILITIES PROGRAM	Project Execution - Design	2018	\$0	\$0	\$0	\$0	\$0	\$519	\$2,222	\$12,092	\$2,741	\$14,833	0.4%	N/A
232001	Fairview Pumping Station - Replace Four Sanitary Pumps	Project Execution - Construction	2011	\$38,787	\$4,840	\$2,497	\$0	\$0	\$0	\$0	\$0	\$2,497	\$46,124	1.3%	63.6
260900	WRRF Facility Optimization Program	Project Execution - Design	2021	\$0	\$43	\$52	\$52	\$52	\$52	\$2,187	\$83,333	\$2,395	\$85,771	2.3%	N/A

CIPNumber	Title	Project_ Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
260905*	WRRF Plumbing Shop Renovation - 260905	Project Execution - Design	2022	\$0	\$78	\$1,586	\$525	\$0	\$0	\$0	\$0	\$2,111	\$2,189	0.06%	N/A
260901*	Rehabilitation of HAZMAT Facility at WRRF	Active - Procurement - Construction	2022	\$227	\$21	\$1,412	\$698	\$0	\$0	\$0	\$0	\$2,110	\$2,359	0.064%	N/A
260702*	Pump Station Assets Updates	Active - Pre- Procurement - Construction	2022	\$0	\$0	\$0	\$0	\$0	\$1,006	\$1,008	\$8,051	\$2,014	\$10,065	0.27%	N/A
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System	Project Execution - Design	2017	\$202	\$307	\$40	\$40	\$40	\$1,176	\$490	\$20,436	\$1,785	\$22,729	0.62%	76.6
260201*	CON-149, Emergency Sewer Repair	Project Execution - Construction	2013	\$34,925	\$4,154	\$1,298	\$216	\$0	\$0	\$0	\$0	\$1,514	\$40,593	1.1%	N/A
211008	WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines	Project Execution - Construction	2017	\$5,488	\$5,735	\$1,459	\$0	\$0	\$0	\$0	\$0	\$1,459	\$12,682	0.35%	78.3
260902*	WRRF 4th Floor Renovation	Project Execution - Construction	2021	\$65	\$2,204	\$1,031	\$0	\$0	\$0	\$0	\$0	\$1,031	\$3,299	0.09%	N/A
260623*	CSO Baby Creek Screen Rehabilitation	Project Execution - Construction	2021	\$23	\$1,449	\$921	\$0	\$0	\$0	\$0	\$0	\$921	\$2,393	0.065%	N/A
260700	Sewer System Infrastructure Improvements and Pumping Stations	Project Execution - Design	2017	\$0	\$40	\$49	\$49	\$49	\$49	\$49	\$742	\$243	\$1,025	0.028%	N/A
211002	WRRF PS No. 2 Pumping Improvements - Phase 1	Project Execution - Construction	2003	\$2,634	\$956	\$137	\$0	\$0	\$0	\$0	\$0	\$137	\$3,728	0.1%	N/A
213007	WRRF Modification to Incinerator Sludge Feed Systems at Complex -II	Project Execution - Construction	2016	\$21,789	\$2,276	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$24,065	0.66%	96.2
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF	Project Execution - Construction	2010	\$6,339	\$2,003	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$8,342	0.23%	94.7
222001	Oakwood District Intercommunity Relief Sewer Modification at Oakwood District	Project Execution - Design	2014	\$1,813	\$547	\$0	\$0	\$0	\$0	\$0	\$79,069	\$0	\$81,428	2.2%	62.7

CIPNumber	Title	Project_ Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
260603*	Conner Creek CSO RTB Automation Improvements	Pending Closeout	2017	\$7,741	\$242	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,984	0.22%	N/A
260618*	Oakwood HVAC Project	Project Execution - Construction	2017	\$4,850	\$1,982	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$6,832	0.19%	N/A
260620*	Baby Creek Roof Replacement	Pending Closeout	2021	\$611	\$441	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,052	0.029%	N/A
260622*	CSO Emergency Generator Improvements	Project Execution - Construction	2021	\$95	\$1,155	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,250	0.034%	N/A
270001	Pilot CSO Netting Facility	Active - Pre- Procurement - Design	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$35,034	\$0	\$35,034	0.95%	89.6
276002	Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility	Project Execution - Construction	2022	\$8	\$305	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$313	0.0085%	92.5

WASTEWATER CIP PROJECTS: FUTURE PLANNED, RANKED BY PRIORITIZATION SCORE

Financial figures are in thousands of dollars (\$1,000's)

Score Note: * Denotes a CIP project that is a Program. For projects with no score, see Appendices for PM Scores

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP	RC SCORE
211010	Rehabilitation of Sludge Processing Complexes A and B	Future Planned - Within 5 Year Plan	2019	\$94	\$0	\$0	\$0	\$1,685	\$768	\$3,930	\$15,627	\$6,383	\$22,104	0.6%	89.7
212010	WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite	Future Planned - Ten-Year CIP	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$6,232	\$0	\$6,232	0.17%	89.7
270002	Meldrum Sewer Diversion and VR-15 Improvements	Future Planned - Within 5 Year Plan	2019	\$0	\$0	\$0	\$0	\$0	\$936	\$1,641	\$3,277	\$2,577	\$5,854	0.16%	88.7
233003	Rouge River In-system Storage Devices	Future Planned - Within 5 Year Plan	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$46,436	\$0	\$46,436	1.3%	88.2
213009	WRRF Biosolids Processing Improvements	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$0	\$642	\$1,436	\$1,439	\$195,907	\$3,517	\$199,423	5.4%	79.6
211011	WRRF PS1 Screening and Grit Improvements	Future Planned - Ten-Year CIP	2019	\$0	\$529	\$1,637	\$1,633	\$600	\$49	\$1,509	\$92,135	\$5,429	\$98,092	2.7%	77.5
211005	WRRF PS No. 2 Improvements Phase II	Future Planned - Within 5 Year Plan	2014	\$15	\$454	\$1,637	\$4,187	\$2,454	\$42	\$42	\$69,459	\$8,363	\$78,290	2.1%	77.4
212009	WRRF Aeration Improvements 3 and 4	Future Planned - Ten-Year CIP	2019	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$69,528	\$0	\$69,528	1.9%	76.3
270008	Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$59	\$324	\$324	\$163	\$6,200	\$870	\$7,070	0.19%	74.4
277002	Baby Creek CSO Facility Influent Flushing System	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$745	\$0	\$745	0.02%	72.3
270014	Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$39	\$4,443	\$39	\$4,482	0.12%	72
270011	HVAC Improvements at Conner Creek and Belle Isle CSO Facilities	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$418	\$0	\$418	0.011%	70.5
222008	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure	Future Planned - Within 5 Year Plan	2023	\$0	\$2,479	\$2,521	\$0	\$0	\$0	\$0	\$0	\$2,521	\$5,000	0.14%	63.9
232004	CONDITION ASSESSMENT AT BLUE HILL PUMP STATION	Future Planned - Within 5 Year Plan	2019	\$0	\$258	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$258	0.007%	60.6
213008	WRRF Rehabilitation of the Ash Handling Systems	Future Planned - Within 5 Year Plan	2017	\$151	\$0	\$0	\$0	\$549	\$549	\$85	\$5,851	\$1,182	\$7,184	0.2%	59.5

CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond		Project Total	Percent of W/S CIP	RC SCORE
270012	Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$0	\$0	\$65	\$337	\$5,573	\$402	\$5,975	0.16%	59
270010	HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$16	\$86	\$85	\$91	\$500	\$746	\$777	\$1,522	0.041%	57.8
270007	Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CSO Facilities	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$201	\$1,081	\$1,081	\$1,084	\$4,842	\$3,449	\$8,291	0.23%	57
270013	Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities	Future Planned - Ten-Year CIP	2021	\$0	\$0	\$0	\$0	\$0	\$0	\$18	\$884	\$18	\$902	0.025%	56.8
270009	Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$0	\$0	\$15	\$78	\$1,296	\$94	\$1,390	0.038%	54.6
273002	CSO Hubbell Southfield VR-8 Gate Improvements	Future Planned - Within 5 Year Plan	2021	\$0	\$0	\$0	\$0	\$0	\$20	\$101	\$1,665	\$120	\$1,786	0.049%	50.2
260500	CSO Outfall Rehabilitation	Future Planned - Within 5 Year Plan	2017	\$0	\$0	\$0	\$0	\$1,513	\$1,513	\$1,517	\$10,594	\$4,542	\$15,136	0.41%	N/A
261000	WRRF Rehabilitation of the Secondary Clarifiers	Future Planned - Within 5 Year Plan	2017	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$39,337	\$0	\$39,337	1.1%	N/A
261001*	WRRF Rehabilitation of the Secondary Clarifiers Phase 1	Future Planned - Within 5 Year Plan	2017	\$0	\$597	\$161	\$242	\$242	\$2,474	\$2,948	\$12,275	\$6,069	\$18,941	0.52%	N/A

WASTEWATER CIP PROJECT TOTALS

Financial figures are in thousands of dollars (\$1,000's)

Title	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total	Percent of W/S CIP
Active Wastewater Projects Total	\$218,772	\$138,290	\$180,582	\$179,937	\$154,444	\$123,830	\$97,556	\$1,803,594	\$736,349	\$2,897,005	79%
Future Planned Wastewater Projects Total	\$261	\$5,534	\$7,442	\$7,875	\$10,640	\$10,828	\$15,470	\$623,582	\$52,255	\$681,632	19%
Listed as Cancelled/Closed/Reclassified	\$83,661	\$2,253	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$85,914	2.3%
Pending Closeout Wastewater Projects Total	\$8,352	\$683	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$9,035	0.25%
Total	\$311,046	\$146,760	\$188,024	\$187,812	\$165,085	\$134,658	\$113,026	\$2,427,176	\$788,604	\$3,673,587	100%

3.6. CENTRALIZED SERVICES PROJECTS

All financial figures are in thousands of dollars (\$1,000's). The planned spend column denotes whether this item is funded by the Water (W) or Wastewater (S). The Project Status column shows which projects are Active (A), Future Planned (FP), or Pending Closeout (PC). Projects that have been Reclassified to a different number, Closed, or Cancelled are not shown in this list; a list of Closed projects can be found in Section 2.2

CENTRALIZED SERVICES CIP PROJECTS

Financial figures are in thousands of dollars (\$1,000's)

CIP Budget	CIPNumber	Title	Project_Status	Year_ Added	Lifetime Actual Thru FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029 & Beyond	2024-2028 CIP Total	Project Total
Wastewater	341002	Security Infrastructure Improvements for Wastewater Facilities	Closed	2019	\$2,345	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,363
Water	341001	Security Infrastructure Improvements on Water Facilities	Closed	2019	\$5,258	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,259
Water	380700	As-Needed Geotechnical and Related Engineering Services	Project Execution - Design	2006	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Water	381000	Power Quality: Electric Metering Improvement Program	Active - Pre- Procurement - Design	2016	\$0	\$489	\$1,069	\$1,066	\$0	\$0	\$0	\$0	\$2,135	\$2,624
Water	383300	Masonry Replacement and Rehabilitation Program	Future Planned - Ten- Year CIP	2020	\$0	\$0	\$0	\$0	\$0	\$0	\$23	\$24,977	\$23	\$25,000

Note: CIP Number 380700 Contract was exhausted in 2021

CIP PROJECTS BY CATEGORY 3.6. CENTRALIZED SERVICES CIP PROJECTS

3.7. TEN-YEAR WATER OUTLOOK

In this section, you will find ten-year outlooks for CIP projects. These ten-year outlooks rely heavily on input from long-term needs assessments, master plans, and condition assessment documents. The planning horizon for these outlooks extend from FY2023 through FY2032. Projects within the 2024-2028 CIP that carry over into the FY2028+ are shown within the following tables by the anticipated fiscal year in which projected expenditures are anticipated.

Only project-level data will be provided within these outlooks. These are subject to change and are based upon the best available data at the time of compiling this report. The primary source of longerterm projects used for the 10-Year Water Outlook are from the 2015 Water Master Plan. In addition, it is anticipated that most programs will continue into the ten-year horizon. The project-level data can be seen below. In addition, a graphical representation of this summary is shown below.

WATER 10-YEAR OUTLOOK PROJECTS

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024- 2028	Total FY 2029- 2033	Total FY 2024- 2033
111001	Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements	\$141,373	\$2,966	\$618	\$2,910	\$6,291	\$24,242	\$13,770	\$28,079	\$24,016	\$18,120	\$17,442	\$0	\$47,831	\$87,657	\$135,489
111006	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements	\$40,350	\$1,018	\$1,237	\$9,567	\$9,590	\$9,590	\$8,066	\$0	\$0	\$0	\$0	\$0	\$38,050	\$0	\$38,050
111008	Lake Huron Water Treatment Plant, Architectural Programming for Laboratory and Admin Building Improvements	\$782	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
111009	Lake Huron Water Treatment Plant - High Lift Pumping, Water Production Flow Metering and Yard Piping Improvements	\$31,153	\$9,526	\$12,243	\$6,325	\$25	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$18,593	\$0	\$18,593
111010	Filtration Improvements	\$58,639	\$0	\$0	\$0	\$0	\$0	\$1,217	\$1,217	\$1,582	\$13,591	\$13,628	\$13,591	\$1,217	\$43,608	\$44,825
111011	Lake Huron WTP Pilot Plant	\$3,268	\$1,031	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
111012	LHWTP-Flocculation Improvements	\$51,331	\$1,700	\$6,702	\$12,006	\$12,006	\$12,006	\$6,447	\$0	\$0	\$0	\$0	\$0	\$49,168	\$0	\$49,168
112003	Northeast Water Treatment Plant High-Lift Pumping Station Improvements	\$172,269	\$613	\$2,764	\$2,756	\$11,654	\$10,415	\$10,443	\$10,415	\$10,415	\$13,715	\$13,743	\$958	\$38,032	\$49,245	\$87,277
112006	Northeast Water Treatment Plant Flocculator Replacements	\$13,382	\$2,389	\$2,876	\$2,868	\$2,868	\$2,048	\$0	\$0	\$0	\$0	\$0	\$0	\$10,660	\$0	\$10,660
112007	NEWTP-Header Galleries and Washwater Building Structural Repair	\$6,685	\$0	\$140	\$2,178	\$2,178	\$2,178	\$12	\$0	\$0	\$0	\$0	\$0	\$6,685	\$0	\$6,685
113003	Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements	\$184,285	\$0	\$0	\$0	\$0	\$0	\$0	\$2,178	\$2,184	\$2,184	\$2,190	\$2,184	\$0	\$10,920	\$10,920
113006	Southwest Water Treatment Plant Chlorine Scrubber, Raw Water Screens & Related Improvements	\$7,628	\$5,132	\$14	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$14	\$0	\$14
113007	Southwest Water Treatment Plant Architectural and Building Mechanical Improvements	\$8,641	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1 111

CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024- 2028	Total FY 2029- 2033	Total FY 2024- 2033
113009	SW Flight and Chain Upgrades	\$3,027	\$1,435	\$1,592	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,592	\$0	\$1,592
114002	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	\$303,261	\$4,819	\$17,896	\$27,906	\$27,421	\$36,116	\$28,505	\$23,839	\$23,303	\$23,303	\$23,367	\$14,773	\$137,843	\$108,586	\$246,429
114005	Springwells Water Treatment Plant, Administration Building Improvements & Underground Fire Protection Loop	\$6,694	\$21	\$20	\$20	\$20	\$20	\$20	\$20	\$2,130	\$2,130	\$1,079	\$0	\$102	\$5,359	\$5,461
114007	Springwells Water Treatment Plant Powdered Activated Carbon System Improvements	\$4,034	\$0	\$0	\$0	\$0	\$0	\$6	\$632	\$907	\$2,489	\$0	\$0	\$6	\$4,028	\$4,034
114008	Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements	\$14,116	\$2,339	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
114010	Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements	\$218,799	\$286	\$0	\$0	\$0	\$0	\$0	\$11,353	\$22,933	\$38,290	\$41,129	\$53,841	\$0	\$167,547	\$167,547
114011	Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements	\$27,987	\$2,632	\$1,133	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,133	\$0	\$1,133
114016	Springwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete Pavement Replacement	\$1,590	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
114017	Springwells Water Treatment Plant Flocculator Drive Replacements	\$25,355	\$3,280	\$7,910	\$7,888	\$5,381	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$21,179	\$0	\$21,179
114018	Springwells Water Treatment Plant - Service Building Electrical Substation and Miscellaneous Improvements	\$2,341	\$0	\$0	\$0	\$0	\$0	\$133	\$1,608	\$599	\$0	\$0	\$0	\$133	\$2,207	\$2,341
115001	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	\$56,073	\$10,275	\$9,019	\$8,995	\$8,995	\$6,752	\$0	\$0	\$0	\$0	\$0	\$0	\$33,761	\$0	\$33,761
115005	WWP WTP Building Ventilation Improvements	\$16,541	\$4,379	\$5,274	\$5,259	\$865	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$11,398	\$0	\$11,398
115006	Water Works Park Site/Civil Improvements	\$5,896	\$0	\$0	\$0	\$0	\$0	\$382	\$526	\$2,494	\$2,494	\$0	\$0	\$382	\$5,514	\$5,896
115007	Water Works Park High Lift Pumping Station Modernization	\$115,090	\$0	\$0	\$0	\$0	\$0	\$2,012	\$2,007	\$2,007	\$2,007	\$10,929	\$20,364	\$2,012	\$37,313	\$39,325
115009	Water Works Park Sedimentation Basins Structural Upgrades	\$16,846	\$0	\$0	\$0	\$0	\$0	\$1,664	\$5,349	\$5,349	\$4,484	\$0	\$0	\$1,664	\$15,182	\$16,846
116002	Pennsylvania and Springwells Raw Water Supply Tunnel Improvements	\$99,063	\$15,013	\$16,052	\$11,885	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$27,937	\$0	\$27,937
116005	Belle Isle Seawall Rehabilitation	\$1,175	\$455	\$719	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$719	\$0	\$719
116006	Belle Isle Intake System Rehabilitation and Improvements	\$2,222	\$0	\$0	\$0	\$0	\$0	\$712	\$706	\$402	\$402	\$0	\$0	\$712	\$1,510	\$2,222
116007	System Electrical Power Improvements	\$4,010	\$1,978	\$2,032	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,032	\$0	\$2,032
122003	Water Works Park to Northeast Transmission Main	\$290,882	\$16,747	\$2,812	\$2,804	\$2,804	\$2,804	\$2,812	\$148	\$148	\$148	\$148	\$148	\$14,037	\$741	\$14,777
122004	96-inch Water Transmission Main Relocation and Isolation Valve Installations	\$262,220	\$38,052	\$78,841	\$59,315	\$20,773	\$20,773	\$23,888	\$4,358	\$0	\$0	\$0	\$0	\$203,589	\$4,358	\$207,947
122005	Schoolcraft Road Water Transmission Main	\$17,045	\$2,313	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
122006	Wick Road Water Transmission Main	\$25,870	\$3,362	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
122007	Merriman Road Water Transmission Main Loop	\$26,209	\$0	\$0	\$0	\$0	\$0	\$1,008	\$1,006	\$323	\$4,339	\$4,880	\$4,867	\$1,008	\$15,414	\$16,423
122011	Park-Merriman Road Water Transmission Main	\$11,564	\$3,195	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
122013	14 Mile Transmission Main Loop	\$115,502	\$52,234	\$34,589	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$34,589	\$0	\$34,589
122016	Downriver Transmission Main Loop	\$67,502	\$287	\$10,814	\$10,784	\$10,784	\$10,784	\$10,814	\$10,784	\$0	\$0	\$0	\$0	\$53,980	\$10,784	\$64,764
					·											

112 GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

CIP PROJECTS BY CATEGORY 3.7. TEN-YEAR WATER OUTLOOK

CIPNumber		Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024- 2028	Total FY 2029- 2033	Total FY 2024- 2033
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station	\$65,552	\$2,207	\$1,280	\$33	\$33	\$33	\$33	\$33	\$33	\$33	\$33	\$33	\$1,412	\$166	\$1,578
122018	Garland, Hurlbut, Bewick Water Transmission System Rehabilitation	\$35,422	\$3,270	\$3,118	\$34	\$34	\$34	\$34	\$34	\$34	\$34	\$34	\$34	\$3,253	\$169	\$3,423
122019	Jefferson Main Replacement Project	\$40,136	\$534	\$96	\$19,753	\$19,753	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$39,602	\$0	\$39,602
132007	Energy Management: Freeze Protection Pump Installation at Imlay Pump Station	\$5,747	\$3,783	\$859	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$859	\$0	\$859
132010	West Service Center Pumping Station - Reservoir, Reservoir Pumping, and Division Valve Upgrades	\$45,621	\$10,684	\$6,547	\$215	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$6,762	\$0	\$6,762
132012	Ypsilanti Booster Pumping Station Improvements	\$42,154	\$1,738	\$25	\$25	\$25	\$25	\$25	\$25	\$25	\$781	\$849	\$10,422	\$124	\$12,102	\$12,225
132014	Adams Road Pumping Station Improvements	\$61,759	\$0	\$0	\$0	\$0	\$0	\$1,264	\$1,261	\$1,261	\$1,594	\$14,996	\$13,767	\$1,264	\$32,878	\$34,142
132015	Newburgh Road Booster Pumping Station Improvements	\$45,690	\$60	\$36	\$36	\$36	\$36	\$36	\$5,643	\$9,828	\$9,828	\$9,855	\$9,801	\$182	\$44,954	\$45,136
132016	North Service Center Pumping Station Improvements	\$76,013	\$109	\$222	\$222	\$8,594	\$19,141	\$19,193	\$19,141	\$9,020	\$0	\$0	\$0	\$47,372	\$28,160	\$75,532
132018	Schoolcraft Pumping Station Improvements	\$24,691	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
132019	Wick Road Pumping Station Improvements	\$24,780	\$0	\$0	\$0	\$0	\$0	\$6	\$2,249	\$2,249	\$1,666	\$9,289	\$9,264	\$6	\$24,717	\$24,723
132020	Franklin Pumping Station Improvements	\$4,918	\$0	\$0	\$0	\$0	\$0	\$723	\$1,397	\$1,352	\$1,352	\$0	\$0	\$723	\$4,102	\$4,825
132021	Imlay Pumping Station Improvements	\$137,968	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$13,692	\$17,756	\$17,707	\$0	\$49,155	\$49,155
132022	Joy Road Pumping Station Improvements	\$39,857	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170109	GLWA-CS-187: FK Eng: Raw Water Intake	\$1,900	\$244	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170300	Water Treatment Plant Automation Program	\$23,317	\$0	\$0	\$0	\$0	\$0	\$0	\$6,219	\$6,821	\$6,821	\$3,457	\$0	\$0	\$23,317	\$23,317
170302	SW SCADA System Upgrade	\$8,311	\$7,170	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170303	Power Monitoring Installation for Water Treatment Plants	\$1,906	\$190	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170304	WWP Scada Infrastructure Upgrade	\$581	\$320	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170305	WWP SCADA Network Upgrade	\$7,542	\$0	\$0	\$0	\$0	\$0	\$0	\$4,714	\$2,828	\$0	\$0	\$0	\$0	\$7,542	\$7,542
170306	SPW SCADA PLC Network Upgrade	\$3,341	\$963	\$2,379	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,379	\$0	\$2,379
170307	NE SCADA Network Upgrade	\$3,112	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$593	\$2,519	\$0	\$0	\$0	\$3,112	\$3,112
170400	Water Transmission Improvement Program	\$32,175	\$0	\$0	\$0	\$0	\$0	\$557	\$574	\$556	\$556	\$558	\$556	\$557	\$2,801	\$3,358
170500	Transmission System Valve Rehabilitation and Replacement Program	\$32,969	\$0	\$1,617	\$1,612	\$1,612	\$3,261	\$3,270	\$3,261	\$3,261	\$3,261	\$3,270	\$3,257	\$11,371	\$16,309	\$27,680
170502	Transmission System Valve Rehabilitation and Replacement Program	\$5,654	\$8	\$9	\$9	\$9	\$9	\$0	\$0	\$0	\$0	\$0	\$0	\$37	\$0	\$37
170503	Transmission System Valve Replacement	\$18,490	\$14,597	\$730	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$730	\$0	\$730
170504	Transmission Mains Valves and Urgent	\$11,000	\$1,021	\$448	\$447	\$447	\$122	\$0	\$0	\$0	\$0	\$0	\$0	\$1,465	\$0	\$1,465
170600	Linear System Integrity Program	\$27,312	\$3	\$31	\$31	\$31	\$31	\$4,539	\$4,527	\$4,527	\$4,527	\$4,539	\$4,527	\$4,663	\$22,646	\$27,309
170601	Linear System Integrity Program	\$9,850	\$482	\$109	\$109	\$5,849	\$3,301	\$0	\$0	\$0	\$0	\$0	\$0	\$9,368	\$0	\$9,368
170800	System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation	\$127	\$12	\$14	\$14	\$14	\$14	\$14	\$14	\$14	\$14	\$0	\$0	\$72	\$43	\$115


CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024- 2028	Total FY 2029- 2033	Total FY 2024- 2033
170801	Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, Springwells Water Treatment Plant, And Southwest Water Treatment Plant	\$27,942	\$6,313	\$3,550	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,550	\$0	\$3,550
170802	Reservoir Inspection, Design, and Construction Management Services Phase II	\$47,175	\$3,067	\$12,333	\$12,299	\$12,299	\$7,177	\$0	\$0	\$0	\$0	\$0	\$0	\$44,108	\$0	\$44,108
170803	Reservoir Inspection, Design, and Construction Management Services Phase III	\$94,432	\$0	\$0	\$0	\$897	\$3,695	\$11,940	\$11,907	\$11,907	\$11,907	\$11,940	\$11,907	\$16,531	\$59,568	\$76,099
170900	Suburban Water Meter Pit Rehabilitation and Meter Replacement	\$28,108	\$0	\$0	\$0	\$0	\$2,027	\$4,027	\$2,752	\$2,752	\$2,752	\$2,759	\$2,752	\$6,055	\$13,766	\$19,821
170901	Suburban Water Meter Pit Rehabilitation and Meter Replacement	\$12,522	\$2,506	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170902	Brownstown Meter Pit	\$222	\$136	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
170904	Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II	\$16,000	\$0	\$3,205	\$3,196	\$3,196	\$3,196	\$3,205	\$0	\$0	\$0	\$0	\$0	\$16,000	\$0	\$16,000
171500	Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities	\$15,948	\$0	\$0	\$0	\$0	\$0	\$0	\$2,529	\$2,651	\$2,625	\$2,375	\$1,919	\$0	\$12,099	\$12,099
171502	Lake Huron and Southwest Roof Replacement	\$2,710	\$0	\$0	\$0	\$0	\$0	\$0	\$1,045	\$1,660	\$5	\$0	\$0	\$0	\$2,710	\$2,710
380700	As-Needed Geotechnical and Related Engineering Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
381000	Power Quality: Electric Metering Improvement Program	\$2,624	\$489	\$1,069	\$1,066	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,135	\$0	\$2,135
383300	Masonry Replacement and Rehabilitation Program	\$25,000	\$0	\$0	\$0	\$0	\$0	\$23	\$23	\$23	\$23	\$23	\$23	\$23	\$115	\$138

10 YEAR WATER CIP OUTLOOK

Financial figures are in thousands of dollars (\$1,000's)

		FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033
Program	\$504	\$2,731	\$2,723	\$1,657	\$5,333	\$12,431	\$19,899	\$20,604	\$20,579	\$16,981	\$13,034
*Project	\$246,887	\$250,243	\$209,845	\$172,827	\$174,498	\$148,372	\$151,671	\$139,580	\$171,106	\$193,288	\$183,661
Total	\$247,391	\$252,973	\$212,568	\$174,484	\$179,831	\$160,802	\$171,570	\$160,185	\$191,684	\$210,269	\$196,694

*Includes projects from programs



10-YEAR WATER CIP OUTLOOK

3.8. TEN-YEAR WASTEWATER OUTLOOK

In this section, you will find ten-year outlooks for CIP projects. These ten-year outlooks rely heavily on input from long-term needs assessments, master plans, and condition assessment documents. The planning horizon for these outlooks extend from FY2024 through FY2033. Projects within the 2024-2028 CIP that carry over into the FY2029+ are shown within the following tables by the anticipated fiscal year in which projected expenditures are anticipated. Only project level data will be provided within these outlooks. These are subject to change and are based upon the best available data at the time of compiling this report.

The primary source of long-term projects used for the 10-Year Wastewater Outlook are from the Regional Wastewater Master Plan Assessment and various condition assessments that have been performed. The project-level data used in the development of this outlook can be seen below. In addition, a graphical representation of this summary is shown below.

WASTEWATER 10-YEAR OUTLOOK PROJECTS

Financial figures are in thousands of dollars (\$1,000's)

CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024-2028	Total FY 2029-2033	Total FY 2024-2033
211002	WRRF PS No. 2 Pumping Improvements - Phase 1	\$3,728	\$956	\$137	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$137	\$0	\$137
211005	WRRF PS No. 2 Improvements Phase II	\$78,290	\$454	\$1,637	\$4,187	\$2,454	\$42	\$42	\$42	\$2,063	\$3,537	\$1,526	\$5,503	\$8,363	\$12,671	\$21,034
211006	WRRF PS No. 1 Improvements	\$92,065	\$5,495	\$16,017	\$13,722	\$13,722	\$13,722	\$13,760	\$9,299	\$313	\$0	\$0	\$0	\$70,943	\$9,612	\$80,555
211007	WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements	\$94,250	\$2,606	\$4,793	\$14,363	\$14,363	\$14,363	\$14,402	\$14,363	\$9,680	\$0	\$0	\$0	\$62,283	\$24,043	\$86,326
211008	WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines	\$12,682	\$5,735	\$1,459	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,459	\$0	\$1,459
211009	WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System	\$22,729	\$307	\$40	\$40	\$40	\$1,176	\$490	\$7,642	\$7,642	\$5,151	\$0	\$0	\$1,785	\$20,436	\$22,220
211010	Rehabilitation of Sludge Processing Complexes A and B	\$22,104	\$0	\$0	\$0	\$1,685	\$768	\$3,930	\$5,209	\$5,209	\$5,209	\$0	\$0	\$6,383	\$15,627	\$22,010
211011	WRRF PS1 Screening and Grit Improvements	\$98,092	\$529	\$1,637	\$1,633	\$600	\$49	\$1,509	\$1,505	\$1,505	\$4,880	\$21,119	\$21,061	\$5,429	\$50,070	\$55,499
212008	WRRF Aeration Improvements 1 and 2	\$77,582	\$2,374	\$10,877	\$10,848	\$10,848	\$10,848	\$10,877	\$10,848	\$9,094	\$0	\$0	\$0	\$54,297	\$19,942	\$74,239
212009	WRRF Aeration Improvements 3 and 4	\$69,528	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$751	\$4,570	\$0	\$5,322	\$5,322
212010	WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite	\$6,232	\$0	\$0	\$0	\$0	\$0	\$0	\$441	\$441	\$179	\$744	\$982	\$0	\$2,788	\$2,788
213006	WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities	\$7,657	\$192	\$1,050	\$413	\$1,604	\$2,182	\$1,919	\$0	\$0	\$0	\$0	\$0	\$7,168	\$0	\$7,168
213007	WRRF Modification to Incinerator Sludge Feed Systems at Complex -II	\$24,065	\$2,276	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
213008	WRRF Rehabilitation of the Ash Handling Systems	\$7,184	\$0	\$0	\$0	\$549	\$549	\$85	\$1,595	\$1,595	\$1,595	\$1,066	\$0	\$1,182	\$5,851	\$7,033

CIP PROJECTS BY CATEGORY 3.8. TEN-YEAR WASTEWATER OUTLOOK

CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024-2028	Total FY 2029-2033	Total FY 2024-2033
213009	WRRF Biosolids Processing Improvements	\$199,423	\$0	\$0	\$0	\$642	\$1,436	\$1,439	\$1,436	\$1,436	\$7,741	\$17,246	\$17,654	\$3,517	\$45,512	\$49,029
216004	Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF	\$8,342	\$2,003	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
216006	Assessment and Rehabilitation of WRRF yard piping and underground utilities	\$26,305	\$6,958	\$7,804	\$7,782	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$15,586	\$0	\$15,586
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station	\$63,975	\$3,509	\$2,707	\$19,518	\$19,518	\$17,058	\$0	\$0	\$0	\$0	\$0	\$0	\$58,801	\$0	\$58,801
216011	WRRF Structural Improvements	\$15,156	\$2,614	\$3,168	\$3,159	\$3,159	\$3,030	\$0	\$0	\$0	\$0	\$0	\$0	\$12,517	\$0	\$12,517
222001	Oakwood District Intercommunity Relief Sewer Modification at Oakwood District	\$81,428	\$547	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$22,547	\$22,609	\$22,547	\$0	\$67,703	\$67,703
222002	Detroit River Interceptor (DRI) Evaluation and Rehabilitation	\$113,560	\$12,711	\$12,623	\$12,589	\$11,261	\$164	\$2,225	\$4,297	\$4,297	\$4,297	\$4,309	\$2,508	\$38,863	\$19,707	\$58,570
222008	North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure	\$5,000	\$2,479	\$2,521	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,521	\$0	\$2,521
232001	Fairview Pumping Station - Replace Four Sanitary Pumps	\$46,124	\$4,840	\$2,497	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,497	\$0	\$2,497
232002	Freud & Conner Creek Pump Station Improvements	\$558,498	\$3,563	\$21,814	\$26,206	\$29,461	\$29,461	\$17,433	\$35,706	\$62,139	\$62,139	\$62,309	\$62,139	\$124,375	\$284,433	\$408,808
232004	CONDITION ASSESSMENT AT BLUE HILL PUMP STATION	\$258	\$258	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
233003	Rouge River In-system Storage Devices	\$46,436	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,761	\$0	\$1,761	\$1,761
260200	Sewer and Interceptor Rehabilitation Program	\$19,117	\$0	\$17	\$17	\$17	\$1,972	\$4,910	\$4,286	\$2,942	\$2,942	\$1,997	\$17	\$6,933	\$12,184	\$19,117
260201	CON-149, Emergency Sewer Repair	\$40,593	\$4,154	\$1,298	\$216	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,514	\$0	\$1,514
260204	Conveyance System Engineering Services-1802575	\$55,551	\$13,573	\$16,380	\$16,335	\$7,340	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$40,054	\$0	\$40,054
260205	NWI Rehabilitation	\$7,734	\$3,348	\$4,041	\$11	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,052	\$0	\$4,052
260206	Conveyance System Repairs (Sewers)	\$34,516	\$2,102	\$8,167	\$7,480	\$3,004	\$4,707	\$4,627	\$4,033	\$0	\$0	\$0	\$0	\$27,985	\$4,033	\$32,018
260207	Rehabilitation of Woodward Sewer Systems	\$20,303	\$10,942	\$5,784	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,784	\$0	\$5,784
260209	Sewer Rehabilitation and Repair	\$25,025	\$5,671	\$6,850	\$6,266	\$6,234	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$19,350	\$0	\$19,350
260210	Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee	\$37,235	\$1,217	\$1,470	\$1,466	\$1,466	\$1,466	\$38	\$3,757	\$15,058	\$11,298	\$0	\$0	\$5,904	\$30,113	\$36,017
260500	CSO Outfall Rehabilitation	\$15,136	\$0	\$0	\$0	\$1,513	\$1,513	\$1,517	\$1,513	\$1,513	\$1,513	\$1,517	\$1,513	\$4,542	\$7,568	\$12,111
260508	B-39 Outfall Rehabilitation	\$10,337	\$5,094	\$4,370	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,370	\$0	\$4,370
260510	Conveyance System Repairs (Outfalls)	\$35,662	\$1,178	\$4,876	\$9,297	\$11,797	\$6,699	\$912	\$0	\$0	\$0	\$0	\$0	\$33,581	\$0	\$33,581
260600	CSO FACILITIES IMPROVEMENT PROGRAM	\$1,030,191	\$916	\$2,111	\$1,604	\$1,604	\$1,604	\$1,609	\$1,106	\$1,106	\$1,106	\$1,106	\$1,106	\$8,533	\$5,528	\$14,061
260603	Conner Creek CSO RTB Automation Improvements	\$7,984	\$242	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
260614	Structural Inspection & Structural Improvements	\$13,967	\$3,088	\$2,433	\$1,245	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,678	\$0	\$3,678
260618	Oakwood HVAC Project	\$6,832	\$1,982	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
260619	Control System Upgrade - St Aubin, Lieb & Mile	\$7,573	\$2,949	\$3,562	\$998	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,561	\$0	\$4,561
260620	Baby Creek Roof Replacement	\$1,052	\$441	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

122 GLWA | CAPITAL IMPROVEMENT PLAN 2024-2028 DRAFT 1

CIP PROJECTS BY CATEGORY 3.8. TEN-YEAR WASTEWATER OUTLOOK

CIPNumber	Title	Lifetime Planned Spend	FY 2023	FY 2024		FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024-2028	Total FY 2029-2033	Total FY 2024-2033
260622	CSO Emergency Generator Improvements	\$1,250	\$1,155	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
260623	CSO Baby Creek Screen Rehabilitation	\$2,393	\$1,449	\$921	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$921	\$0	\$921
260700	Sewer System Infrastructure Improvements and Pumping Stations	\$1,025	\$40	\$49	\$49	\$49	\$49	\$49	\$123	\$158	\$178	\$159	\$123	\$243	\$742	\$985
260701	Conveyance System Infrastructure Improvements	\$57,929	\$11,237	\$16,997	\$13,829	\$9,829	\$3,797	\$0	\$0	\$0	\$0	\$0	\$0	\$44,451	\$0	\$44,451
260702	Pump Station Assets Updates	\$10,065	\$0	\$0	\$0	\$0	\$1,006	\$1,008	\$1,006	\$1,006	\$1,006	\$1,008	\$1,006	\$2,014	\$5,031	\$7,045
260800	WRRF ROOF REPLACEMENT FOR MULTIPLE FACILITIES PROGRAM	\$14,833	\$0	\$0	\$0	\$0	\$519	\$2,222	\$2,216	\$19	\$519	\$2,222	\$2,216	\$2,741	\$7,192	\$9,933
260802	2022 WRRF Roof Improvements Project	\$4,845	\$174	\$2,338	\$2,289	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,627	\$0	\$4,627
260900	WRRF Facility Optimization Program	\$85,771	\$43	\$52	\$52	\$52	\$52	\$2,187	\$4,334	\$4,334	\$4,334	\$4,346	\$4,334	\$2,395	\$21,684	\$24,079
260901	Rehabilitation of HAZMAT Facility at WRRF	\$2,359	\$21	\$1,412	\$698	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,110	\$0	\$2,110
260902	WRRF 4th Floor Renovation	\$3,299	\$2,204	\$1,031	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,031	\$0	\$1,031
260903	WRRF Front Entrance Rehabilitation	\$4,000	\$405	\$2,467	\$991	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,458	\$0	\$3,458
260904	WRRF 3rd Floor Renovation	\$3,421	\$174	\$13	\$409	\$2,139	\$682	\$0	\$0	\$0	\$0	\$0	\$0	\$3,243	\$0	\$3,243
260905	WRRF Plumbing Shop Renovation - 260905	\$2,189	\$78	\$1,586	\$525	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,111	\$0	\$2,111
261000	WRRF Rehabilitation of the Secondary Clarifiers	\$39,337	\$0	\$0	\$0	\$0	\$0	\$0	\$37	\$37	\$37	\$38	\$7,833	\$0	\$7,983	\$7,983
261001	WRRF Rehabilitation of the Secondary Clarifiers Phase 1	\$18,941	\$597	\$161	\$242	\$242	\$2,474	\$2,948	\$2,940	\$2,940	\$2,940	\$2,948	\$507	\$6,069	\$12,275	\$18,344
270001	Pilot CSO Netting Facility	\$35,034	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
270002	Meldrum Sewer Diversion and VR-15 Improvements	\$5,854	\$0	\$0	\$0	\$0	\$936	\$1,641	\$1,636	\$1,636	\$4	\$0	\$0	\$2,577	\$3,277	\$5,854
270003	Long Term CSO Control Plan	\$12,607	\$4,497	\$2,345	\$947	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,292	\$0	\$3,292
270004	Oakwood and Leib CSO Facilities Improvement Project	\$16,552	\$1,757	\$2,183	\$1,316	\$2,675	\$3,066	\$3,074	\$2,411	\$0	\$0	\$0	\$0	\$12,314	\$2,411	\$14,725
270006	CSO Facilities Improvements II	\$14,797	\$453	\$886	\$562	\$19	\$2,398	\$5,139	\$5,125	\$154	\$0	\$0	\$0	\$9,005	\$5,280	\$14,284
270007	Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CSO Facilities	\$8,291	\$0	\$0	\$201	\$1,081	\$1,081	\$1,084	\$530	\$1,171	\$1,719	\$1,422	\$0	\$3,449	\$4,842	\$8,291
270008	Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities	\$7,070	\$0	\$0	\$59	\$324	\$324	\$163	\$1,199	\$1,767	\$1,767	\$1,467	\$0	\$870	\$6,200	\$7,070
270009	Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities	\$1,390	\$0	\$0	\$0	\$0	\$15	\$78	\$76	\$88	\$455	\$456	\$221	\$94	\$1,296	\$1,390
270010	HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities	\$1,522	\$0	\$16	\$86	\$85	\$91	\$500	\$498	\$247	\$0	\$0	\$0	\$777	\$746	\$1,522
270011	HVAC Improvements at Conner Creek and Belle Isle CSO Facilities	\$418	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$17	\$61	\$131	\$0	\$209	\$209
270012	Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities	\$5,975	\$0	\$0	\$0	\$0	\$65	\$337	\$329	\$372	\$1,958	\$1,963	\$950	\$402	\$5,573	\$5,975
270013	Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities	\$902	\$0	\$0	\$0	\$0	\$0	\$18	\$91	\$57	\$296	\$296	\$143	\$18	\$884	\$902
	Facility Improvements at Puritan Fenkell and Seven		\$0	\$0	\$0	\$0	\$0	\$18	\$91						\$884	- 1

CIP PROJECTS BY CATEGORY 3.8. TEN-YEAR WASTEWATER OUTLOOK


CIPNumbe	r Title	Lifetime Planned Spend	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033	Total FY 2024-2028	Total FY 2029-2033	Total FY 2024-2033
270014	Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities	\$4,482	\$0	\$0	\$0	\$0	\$0	\$39	\$205	\$205	\$101	\$772	\$1,120	\$39	\$2,405	\$2,444
273001	Hubbell Southfield CSO Facility Improvements	\$52,939	\$104	\$228	\$2,971	\$2,521	\$3,082	\$10,712	\$10,769	\$10,769	\$10,769	\$590	\$0	\$19,514	\$32,896	\$52,410
273002	CSO Hubbell Southfield VR-8 Gate Improvements	\$1,786	\$0	\$0	\$0	\$0	\$20	\$101	\$98	\$113	\$585	\$586	\$284	\$120	\$1,665	\$1,786
276002	Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility	\$313	\$305	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
277001	Baby Creek Outfall Improvements Project	\$15,835	\$2,510	\$3,199	\$3,190	\$3,190	\$2,194	\$0	\$0	\$0	\$0	\$0	\$0	\$11,772	\$0	\$11,772
277002	Baby Creek CSO Facility Influent Flushing System	\$745	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$15	\$0	\$15	\$15

10-YEAR WASTEWATER CIP OUTLOOK

Financial figures are in thousands of dollars (\$1,000's)

	FY 2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	FY 2031	FY 2032	FY 2033
Program	\$999	\$2,229	\$1,722	\$3,235	\$5,708	\$12,494	\$13,616	\$10,109	\$10,629	\$11,384	\$17,142
*Project	\$143,508	\$185,795	\$186,090	\$161,850	\$128,949	\$100,532	\$127,086	\$140,999	\$150,191	\$143,251	\$143,102
Total	\$144,507	\$188,024	\$187,812	\$165,085	\$134,658	\$113,026	\$140,701	\$151,108	\$160,820	\$154,635	\$160,245

*Includes projects from programs



10-YEAR WASTEWATER CIP OUTLOOK

CIP PROJECTS BY CATEGORY 3.8. TEN-YEAR WASTEWATER OUTLOOK

Placeholder for Image

О4 FINANCE



[Finance section coming in future draft]

[Finance section coming in future draft]

05 WATER PROJECTS

WATER PROJECTS



- 33 FUTURE PLANNED
- 46 ACTIVE
- 1 CLOSED
- 0 RECLASSIFIED




\$1.91 BILLION





FIND THE FULL BUSINESS CASE EVALUATIONS FOR WATER PROJECTS IN APPENDIX A.

tivity ID	Activity Name	· · · · · · · · · · · · · · · · · · ·	Remaining	Actual/Forecasted	Actual/Forecasted	2022	FY2023	FÝ2024	FY2025	FY2
			Duration	Start	Finish	FF	FFFF	FFFF	FFFF	FF
Water Proje	ects		6701	07-Dec-18 A	02-Nov-40			· · · ·		
111001: La	ake Huron Water Treatment Plant, Low-Lift, High Lift and Fi	Iter Backwash Pumping System Improvements	3654	16-Mar-20 A	30-Jun-32					
111006: La	ake Huron Water Treatment Plant, Filter Instrumentation an	d Raw Water Flow Metering Improvements	2134	15-Apr-22 A	02-May-28					-
111008: La	ake Huron Water Treatment Plant, Architectural Programmi	ng for Laboratory and Admin Building Improvements	922	22-Dec-31	30-Jun-34					
111009: La	ake Huron Water Treatment Plant - High Lift Pumping, Wate	er Production Flow Metering and Yard Piping Improve	920	26-Oct-20 A	04-Jan-25]	
111010: Fi	Itration Improvements		2894	04-Aug-26	06-Jul-34					
111011: La	ake Huron WTP Pilot Plant		397	03-Feb-21 A	31-Jul-23					
	HWTP-Flocculation Improvements		2023	29-Jan-21 A	12-Jan-28					
	ortheast Water Treatment Plant High-Lift Pumping Station I	mprovements	5359	31-Oct-22	02-Jul-37					
	ortheast Water Treatment Plant Flocculator Replacements		1723	08-Sep-20 A	18-Mar-27					
112007: N	EWTP-Header Galleries and Washwater Building Structure	al Repair	1828	01-Jul-22	02-Jul-27					
	12008: Northeast WTP Filter Rehab		3287	03-Jan-23	02-Jan-32					
	outhwest Water Treatment Plant, Low- and High-Lift Pumpir		2920	12-Jul-30	09-Jul-38	_				
	outhwest Water Treatment Plant Chlorine Scrubber, Raw W	-	367	26-Feb-20 A	01-Jul-23	-				
	outhwest Water Treatment Plant Architectural and Building	Mechanical Improvements	2161	01-Aug-32	01-Jul-38					
	WP Reservoir Replacement		2819	01-Jan-26	19-Sep-33	_				
	W Flight and Chain Upgrades		702	01-May-22 A	31-May-24	_				
	pringwells Water Treatment Plant, Low-Lift and High-Lift Pu		4749	11-Feb-20 A	30-Jun-35					
	pringwells Water Treatment Plant, Administration Building		3473	10-Aug-20 A	01-Jan-32					
	pringwells Water Treatment Plant Powdered Activated Carl		1432	30-Jul-27	30-Jun-31					
	pringwells Water Treatment Plant 1930 Sedimentation Bas		366	10-Aug-20 A	30-Jun-23					
	pringwells Water Treatment Plant, Yard Piping and High-Lif		5293	27-Mar-20 A	25-Dec-36	-				
	pringwells Water Treatment Plant Steam, Condensate Retu		496	01-Feb-19A	07-Nov-23					
	pringwells Water Treatment Plant 1958 Settled Water Cond		120	03-Jan-22 A	27-Oct-22					
	pringwells Water Treatment Plant Flocculator Drive Replac		1346	10-Aug-20 A	06-Mar-26					
	pringwells Water Treatment Plant - Service Building Electri		1197	05-Aug-26	13-Nov-29					
	Ater Works Park Water Treatment Plant Yard Piping, Valves	s and venturi meters Replacement	1736	19-Oct-20 A	31-Mar-27		1			
	WP WTP Building Ventilation Improvements		1157	29-Sep-20 A	29-Aug-25					
	Ater Works Park Site/Civil Improvements		1461	01-Jul-27	30-Jun-31	_				
	Ater Works Park High Lift Pumping Station Modernization		3915	01-Jul-26	19-Mar-37	-				
	Ater Works Park Sedimentation Basins Structural Upgrade		1737 1186	31-Jul-26 01-Apr-19 A	02-May-31					
	ennsylvania and Springwells Raw Water Supply Tunnel Im elle Isle Seawall Rehabilitation	provements	574	01-Sep-22	30-Jun-26 27-Mar-24					
	elle Isle Intake System Rehabilitation and Improvements		1461	01-Jul-27	30-Jun-31					
	ystem Electrical Power Improvements		551	04-May-22 A	01-Jan-24					
	Ater Works Park to Northeast Transmission Main		5907	01-Nov-19 A	31-Aug-38					
	6-inch Water Transmission Main Relocation and Isolation \	Valve Installations	2322	15-Jun-20 A	06-Nov-28					
	choolcraft Road Water Transmission Main		366	08-Oct-21 A	30-Jun-23		· · · ·			
	/ick Road Water Transmission Main		351	31-Aug-19 A	15-Jun-23					
	lerriman Road Water Transmission Main Loop		3259	02-Aug-26	04-Jul-35					
	ark-Merriman Road Water Transmission Main		64	27-Oct-22	29-Dec-22					
	4 Mile Transmission Main Loop		926	11-Aug-20 A	10-Jan-25					
	ownriver Transmission Main Loop		2558	01-Jun-20 A	30-Jun-29					
	Mile/Nevada Transmission Main Rehab and Carrie/Nevada	a Flow Control Station	6212	12-Mar-21 A	02-Jul-39					
	arland, Hurlbut, Bewick Water Transmission System Reha		5846	01-Dec-20 A	01-Jul-38					
	efferson Main Replacement Project		1462	29-Jun-21 A	30-Jun-26					
	nergy Management: Freeze Protection Pump Installation at	t Imlay Pump Station	428	01-Jun-20 A	31-Aug-23					
	lest Service Center Pumping Station - Reservoir, Reservoir		744	01-Apr-21 A	12-Jul-24					
	psilanti Booster Pumping Station Improvements		4666	30-Jun-21 A	08-Apr-35					
	dams Road Pumping Station Improvements		3258	30-Jul-26	30-Jun-35					
	ewburgh Road Booster Pumping Station Improvements		4018	05-Feb-20 A	29-Jun-33					
	orth Service Center Pumping Station Improvements		2730	03-Dec-20 A	19-Dec-29					
	choolcraft Pumping Station Improvements		2135	02-Aug-33	06-Jun-39					
	lick Road Pumping Station Improvements		2160	02-Aug-27	30-Jun-33					
	+								1	
Constr		CIP 2024 - Integrated Master		- WTP Projects			Date: 12-Oct		Page	e 1 of 2
Design	Work In Progress	June 2022	Update			Data	Date: 30-Ju	า-22		



ity ID	Activity Name	Remaining	Actual/Forecasted		2022	FY2023	FY2024	FY2025	FY2
		Duration	Start	Finish	FF	FFFF	FFFF	FFFF	FF
132020	: Franklin Pumping Station Improvements	1699	05-Nov-26	30-Jun-31					
132021	: Imlay Pumping Station Improvements	2953	31 - May-30	30-Jun-38					
132022	: Joy Road Pumping Station Improvements	2684	29-Jun-33	02-Nov-40					
170109): GLWA-CS-187: FK Eng: Raw Water Intake	5	30-Jun-21 A	04-Jul-22					
170300	: Water Treatment Plant Automation Program	3653	01-Jul-23	30-Jun-33					
	2: SW SCADA System Upgrade	366	07-Jul-20 A	30-Jun-23					
170303	: Power Monitoring Installation for Water Treatment Plants	184	13-Jul-20 A	30-Dec-22		3			
170304	I: WWP Scada Infrastructure Upgrade	303	29-Apr-21 A	28-Apr-23	Þ				
170305	: WWP SCADA Network Upgrade	796	02-Dec-27	04-Feb-30					
170306	: SPW SCADA PLC Network Upgrade	581	04-May-22 A	31-Jan-24			₽		
170307	: NE SCADA Network Upgrade	589	15-Nov-29	26-Jun-31					
	: Water Transmission Improvement Program	3595	29-Aug-26	01-Jul-36					
170500	: Transmission System Valve Rehabilitation and Replacement Program	4749	01-Jul-23	30-Jun-36					
170502	: Transmission System Valve Rehabilitation and Replacement Program	1827	02-Jan-22 A	30-Jun-27					
170503	: Transmission System Valve Replacement	1827	01 - May-20 A	30-Jun-27			1		
170504	: Transmission Mains Valves and Urgent	1562	08-Oct-21 A	08-Oct-26			1		
170600	: Linear System Integrity Program	4019	30-Jun-22	30-Jun-33			1		
	: Linear System Integrity Program	1668	13-Feb-21 A	22-Jan-27			1		
170800	: System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation	3288	30-Jun-21 A	30-Jun-31					
170801	: Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, Spri	398	07-Dec-18 A	01-Aug-23					
170802	Reservoir Inspection, Design, and Construction Management Services Phase II	1675	06-Jun-22 A	29-Jan-27					
170803	: Reservoir Inspection, Design, and Construction Management Services Phase III	3731	27-Oct-24	13-Jan-35					
170900): Suburban Water Meter Pit Rehabilitation and Meter Replacement	4018	01-Jul-26	30-Jun-37					
170901	: Suburban Water Meter Pit Rehabilitation and Meter Replacement	180	21-Nov-22	19-May-23	[
170902	2: Brownstown Meter Pit	93	03-Feb-20 A	30-Sep-22					
170903	: NOT IN CIP	1591	24-Sep-22	31-Jan-27					
170904	: Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II	2193	06-Apr-21 A	30-Jun-28					
171500	Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities	2924	01-Jul-27	02-Jul-35					
171502	: Lake Huron and Southwest Roof Replacement	854	29-Feb-28	01-Jul-30					
180000): Water Inflation Allowance	2192	01-Jul-22	30-Jun-28					
Water P	rojects - Centralized Services	5480	30-Jun-21 A	30-Jun-37					
341001	: Security Infrastructure Improvements on Water Facilities	90	30-Jun-21 A	27-Sep-22					
): As Nee de d Ge otec hni cal a nd Rel ated Enginee ring Se rvic es	91	02-Oct-21 A	28-Sep-22					
	: Power Quality: Electric Metering Improvement Program	1096	01-Jul-22	30-Jun-25					
383300	: Masonry Replacement and Rehabilitation Program	3653	01-Jul-27	30-Jun-37		1			

Construction Study	CIP 2024 - Integrated Master Schedule - WTP Projects	Run Date: 12-Oct-22	Page 2 of 2
Design Work In Progress	June 2022 Update	Data Date: 30-Jun-22	







Project Title: Masonry Replacement and Rehabilitation Program

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Centralized Services Class Lvl 2: General Purpose Class Lvl 3: General Purpose Lookup Location: Multiple Counties	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Douglas Atkinson Director: Paula Anderson	Project Score 0	
Problem Statement: Cracks and deterioration have been identified in masonry walls, exterior concrete, retaining walls, concrete decks and floor repair or replacement causing safety concerns. Repair or replacement is needed to address this deterioration	Scope of Work/Project Alternatives: For NE WTP: Analyze the movement and moisture penetration problem, rebuild portions of masonry and concrete walls, floors, roof parapets and deck elements. For SW WTP: Assess the panels and support structure, replace panels, repair or restore rusted steel members. For Imlay City: Remove or rebuild retaining walls to withstand soils pressure.	Other Important Info: Three sites have been identified for this project all have some failing concrete. 1)Northeast WTP 2)Southwest WTP 3) Imlay City Pumping Station

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

*Design & Construction costs are inclusive of salaries where salaries are not defined

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$230	\$0	\$0	\$0	\$0	\$23	\$23	\$115
TBD/Unallocated	\$24,770	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Repre	esentative Switchgear to be Replaced under CIP 111001
Project Engineer/Manager: Eric Kramp		Project Sco	re	
Director: Peter Fromm		79.7		
Problem Statement:	Scope of Work/Project	Alternatives:		Other Important Info:
This project addresses multiple issues at the LHWTP, primarily focused on electrical, pumpin and limited chemical feed system improvements		The project's so	ope of	*Innovation note: Ensure energy efficiency. Coordination between existing pumping unit and motor required during design. Critical speed

Improvements are needed to align the existing low lift pumping rate with the Lake Huron WTP production rate per the 2015 Water Master Plan Update. Currently, constant speed pumping at the low-lift portion of the plant can force it to operate in a semi-batch mode during night-time, low-demand periods. Existing electrical gear for low- and highlift pum...

or replacement of the following systems and equipment:

1. High and medium voltage electrical system

2. Low-lift pumps, to be right-sized to current and projected demands.

3. High-lift pumping units, right-sized to current and projected demands.

4. Filter wash water pumps and related equipment. 5. Phosphoric acid storage tanks and fill piping...

analysis may show the pump improvements needed to operate at reduced speeds. Developing an innovative rehabilitation design to minimize maintenance of existing drives.

This project will also replace the existing 60 MGD wash water "on-demand" system with an elevated tank system, decreasing the potential of filter upset by control loss.



Project Title: Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,307	\$121	\$121	\$102	\$121	\$121	\$121	\$121	\$121	\$603	\$482
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (1803769)	\$15,966	\$2,875	\$2,875	\$2,864	\$497	\$753	\$1,665	\$1,665	\$1,669	\$6,248	\$4,055
Construction (Build) # 1	\$9,000	\$0	\$0	\$0	\$0	\$2,037	\$4,506	\$2,457	\$0	\$9,000	\$0
Construction (Build) # 2	\$16,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,655	\$3,655	\$12,345
Construction (Build) # 3	\$77,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,856	\$7,856	\$69,144
Construction (Build) # 4	\$2,100	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$469	\$469	\$1,631
Construction (Build) # 5	\$20,000	\$0	\$0	\$0	\$0	\$0	\$0	\$20,000	\$0	\$20,000	\$0



Project Title: Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements

Project Status: Active - Procurement - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	WW Master Plan Water Master Plan Right Sizing	Great Lakes Water Authority		
Project Engineer/Manager: Eric Kramp	Project Score			
Director: Peter Fromm	60.5			
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:		
The filter instrumentation and raw water metering at the Lake Huron WTP is non functioning and is in need of replacement.	The Contract has been redeveloped to give full consideration to CS-108 guidelines.	Contract is being redeveloped for full integration with CS-108 guidelines.		

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$400	\$87	\$87	\$46	\$55	\$55	\$55	\$55	\$46	\$267	\$0
Professional Services	\$181	\$188	\$188	(\$7)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1771)	\$2,600	\$963	\$963	\$0	\$0	\$425	\$426	\$426	\$359	\$1,637	\$0
Design/Engineering (CS-1499)	\$44	\$44	\$44	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build (2101680)	\$37,125	\$0	\$0	\$979	\$1,182	\$9,087	\$9,108	\$9,108	\$7,661	\$36,146	\$0



Project Title: Lake Huron Water Treatment Plant, Raw Sludge Clarifier and Raw Sludge Pumping System Improvements

Project Status: Closed Class LvI 1: Water Class LvI 2: Treatment Plants and Facilities Class LvI 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Overall progress photo that shows new WWRB, JS1, JS2 and SPS 8/20/20
--	---	---

Project Engineer/Manager: Brian VanHall

Director: Peter Fromm

Problem Statement:

The existing Waste Wash Water Retention Basin (WWRB) and clarifiers have noticeable deteriorating concrete and walls that have permanently deflected. There is also concrete deterioration in the sludge pumping station as well as issues with maintenance and operation of the existing pumps. The existing pumps are not equipped with permanent lifting mechanisms. The new sludge pumping units will be equipped with permanent lifting mechanisms so that pumps can be pulled by plant staff without mobilizi...

Scope of Work/Project Alternatives:

This project will be delivered using a design-bidbuild project delivery method. GLWA retained an engineering consultant under GLWA Contract No. CS-171 "Raw Sludge Clarifiers and Raw Sludge Pumping Station Improvements" to conduct a condition assessment and design improvements for LH raw sludge handling. The WWRB, Clarifier Nos. 1 and 2, and the sludge pumping station all require improvement. The scope of construction involves:

Project Score

74.4

1. Demolish existing clarifiers and sludge pumping station

2. Con...

Other Important Info:

This project should be completed prior to cessation of treatment at the Northeast WTP.

Project History: The clarifier/backwash structure is original to the plant. The tank walls appear to have been inadequately designed and/or constructed to withstand the loading of the surrounding soils.

Challenges: Improvements will require coordination with plant operations (filter backwashing, sedimentation basin cleaning) and bypass pumping due to significant leakage from filter outlet valves.



Project Title: Lake Huron Water Treatment Plant, Raw Sludge Clarifier and Raw Sludge Pumping System Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$104	\$104	\$104	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$8	\$8	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-171)	\$1,556	\$1,502	\$1,502	\$54	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$7,254	\$7,254	\$7,254	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Lake Huron Water Treatment Plant, Architectural Programming for Laboratory and Admin Building Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Brian VanHall	Project Score	
Director: Peter Fromm	49.5	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The Lake Huron Water Treatment Plant started operating in 1976. The existing process control laboratory and administration building interiors and original construction, including flooring, wall coverings, doors, ceilings, lab cabinetry, control	This project will start with a study phase to determine the most efficient architectural layout that meets current process laboratory control technology and administrative workflow practices; and that can be provided through a construction	N/A

Current Expenses (All figures are in \$1,000's)

room boards, bathroom fixtures, and lighting

fixtures. The original control room board is still

located in the laboratory and consumes a large

The architectural layout of the laboratory and

administration...

amount of space that is not used and inefficient.

"Total Costs" include costs outside of the 10 year planning window

*Design & Construction costs are inclusive of salaries where salaries are not defined

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$775	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

renovation project within the existing building

area and interior/exterior doors.

footprint. Additional minor architectural needs will

be evaluated in the study phase that include stairs

from the exterior door down to the retention basin



Project Title: Lake Huron Water Treatment Plant - High Lift Pumping, Water Production Flow Metering and Yard Piping Improvements

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Conceptual new h/L pump arrangement
Project Engineer/Manager: Brian VanHall Director: Peter Fromm		Project Score 75.7	
	l		
Problem Statement:	Scope of Work/Project		Other Important Info:
Three new, smaller capacity, high-lift pumping u are needed to provide reduced finished water flo out of Lake Huron WTP to accommodate the relocation of the 96-inch transmission main sout of Dorsey-Dickenson valve and to accommodate the installation of a new water production flow meter at the Lake Huron WTP. The three, new smaller capacity high-lift pumping units will also serve a longer term need to better match lower diurnal demands seen at the Lake Huron WTP. Installation of the new w	project delivery method.involves designing and binvolves designing and bproduction flow meter arto more accurately measproduction flows from thealso entail constructing a	ouilding a new water ad associated meter vault sure finished water e facility. This work will additional high-lift, finished wes and appurtenances to the new metering	d

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$355	\$269	\$269	\$33	\$37	\$19	\$0	\$0	\$0	\$55	\$0
Professional Services (CS-272)	\$481	\$173	\$173	\$322	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-166)	\$295	\$60	\$60	\$61	\$74	\$74	\$25	\$0	\$0	\$173	\$0
Design-Build # 1	\$30,023	\$2,661	\$2,661	\$9,109	\$12,132	\$6,232	\$0	\$0	\$0	\$18,364	\$0 145



Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Eric Kramp	Project Score 77.4	
Director: Peter Fromm	17.4	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Significant issues exist in the filtration process of the Lake Huron WTP: Filter influent and drain valves do not seal well, creating water loss and burdening the solids handling system with more influent than necessa Filter underdrains have not been evaluated and require condition assessment. Filter media has lost considerable depth. Isolation valves between the filters, filtered water conduit, filter to drain, and clearwells currently le heavily	 build project delivery method. The scope of work will generally include the following: 1. Construct filtration improvements, including filter media, filter auxiliary scouring equipment, filter wash water troughs, and other filter tank work. 2. Replace the existing filter control valves and valve operators. 3. Rehabilitate concrete associated with the filters. 	n/a



Project Title: Filtration Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$527	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$75	\$75	\$376
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$7,058	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,142	\$1,142	\$4,755
Construction (Build) # 1	\$51,053	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$38,477



Project Title: Lake Huron WTP Pilot Plant

CIP Number: 111011

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Lake Huron WTP Pilot Plant - Process Flow Diagram
Project Engineer/Manager: Nichole Sajdak Director: John Norton	Project Score 50.7	
Problem Statement: Water Operations staff at Lake Huron would benefit from the ability to test potential changes existing water treatment practices and investiga new and innovative treatment advances.		he planning, construction and training. g

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$110	\$0	\$0	\$110	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (1904449)	\$3,157	\$2,332	\$2,332	\$921	\$0	\$0



Project Title: LHWTP-Flocculation Improvements

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Lake Huron Lookup Location: Lake Huron Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLANA Great Lakes Water Authority
Project Engineer/Manager: Eric Kramp Director: Peter Fromm	Project Sco 91.5	ore	

Problem Statement:

The flocculators at the Lake Huron Water Treatment Plant are non-functional. While the plant has been able to maintain water quality, the State of Michigan has identified this a serious issue. This project solves this problem and addresses other issues with the flocculation systems such as any found defects that in process and structure that are identified.

Scope of Work/Project Alternatives:

The project will be executed on a traditional design/bid/build delivery process. Design/build would be unsuitable as the selection of flocculation technology will be the primary driver of overall cost, and is unknown.

Other Important Info:

The contract will also correct a process defect in the plant, where a section of the station conduits can not be taken out of service without loss of the entire station. This will entail the construction of approximately 150 lineal feet of new parallel raw water conduit.

This project will also, if approved, separate the two flocculation and sedimentation basins into four, decreasing the impact of sediment upset on filter efficient and/or UFRB.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$462	\$9	\$9	\$73	\$84	\$84	\$84	\$84	\$45	\$382
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance	\$7,870	\$523	\$523	\$1,627	\$1,562	\$1,194	\$1,194	\$1,194	\$641	\$5,785
Construction (Build)	\$43,000	\$0	\$0	\$0	\$5,055	\$10,728	\$10,728	\$10,728	\$5,761	\$43,000



Project Title: Northeast Water Treatment Plant High-Lift Pumping Station Improvements

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Northeast Lookup Location: Northeast WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Corey Brech	Project Score	
Director: Peter Fromm	82.2	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Existing mechanical, electrical, instrumentation, and control system equipment within the high-lift pumping plant at the Northeast Water Treatment Plant is mostly original (i.e. 1956). The following are beyond their useful life. Both medium-voltage and low-voltage switchgear. (Stock replacement parts are no longer available. Medium-voltage switchgear cubicles are irrepairable. All medium-voltage cables are (especially with respect to insulation properties) Primary service transformers (being	 This project will be delivered using a design-bidbuild project delivery method. The scope of work generally includes: 1) Replace medium voltage switchgear, Unit Substation 1, all motor control centers (MCCs), power panels, transformers, and lighting panels. 2) Replace HL Pumps and size according to projected demands. 3) Replace pump motor controls to accommodate remote operation. 4) Replace primary transformers and test/replace feeders to property lines. Coordinate with DTE to ensure th 	na



Project Title: Northeast Water Treatment Plant High-Lift Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,149	\$30	\$30	\$0	\$80	\$80	\$80	\$80	\$80	\$400	\$399
Professional Services	\$1,120	\$510	\$510	\$613	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance (Electrical Service)	\$11,000	\$0	\$0	\$0	\$2,684	\$2,677	\$1,867	\$628	\$630	\$8,486	\$2,514
Design/Engineering (Non-Critical Electrical Service Changes)	\$11,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,479
Construction (Build) # 1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Electrical Service Change)	\$68,000	\$0	\$0	\$0	\$0	\$0	\$9,707	\$9,707	\$9,733	\$29,147	\$38,853
Construction (Non- Critical Electrical Service Changes)	\$80,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Northeast Water Treatment Plant Flocculator Replacements

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Northeast Lookup Location: Northeast Water Treatment Plant Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Brian VanHall	Project Score	e

82.4

Director: Peter Fromm

Problem Statement:

The existing flocculators are not operable and are beyond repair, which reduces sedimentation effectiveness and creates a greater load on the filtration process. The State of Michigan Department of Environment, Great Lakes & Energy (EGLE) noted the condition of the existing flocculators at the Northeast Water Treatment Plant as a deficiency in ELGE's 2021 Northeast Water Treatment Plant Sanitary Survey, dated March 4, 2021.

Scope of Work/Project Alternatives:

This CIP project is being delivered under a designbid-build project delivery method and generally includes the following scope of work: 1. Demolish and remove existing flocculators including drives, motors, shafts, paddle wheels, control panels, electrical service, and related appurtenances.

 Install a complete, new flocculation system designed to current industry standards.
 Construct new stairways and platforms to

improve access to the flocculator drive galleries.

Other Important Info:

Existing flocculators are original to the plant (circa 1956) and are (1) not operable, (2) beyond repair, and (3) do not provide present day flocculation mixing energies. The new flocculation system is designed to current and best industry standards for flocculation mixing energies, tapered flocculation, and is conducive to easier operation and maintenance.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$413	\$251	\$251	\$38	\$36	\$36	\$36	\$26	\$0	\$133	\$0
Professional Services (CS-272)	\$60	\$60	\$60	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-166)	\$210	\$31	\$31	\$33	\$40	\$40	\$40	\$26	\$0	\$146	\$0
Construction (Build) # 1	\$12,699	\$0	\$0	\$2,318	\$2,800	\$2,792	\$2,792	\$1,997	\$0	\$10,381	^{\$0}



Project Title: NEWTP-Header Galleries and Washwater Building Structural Repair

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Northeast Lookup Location: NA Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Govind Patel Director: Terry Daniel	Project Sco 95.2	core

Problem Statement:

The NEWTP was constructed in 1953 and consist largely of reinforced concrete frames and slabs. Deterioration due to water infiltration from the hatch covers and other cracks over time has weakened some structures and and resulted in corrosion to header, catwalks, and staircase.

Scope of Work/Project Alternatives:

The scope of the project includes repair of concrete beams with new reinforcement, CFRP shear wrap and crack injection, roof slab crack injection, and crack injection of the Plant North and South High Lift vault walls. It also includes replacing all the concrete Hatch covers with steel covers and surrounding curbs to prevent water entering the hatches, together with adding concrete topping to improve drainage by providing surface area drains.

Other Important Info:

Concrete debris fell from ceiling beams on catwalks and the south header pipe vault floor during the mid-night shift on March 13, 2021. No one injured, but this incident highlighted the risk to employee safety

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$60	\$0	\$0	\$0	\$15	\$15	\$15	\$15	\$0	\$60
Design/Engineering	\$625	\$0	\$0	\$0	\$125	\$166	\$166	\$166	\$1	\$625
Construction	\$6,000	\$0	\$0	\$0	\$0	\$1,996	\$1,996	\$1,996	\$11	\$6,000



Project Title: Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Southwest Lookup Location: Southwest WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside o Predecessor Project(s) 		GELVAA Great Lakes Water Authority
Project Engineer/Manager: Jacob Mangum Director: Peter Fromm		Project Score 52.4	

Problem Statement:

Most of the plant's process mechanical, building mechanical and electrical systems are original to the plant (circa1962) and are nearing or are past end of useful service life. As a result, additional plant maintenance effort is necessary to meet plant operational needs.

Scope of Work/Project Alternatives:

The work includes design and construction services for the replacement of numerous largediameter butterfly valves and water-control gates throughout the low-lift, high-lift, filtration, and flocculator buildings. The low- and high-lift pumping units, flocculators and filters will all be right sized taking into consideration the current and 20-year projected demands.

Other Important Info:

This work is included in the 2015 water master plan update. It also recommends that GLWA consider decommissioning treatment at the Southwest Water Treatment Plant if water demand continues to trend in a downward direction.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,657	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$826
Design & Construction Assistance # 1	\$35,328	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$10,094
Construction	\$147,300	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Southwest Water Treatment Plant Chlorine Scrubber, Raw Water Screens & Related Improvements

Project Status: Project Execution - Construction Class LvI 1: Water Class LvI 2: Treatment Plants and Facilities Class LvI 3: Southwest Lookup Location: Southwest WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(s) 	of Facilities		GLANA Great Lakes Water Authority
Project Engineer/Manager: Jacob Mangum		Project Sco	ore	
Director: Peter Fromm		90.6		

Problem Statement:

The existing chlorine gas scrubber is nearing its end of useful service life and its absorption media will be expiring within the next few years. Similarly, the existing raw water screening system is original to the plant (circa 1962), is not functional, and is beyond repair. As a result, this system also requires replacement. Both the chlorine gas scrubber and raw water screening systems will require ancillary equipment improvements related to electrical, alarms, instrumentation, and controls.

Scope of Work/Project Alternatives:

This project will be delivered using a design-build project delivery model. The existing gas chlorine scubber and raw water screens will be replaced with new system equipment meeting current building codes and industry best practices. The new gas chlorine scrubber and raw water screens will be designed for current and projected water demands in accordance with the recommendations of the 2015 Water Master Plan Update. The new equipment will be right-sized.

Other Important Info:

GLWA intends to use the services of AECOM under its CIP program management contract to implement this design-build project.

E. Klun 8/27/20 update as follows: 1. RFP for DB contract delivery underway by AECOM under CS-272 Task 71011A.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	5 Year Total
GLWA Salaries	\$159	\$116	\$116	\$47	\$0	\$0	\$0	\$0
Professional Services	\$629	\$211	\$211	\$445	\$1	\$0	\$0	\$1
Design/Engineering (Study)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1	\$6,840	\$3,107	\$3,107	\$4,640	\$12	\$0	\$0	\$12



Project Title: Southwest Water Treatment Plant Architectural and Building Mechanical Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Southwest Lookup Location: Southwest WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Shakil Ahmed	Project Score	
Director: Peter Fromm	38.7	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Most of the existing low- and high- lift pumping station and administration buildings' mechanical equipment (HVAC, dehumidification, plumbing) and architectural components such as doors, windows, floors, and furnishings, are over 50 year old and are beyond their normal useful service life Additional architectural improvements at Southwest Water Treatment Plant will include renovation of staff locker rooms and bathrooms, including a restroom for female staff.		CS-1528 water master plan update included these improvements.



Project Title: Southwest Water Treatment Plant Architectural and Building Mechanical Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$141	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$1,500	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$7,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Cancelled Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Southwest Lookup Location: SWP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Reservoir No. 3, Access door cut into side of reservoir to perform work.
Project Engineer/Manager: John McCallum Director: Peter Fromm	Project Sco 75.6	ore
Problem Statement: The three carbon steel 10 million gallon reservoi at the SWP are 60 years old and coming to the end of their useful life.	Scope of Work/Project Alternatives: Replace all three steel 10-Million-gallon with preloaded circular concrete reserve to those currently being built at the Wes Center. One reservoir will be replaced demand season over a three-year cons period. Refurbish the seals and add electric op eight 96-inch valves, Refurbish or replace two 48-inch valves Remove lead paint from the main head operators and repaint. Install new overflow swales, sample sta lighting	oirs similar st ServiceSchedule: Start Design 2023, Start Construction: 2025 – 2029 Completein each low structionEstimated Cost: \$45,000,000 (includes escalation through duration of project) 50-year projected cost to maintain existing reservoirs to store high-quality drinking water is estimated to be \$58M as compared to install and maintain new concrete reservoirs over the same period of \$42M.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	^{\$0}



Project Status: Project Execution -Innovation Construction GLWA WW Master Plan Class Lvl 1: Water Water Master Plan Right Sizing Class Lvl 2: Treatment Plants and Redundancy Facilities **NE WTP Repurposing** Class Lvl 3: Southwest Great Lakes Water Authority Linear Assets Outside of Facilities Lookup Location: SWTP **Predecessor Project(s)** ~ **Project New to CIP:** Project Engineer/Manager: Shakil Ahmed **Project Score** 68.7 **Director:** Terry Daniel **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: The flight and chain system will be removed and The existing flight and chains are not in service Project not scored by risk committee since it is and require replacement due to poor performance. replaced with upgraded components and new far advanced control logic.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window *Design & Construction costs are inclusive of salaries where salaries are not defined

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$27	\$0	\$0	\$13	\$14	\$14
Construction	\$3,000	\$0	\$0	\$1,423	\$1,577	\$1,577



Project Title: Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLANA Great Lakes Water Authority
Project Engineer/Manager: Erich Klun	Project Sco	ore	

90.9

Project Engineer/Manager: Erich Klun

Director: Peter Fromm

Problem Statement:

Existing low- and high-lift pumping system electrical switchgear is original to the plant (1930s) and well beyond it's useful service life. This switchgear is unsafe, unreliable and is oversized for current and projected demands. The existing pumping units are a mix of 1930s and 1950s units and are in need of either replacement or in the case of the pumps rehabilitation. The exterior windows on the pumping plant building are original (1930s), in poor condition and are not well insulated. As a r...

Scope of Work/Project Alternatives:

This CIP project will be delivered under a designbid-build project delivery using a single-prime engineering consultant and multiple prime construction contracts to deliver the entire project. The scope of work generally includes: 1. Replacement of low- and high-lift pumping units, including pumps, motors, valves, and piping. 2. Replacement of exterior windows in the pump house, turbine house, boiler house, and switch house.

3. Replacement of medium-voltage electrical system. 4. Replacemen...

Other Important Info:

E. Klun 8/19/20 updates:

1. Scope updates are being added to the design being completed under Contract CS-103 via Amendment No. 2 that is expected to go for approval in September of October 2020. Cashflow and schedule updates herein reflect both the engineering and construction impacts of an approved CS-103 Amendment No. 2.



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$2,727	\$748	\$748	\$269	\$313	\$312	\$312	\$312	\$313	\$1,562	\$157
Professional Services	\$108	\$84	\$84	\$26	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (MISC)	\$20	\$20	\$20	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-103)	\$15,244	\$8,782	\$8,782	\$1,135	\$1,466	\$1,462	\$752	\$752	\$754	\$5,185	\$379
Design-Build # 1 (Contract A, 1900134, 1904795)	\$17,161	\$13,145	\$13,145	\$1,889	\$2,192	\$0	\$0	\$0	\$0	\$2,192	\$0
Construction (Contract B)	\$52,000	\$0	\$0	\$1,500	\$13,925	\$18,887	\$13,887	\$3,800	\$0	\$50,500	\$0
Construction (Contract C)	\$200,000	\$0	\$0	\$0	\$0	\$7,245	\$8,530	\$23,263	\$23,367	\$62,404	\$108,050
Construction (Contract D)	\$16,000	\$0	\$0	\$0	\$0	\$0	\$3,940	\$7,989	\$4,071	\$16,000	\$0



Project Title: Springwells Water Treatment Plant, Administration Building Improvements & Underground Fire Protection Loop

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm	Project Score	
Director: Peter Fromm	76.4	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Existing administration building, bathrooms, machine shop and offices throughout the facility are nearly 90 years old with many of its facilities being original to the plant. The building needs	The work includes removal and replacement of the existing plumbing and electrical along with architectural upgrades. The machine shop will be upgraded to include new air conditioning. There is	Challenges: . All plumbing needs to be replaced, the majority of which is in existing walls. The underground facilities (e.g., electrical duct banks, gas service mains, fiber optic, tunnels, conduits,

improvements.

architectural, plumbing and electrical

ded to include new air conditioning. There is upgi an existing locker room that will be converted to a training center.

service mains, liber optic, tunnels, uits, major pipelines, etc.) at Springwells have been modified several times since initially being commissioned around 1930.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$281	\$91	\$91	\$17	\$20	\$20	\$20	\$20	\$20	\$102	\$71
Professional Services	\$152	\$37	\$37	\$4	\$0	\$0	\$0	\$0	\$0	\$0	\$115
Design/Engineering (CS-282)	\$1,415	\$1,088	\$1,088	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$327
Design/Engineering (CS-201)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$4,846	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,846



Project Title: Power Quality: Electric Metering Improvement Program

 Project Status: Active - Pre-Procurement - Design Class Lvl 1: Centralized Services Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: System-wide Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Image: NotesPower Quality Meters
Project Engineer/Manager: Eric Griffin	Project Score	
Director: John Norton	0	

Problem Statement:

This includes advanced meters for measuring power usage in real-time to reduce the electrical demands and further optimize load management practices,

GLWA experienced a lot of power outages at facilities. The installation of the New Power Monitors provide real wave form data to determine the cause of the outages and the time period of sagging or swelling voltage which effects the integrity of the equipment. MFG 7/25/2019

Scope of Work/Project Alternatives:

This program will increase the number of electric meters at pumping stations and treatment facilities to facilitate active demand management to reduce electricity rates. The meters can be tied to the existing data management system for data archival and use.

The installation of the New Power Monitors will provide real wave form data to determine the cause of outages and the time period of sagging or swelling voltage which effects the integrity of equipment. MFG 07/25/2019

Other Important Info:

Project History: Project will find high demand (kW) sites i.e all the water treatment plants (Phase 1)

We would like to change the project to design build and move up on the CIP. The outages are affecting the pressures resulting in water main breaks and boil water advisories, This will help to better communicate DTE problems that occur and lead to solutions to improve the process or equipment. MFG 7/25/2019

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$125	\$0	\$0	\$37	\$44	\$44	\$0	\$0	\$0	\$89
Design/Engineering	\$2,498	\$0	\$0	\$452	\$1,024	\$1,022	\$0	\$0	\$0	\$2,046



Project Title: Springwells Water Treatment Plant Powdered Activated Carbon System Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Ficture
Project Engineer/Manager: Justin Kietur	Project Score	
Director: Peter Fromm	36.8	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Powdered activated carbon (PAC) is added to the treatment process to address taste and odor issues in the raw water supply. Taste and odor issues are infrequent, but the existing PAC system is difficult to operate and maintain. A more operate friendly and easier to maintain system is needed. Currently the plant is able to feed PAC through extraordinary measures due to deficiencies in the system. This creates additional operations and maintenance expense and inefficiencies. If raw water quality	carbon system with a new system designed fo improved operations and maintainability when dosing is needed.	pr congested storage areas and pipe chases. PAC bon ctors. ks

associated piping, valves and co...



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$159	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$158
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$975	\$0	\$0	\$0	\$0	\$0	\$0	\$6	\$6	\$969
Construction (Build) # 1	\$2,900	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,900



Project Title: Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Updated project photo
Project Engineer/Manager: Peter Fromm Director: Peter Fromm	Project Scor 86.1	re
Problem Statement: Existing sedimentation basin gates, guides and hoists are early 1930s and are in need of replacement. Operation of the sluice gates in their existing condition and design does not meet current best practices for safe maintenance and operation.	 Scope of Work/Project Alternatives: This CIP project is being delivered under build project delivery method and general includes the following scope of work: 1. Demolition of the existing eight (8) 1930 sedimentation basins gates, guides, and 2. Installation of the new eight (8) 1930 sedimentation basins gates, guides, and 3. Concrete restoration within the four (4) sedimentation basins. 4. Concrete repairs to the air vents, acce access hatches on top of the 1930 sedimentation. 	Illybe shutdown during three low demand seasons to complete the work. This contractor will need to coordination with CON-170: Sludge Removal and Disposal for cleaning the sedimentation basins, SP-563, CON-253, and other construction projects to ensure that the system can handle the long duration shutdown.ss ramp,



Project Title: Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$240	\$243	\$243	(\$3)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$127	\$61	\$61	\$79	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Contractual Professional Services (1802774)	\$23	\$23	\$23	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-289)	\$23	\$23	\$23	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (1802774)	\$13,703	\$11,440	\$11,440	\$2,263	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilit Predecessor Project(s) 	ies	Geat Lakes Water Authority
Project Engineer/Manager: Erich Klun	-	ect Score	
Director: Peter Fromm	58.3	3	

Problem Statement:

Six (6) of the seven (7) 72-inch mains leaving the site are original to the 1930 plant construction and consist of riveted steel pipe material. Main No. 7 is a prestressed concrete cylinder pipe material installed in 1958. The steel mains are leaking and in need of replacement to maintain system reliability. Additionally, isolation valves associated with the 72-inch mains need to be replaced because several are leaking and unable to isolate flow. It is suspected that the other large-diameter is...

Scope of Work/Project Alternatives:

This project consists of removal and replacement of the High Pressure Zone (HPZ) and Intermediate Pressure Zone (IPZ) discharge header piping and yard piping with additional replacement occurring outside the Springwell's Property to locations that minimize the number of isolation points required for work to be completed. The scope will be divided between IPZ and HPZ to maintain operations during construction. This project also includes miscelaneous site infrastructure improvements such as the...

Other Important Info:

E. Klun 8/28/20 update based on the outcome of AECOM's effort on CS-272 Task 71013A, Phase I is as follows:

The project will be delivered by multiple projects comprised of equipment procurement, DB construction, consultant services, and DBB construction contracts as follows:

 Contract A, Procurement of large diameter, high-performance butterfly valves to be installed under Contract D.
 Contract B, Procurement of pressure regulating/flow control valves to be installed under Contract E...



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,968	\$160	\$160	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,065
Professional Services	\$1,831	\$1,621	\$1,621	\$286	\$0	\$0	\$0	\$0	\$0	\$0	\$0
CMAR #1	\$215,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$166,482



Project Title: Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Maintenance building photo 1 of finished section of piping
Project Engineer/Manager: Brian VanHall	Project Sco	pre

Project Engineer/Manager: Brian VanHall

Director: Peter Fromm

Problem Statement:

The steam, condensate return, compressed air, and natural gas piping systems at the Springwells WTP need to be replaced. These systems are original to the plant (i.e. 1930 or 1958) and are beyond their useful life. The existing steam and condensate systems are in poor condition and require multiple repairs each heating season due to frequent failures. This often requires taking the entire steam system out of service which places equipment at risk of freezing. Active steam, condensate, and air I...

Scope of Work/Project Alternatives:

This project is being delivered using a design-bidbuild project delivery method. This engineering services contract involves designing a new, more energy-efficient steam heating system for the entire Springwells Water Treatment Plant, including all steam unit heaters, steam piping, condensate return piping, condensate return pumping stations, steam pressure reducing valves, and appurtenances. This project also includes replacing the compressed air piping in the plant used for service air. Once...

77

Other Important Info:

Many components of the existing system are original to the existing heating system, are not functioning and need to be replaced. Seasonal work and sequencing with the heating season is required.



Project Title: Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$278	\$186	\$186	\$55	\$39	\$0	\$0	\$0	\$0	\$39	\$0
Professional Services	\$8	\$8	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (MISC)	\$5	\$5	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Contractual Professional Services (Clark Const CON-252)	\$277	\$277	\$277	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1671)	\$1,776	\$1,367	\$1,367	\$263	\$173	\$0	\$0	\$0	\$0	\$173	\$0
Construction (Build) # 1 (CON-252)	\$25,643	\$22,576	\$22,576	\$2,314	\$921	\$0	\$0	\$0	\$0	\$921	\$0



Project Title: Springwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete Pavement Replacement

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm	Project Score	
Director: Peter Fromm	71.7	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The existing concrete pavement that covers the 1958 settled water conduits has failed with significant concrete deterioration and corrosion of the reinforcement steel. The condition of the concrete pavement has deteriorated over the past	This CIP project is being delivered under a de- bid-build project delivery method and generally includes the following scope of work: 1. Demolition of the existing concrete pavement that covers the 1958 settled water conduit and	 the settled water conduit to avoid damaging the structure concrete of the settled water conduit.

12 months and the concrete is crumbling in many areas. The conditions in certain areas are such that there are now potential safety hazards to those walking on the pavement. The plant

chemists have to walk some of the areas

frequently to obtain settled water sa...

loading dock.

2. Placement of new concrete pavement that covers the 1958 settled water conduit and the loading dock.

3. Demolition and installation of handrail around the 1958 settled water conduit.

4. Demolition of the existing concrete loading dock.

5....



Project Title: Springwells Water Treatment Plant 1958 Settled Water Conduits and Loading Dock Concrete Pavement Replacement

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$115	\$115	\$115	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$252	\$230	\$230	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-166)	\$10	\$10	\$10	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$26	\$26	\$26	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-272)	\$0	(\$2)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$1,187	\$1,187	\$1,187	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Springwells Water Treatment Plant Flocculator Drive Replacements

Project Status: Active - Procurement - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Springwells WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm	Project Score 89.7	
Director: Peter Fromm		
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The existing 1958 flocculators are beyond useful service life and require replacement.	 This CIP will be delivered under a design-bid-build project delivery model. The scope of work will generally include the following: 1. Replacement of the existing flocculator drives, motors, and control panels. 2. Replacement of all drive shaft bearings and associated grease lines. 3. Replacement of access doors between the flocculator chambers 4. Replacement of ladder rungs to all flocculators. 5. Improvement of flocculation system related instrumentation and controls. 6. Flocculator b 	Implementation of this CIP project is being sequenced and coordinated with the 1930 Sedimentation Basins Sluice Gate Improvements Project.



Project Title: Springwells Water Treatment Plant Flocculator Drive Replacements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	5 Year Total
GLWA Salaries	\$309	\$73	\$73	\$57	\$67	\$67	\$46	\$180
Professional Services	\$164	\$63	\$63	\$108	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$1,893	\$780	\$780	\$320	\$317	\$317	\$216	\$850
Design/Engineering (CS-259)	\$45	\$45	\$45	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$22,945	\$0	\$0	\$2,796	\$7,525	\$7,504	\$5,119	\$20,149



Project Title: Springwells Water Treatment Plant - Service Building Electrical Substation and Miscellaneous Improvements

 Project Status: Active - Pre-Procurement Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Springwells Lookup Location: Water Treatment Plants Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Picture
Project Engineer/Manager: Justin Kietur Director: Peter Fromm	Project Score 62.7	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The electrical substation located inside the Servic Building provides electrical service to the entire service building including the filter wash water pumping units. The existing electrical substation has experienced corrosion to its interior components and electrical cables. As a result the substation does not automatically switch-over during power trips and requires manual switch- over. This substation provides power to the filter wash water pumps and if there are power disruptions associate	 Project will be delivered using a progressive design-build project delivery. The scope of improvements will generally include: 1. Replacement of the electrical substation in 1958 Service Building 2. Connection of replacement electrical substation for vation for status monitoring 3. Replacement of electrical panel in 1930 p and new conduit and cable runs to the associed equipment 4. Rehab of masonry on exterior of phospho acid fill station 5. Insulation of piping and pipe chase 	n the station lant ciated

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY28	5 Year Total	FY29-33
GLWA Salaries	\$178	\$0	\$0	\$0	\$0	\$0	\$75	\$75	\$103
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$2,163	\$0	\$0	\$0	\$0	\$0	\$58	\$58	\$2,105



Project Title: Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: Waterworks Park WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(s) 	of Facilities	Great Lakes Water Authority
Project Engineer/Manager: Jacob Mangum		Project Score	
Director: Peter Fromm		77.9	
Problem Statement:	Scope of Work/Project	t Alternatives:	Other Important Info:
The existing yard piping is 80-140 years old and requires replacement with new piping installed in more efficient configuration.	 a build project delivery me generally includes: 1. Removing existing ya buried venturi meters ar 2. Constructing new yar production flow meters, vaults, and related system 	nd related vaults. d piping, valves, water buried valve and meter em equipment. g transmission main piping. sioning the new main,	This project is being coordinated with the new Waterworks Park to Northeast Transmission Main project. Challenges: Complicated sequence of construction, and demands of DWSD must be maintained along with the coordination transmission system between Water Works Park and Northeast WTPs. Condition of existing valves required to complete the work is unknown. Complex construction staging is accounted for in the design to avoid loss of service and delays to the construction contract. Multiple line



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$504	\$106	\$106	\$72	\$87	\$87	\$87	\$65	\$0	\$326	\$0
Professional Services	\$9	\$9	\$9	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-055)	\$5,598	\$2,966	\$2,966	\$526	\$576	\$574	\$574	\$431	\$0	\$2,156	\$0
Design/Engineering - (RECLASSIFICATION 115001/115003/1150 04)	\$44	\$44	\$44	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (2000610)	\$49,468	\$11,270	\$11,270	\$9,677	\$8,356	\$8,334	\$8,334	\$6,256	\$0	\$31,280	\$0
Miscellaneous	\$450	\$450	\$450	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: WWP WTP Building Ventilation Improvements

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: Water Works Park WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 	of Facilities	Water Works Park Water Treatment Plant
Project Engineer/Manager: Michael Dunne Director: Terry Daniel		Project Score 93	
Problem Statement: The existing ventilation systems are not adequate for the chemical storage rooms, the ozone generator room, ozone destruct room, laboratory rooms, pilot plant rooms, flocculation and sedimentation rooms, and filter galleries at the Water Works Park Water Treatment Plant. Inadequate ventilation poses safety hazards to employees and visitors.	 build project delivery me will generally include the 1) Design of the improve for the facility. 2) Selective removal of e equipment. 3) Construction of new r systems. 4) Installation of electrica mechanical ventilation e 	ered using a design-bid- ethod. The scope of work e following: ed, new ventilation systems existing ventilation system mechanical ventilation al feeders for new equipment. strumentation equipment	Other Important Info: Many of the areas of work are adjacent to the tour path. Ventilation improvements should eliminate noxious gasses from entering the tour path.



Project Title: WWP WTP Building Ventilation Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$238	\$8	\$8	\$64	\$77	\$77	\$13	\$0	\$0	\$166	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (1802499)	. ,	\$770	\$770	\$174	\$194	\$194	\$32	\$0	\$0	\$420	\$0
Construction (Build) # 1 (1802499)	\$14,953	\$0	\$0	\$4,141	\$5,003	\$4,989	\$820	\$0	\$0	\$10,812	\$0



Project Title: Water Works Park Site/Civil Improvements

meet the needs of employees and visitors. There is

no truck vehicle we...

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: Water Works Park WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right S Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Water Works Park Water Treatment Plant
Project Engineer/Manager: Michael Dunne		Project Score 53.9	
Director: Peter Fromm		55.5	
Problem Statement:	Scope of Work/Project A	Iternatives:	Other Important Info:
Many of the existing roadways and pedestrian sidewalks have substantial cracking, crumbling concrete and un-even surfaces whose condition becomes deteriorates every year. The concrete bases for several portions of the site perimeter security fencing are also heavily deteriorated with crumbling concrete. Additionally, there is insufficient employee and visitor parking space for the facility and new parking areas are needed to	1. Construct 30 car parking	dule is predicated on ild assistance services nagement Contract CS- r this project includes the g lot adjacent to plant	Concrete conditions will continue to worsen over the years.

3. Construct 10 car parking lot across from engineering building to serve as vi...

parking.

maintenance garage to serve as GLWA vehicle



Project Title: Water Works Park Site/Civil Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$164	\$0	\$0	\$0	\$0	\$0	\$41	\$41	\$123
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 272)	\$1,343	\$0	\$0	\$0	\$0	\$0	\$341	\$341	\$1,002
Construction (Build) # 1 (TBD)	\$4,389	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,389



Project Title: Water Works Park High Lift Pumping Station Modernization

Class LvI 2: Treatment Plants and Facilities	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Water Works Park High Lift Pumping Station
Project Engineer/Manager: Michael Dunne	Project Score	
Director: Peter Fromm	58.3	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
In accordance with GLWA's Master Plan, the Northeast Water Treatment Plant is scheduled to	This project will be delivered under a Progressive Design Build delivery method . In general, the	e The current pumping system in the High Lift

Northeast Water Treatment Plant is scheduled to be repurposed as a booster station. Most of the water production will be shifted to the Water Works Park Water Treatment Plant and will bring additional pumping burdens to the plant. There is a need to identify and improve configurations, capacity, redundancy, electrical efficiency, instrumentation, monitoring and controls of the High Lift pumping system at Water Works Park. This project will be delivered under a Progressive Design Build delivery method. In general, the scope will contain the following items:
1. Replace and/or re-engineer pumps and motors based on an evaluation of contemporary and future flows, pressure, and energy needs.
2. Replace and/or improve the current highpressure water system to create a more robust process.
3. Improve ventilation in the pump room to allow pumping units to operate at proper working temperatures.

4. Replace or repair ...

The current pumping system in the High Lift building at Water Works Park was constructed in the early 1960s. Now, 60 years later, it is necessary to realign Water Works Park's pumping system with contemporary and future flow, pressure, and energy requirements.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,035	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$107	\$107	\$532
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build	\$114,055	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,905	\$1,905	\$36,781 183



Project Title: Water Works Park Sedimentation Basins Structural Upgrades

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: City of Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 	f Facilities	Photo of Water Works Park Plant
Project Engineer/Manager: Jacob Mangum Director: Peter Fromm		Project Score 75.3	

Problem Statement:

The existing pre-stressed precast concrete beams that support the plate settlers in the sedimentation basins have developed extensive cracks. Additionally, the concrete knee walls that support the beams have begun to delaminate and spall. The integrity of the structural support system is not compromised at this time, however, to avoid further deterioration of the structure the cracks and spall need to be addressed.

Scope of Work/Project Alternatives:

This project will be delivered under a Progressive Design Build delivery model. The structural system will be examined to confirm preliminary findings, methods for rehabilitation will be proposed, and upgrades will be completed to address the present deterioration of the beams and supports with the goal of extending their service life.

Other Important Info:

Reliability of all treatment systems at Water Works Park is critical to support system rightsizing and decommissioning of Northeast WTP.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY28	5 Year Total	FY29-33
GLWA Salaries	\$179	\$0	\$0	\$0	\$0	\$0	\$0	\$43	\$43	\$136
Design/Engineering	\$793	\$0	\$0	\$0	\$0	\$0	\$0	\$793	\$793	\$0
Construction	\$15,874	\$0	\$0	\$0	\$0	\$0	\$0	\$828	\$828	\$15,046



Project Title: Pennsylvania and Springwells Raw Water Supply Tunnel Improvements

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: General Purpose Lookup Location: Springwells, Northeast, & Pennsylvania raw water tunnels Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Author	A prity
Project Engineer/Manager: Nick Hoffman	Project Sco	pre	

94.3

Director: Peter Fromm

Problem Statement:

Significant structural distress in the form of cracking and ovality have been detected in the Pennsylvania, Northeast (NE) and Springwells (SPRG) raw water tunnels that deliver raw water to the Northeast and Springwells Water Treatment Plants. The extent and magnitude of the distress requires that these segments of tunnel be rehabilitated and restored to provide renewed structural integrity and reliability.

Scope of Work/Project Alternatives:

This project is being delivered using Progressive Design-Build. The scope of work generally includes supplemental remove operated vehicle (ROV) and personnel diver underwater, detailed investigations to determine the nature, magnitude and extent of total tunnel rehabilitation required. The detailed investigations are also used to collect sufficient information and data to determine the preferred design and construction approach best suited to the conditions identified. The investigation work of...

Other Important Info:

These tunnels are 80 to 100 feet below ground surface. Dewatering the tunnels for repair will create extensive stresses that must be considered. Maintaining a supply of raw water to SPRGW, NE and WWP throughout construction to meet the demands of the system must be accommodated. Specialized construction will be involved.

Project History: Portions of the Raw Water Tunnel system are approaching 100 years of service. This project is based on the recommendations of CS-1623, which is inspecting...



Project Title: Pennsylvania and Springwells Raw Water Supply Tunnel Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$891	\$123	\$123	\$249	\$299	\$221	\$0	\$0	\$0	\$520	\$0
Professional Services	\$9	\$9	\$9	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-187)	\$438	\$132	\$132	\$307	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-166)	\$45	\$45	\$45	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (DB- 150, CS-166, CS-187)	\$94,577	\$54,120	\$54,120	\$14,458	\$15,753	\$11,664	\$0	\$0	\$0	\$27,417	\$0
Miscellaneous	\$3,103	\$3,103	\$3,103	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Active - Procurement - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: Belle Isle Intake Project New to CIP:	ial image of Belle Isle intake structure and lagoon.
--	--

Project Engineer/Manager: Michael Dunne

Director: Terry Daniel

Problem Statement:

The Belle Isle intake system is the source water intake for three of the five GLWA water treatment plants. The intake is surrounded by a man-made dike system that creates a large lagoon on the northeast tip of Belle Isle. The dike system is showing signs of substantial erosion on the tip of the southern dike. Other areas on the southern dike are showing signs of erosion to a lesser degree.

Scope of Work/Project Alternatives:

This design/build project will evaluate and recommend solutions to permanently correct ongoing erosion issues and current deficiencies that may result in future dike erosion and failure. The general scope will include.

Project Score

57.5

1. Installing sheet piling, tie backs, and rip rap at the tip of the lagoon.

2. Stabilize lampposts that are leaning due to erosion.

3. Install armor stone where erosion is beginning, but not yet significant.

4. Grade and dress the lagoon access road in select areas.

5. Rep...

Other Important Info:

The Belle Isle Iagoon, formed by the man-made dikes, was designed to prevent frazil ice from impeding water flow into the raw water tunnels. Continued erosion of the dike system will lead to short circuiting of the intake Iagoon. The design intent of the Iagoon, and its benefits, will be compromised and leave the raw water intake which supplies three water treatment plants vulnerable.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$136	\$1	\$1	\$72	\$64	\$64
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$1,039	\$0	\$0	\$384	\$655	\$655



Project Title: Belle Isle Intake System Rehabilitation and Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: Water Works Park Lookup Location: Belle Isle Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Belle Isle Intake
Project Engineer/Manager: Michael Dunne	Project Score	
Director: Terry Daniel	55.8	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The Belle Isle Intake structure and man-made lagoon were constructed in the 1930s. Periodic maintenance and improvements have taken place over the years to keep the building and lagoon in operating condition. As a result of recommendations from the State and CS-187 - Raw Water Condition Assessment, another project is needed. The intake system has experienced a buildup of sediment in critical areas that needs to be removed. Vegetation has grown on the dike system and needs to be removed to pr	 Removal of accumulated sediment in the intake building, emergency intake system, and tunnel system. 	 water treatment process. A fully reliable and modern intake system is crucial in maintaining superior drinking water.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$235	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$59	\$59	\$176
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance	\$1,987	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$653	\$653	\$1,334 188



Project Title: System Electrical Power Improvements

Project Status: Active - Pre-Procurement - Design Class Lvl 1: Water Class Lvl 2: Treatment Plants and Facilities Class Lvl 3: General Purpose Lookup Location: Multiple Counties Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Signal Redundancy NE WTP Repurposing Linear Assets Outside of Fignal Predecessor Project(s) 		Great Lakes Water Authority
Project Engineer/Manager: Eric Griffin		Project Score	
Director: Peter Fromm		77.1	
Problem Statement: Electrical power redundancy and reliability is critically important for the successful operation of the sewage pumping stations, especially during storm events. Storm events and performance of certain sewage pumping stations during the summer of 2021 require that GLWA review the firm and total installed capacities of pumping units, the redundancy and reliability of power supplies, electrical switchgear configurations, and backup power generation capabilities at its sewage pumping stations. Defi	Scope of Work/Project Alta Conduct a condition assess assessment of the primary a electrical systems at all GLV stations to include. 1.Primary power feeds 2.Electrical system configura 3.Electrical switchgear, moto VFDs. 4.Motor controls 5.Medium-voltage power sys 6.Onsite backup power gene 7.Other electrical power, dis that impact the redundancy pumping units Once the n	ment and needs and secondary VA's sewage pumping ation or control centers, stem eration and distribution tribution and controls	Other Important Info: N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$102	\$0	\$0	\$50	\$52	\$52
Design/Engineering	\$3,908	\$0	\$0	\$1,927	\$1,981	\$1,981



Project Title: Water Works Park to Northeast Transmission Main

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: WWP to NE WTP Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLANA Great Lakes Water Authority
Project Engineer/Manager: Mike Garrett Director: Peter Fromm	Project 76.8	Score	

Problem Statement:

The 2015 GLWA Water Master Plan (WMP) update indicated that the regional system has significant excess capacity for water treatment compared to projected water demands. The analysis indicated that for average day demand conditions, the five WTPs typically operate between 23 percent to 35 percent of the rated treatment capacity and for maximum day demand conditions typically operate between 38 percent to 67 percent of the treatment rated capacity. To address this the WMP update recommended reduc...

Scope of Work/Project Alternatives:

This project includes three separate construction phases for the completion of the overall water transmission system from Water Works Park to Northeast:

 Phase 1 - Construction of 84-inch yard piping and a Flow Control Facility at the Northeast site.
 Phase 2 - Construction of 4 miles of 81-inch water transmission main (WTM) from the Northeast site to I-94.

(3) Phase 3 - Construction of 6,000 feet of 60inch/69-inch WTM along Hurlbut from I-94 to the intersection of Hurlbut/Sylvester.

Other Important Info:

Challenges: Construction of large diameter WTM in the road ROW north of I-94 and along Hurlbut south of I-94.

This project was recommended as part of the 2015 Water Master Plan Update to align treatment capacity with decreasing water demands.



Project Title: Water Works Park to Northeast Transmission Main

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$3,486	\$1,116	\$1,116	\$126	\$148	\$148	\$148	\$148	\$148	\$741	\$741
Professional Services	\$19	\$19	\$19	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-272)	\$180	\$0	\$0	\$180	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-152)	\$4,448	\$4,422	\$4,422	\$86	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Phase #1 (1803258)	\$24,990	\$25,575	\$25,575	(\$394)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build Phase #2 (1904254)	\$3,747	\$3,747	\$3,747	\$410	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build Phase #3	\$235,262	\$0	\$0	\$11,626	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build Phase #4 (2003102)	\$18,750	\$922	\$922	\$4,713	\$2,664	\$2,656	\$2,656	\$2,656	\$2,664	\$13,296	\$0



Project Title: 96-inch Water Transmission Main Relocation and Isolation Valve Installations

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Imlay Station to North Service Center Project New to CIP:

Project Score

77.5

Project Engineer/Manager: Peter Fromm

Director: Peter Fromm

Problem Statement:

This project is critical to providing isolation and redundancy to Lake Huron WTP supply, while protecting the water supply from potential contamination at the former G&H Industrial Landfill site. The project includes relocation around existing superfund landfill and addition of isolation valves along the 96-inch water transmission main.

Scope of Work/Project Alternatives:

Relocate 2.5 miles of 96-inch transmission main currently located in an EPA NPL landfill, a portion of which is submerged in landfill leachate. Relocation includes crossing the Clinton River, coordination with various authorities having jurisdiction and easement acquisition. The isolation valve installation portion of the project provides the ability to isolate segments of the 96-inch main between Imlay Station and North Service Center for maintenance while maintaining customer expected level o...

Other Important Info:

Challenges: Shutdown, continued customer service, isolation valve installations while maintaining the Lake Huron WTP supply to Rochester Station. Property acquisition will be required for the chesterfield temporary booster station and East Pond Creek discharge facility for relocation around the landfill.



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$2,658	\$402	\$402	\$306	\$366	\$365	\$365	\$365	\$366	\$1,825	\$129
Professional Services	\$6	\$6	\$6	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-272)	\$227	\$0	\$0	\$227	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1900741)	\$31,510	\$13,965	\$13,965	\$3,839	\$2,733	\$2,726	\$2,726	\$2,726	\$2,733	\$13,644	\$963
Design/Engineering (CS-165)	\$1,687	\$1,687	\$1,687	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC - Route Study)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$226,132	\$1,658	\$1,658	\$33,680	\$75,742	\$56,225	\$17,682	\$17,682	\$20,789	\$188,120	\$3,265



Project Title: Schoolcraft Road Water Transmission Main

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Schoolcraft water main Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		at Lakes Water Authority
Project Engineer/Manager: Nick Hoffman	Project Sc	ore	
Director: Peter Fromm	54.7		

Problem Statement:

Currently there is an existing 48-inch water transmission main on West Bound Schoolcraft Road. This existing PCCP transmission main was manufactured by Interpace Corporation which has a long-documented history of PCCP failures due to manufacturing means and methods associated with the pre-stressed wires. Due to excessive breaks over the years and the downstream effect on customers, this project will improve the transmission system reliability and redundancy by installing a new 48-inch water tra...

Scope of Work/Project Alternatives:

Design and Construction of approximately 12,000 linear feet of new PCCP or Carbon Steel 48-inch water transmission main along Eastbound Schoolcraft service drive between Middlebelt and Beech Daly. Including isolation valves, blowoff's, valve vaults, manhole entrances and related appurtenances. Upon completion and tie-in of the new Eastbound Schoolcraft transmission main the existing will be abandoned in place.

Other Important Info:

Designed under CS-1488 by Somat Engineering



Project Title: Schoolcraft Road Water Transmission Main

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$757	\$766	\$766	(\$1)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$144	\$144	\$144	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 1488, CS-259)	\$651	\$562	\$562	\$99	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1488 - to be moved to CS-259)	\$35	\$35	\$35	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (1804129)	\$13,101	\$12,632	\$12,632	\$469	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Phase #2)	\$2,358	\$612	\$612	\$1,746	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (2201870)	\$0	\$1,044	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Wick Road Water Transmission Main

break in this line is disruptive to several

system reliability/redundancy by means of constructing a parallel 48-inch water main along

Wick Road.

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Romulus Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside o Predecessor Project(s) 		Great Lakes Water Authority
Project Engineer/Manager: Nick Hoffman		Project Score	
Director: Peter Fromm		62.9	
Problem Statement:	Scope of Work/Project	Alternatives:	Other Important Info:
Existing water main from Wick Station to Ypsilanti station has a history of excessive breaks. Additionally, the main is the only primary	Design and Construction transmission main along Romulus, MI including is	Westbound Wick Road in	N.A.

connection between the two facilities with multiple interconnects that will tie-in with the existing main along the alignment. Completion of this project will community Master Meters along its alignment. A alleviate pressures and potential transients communities depending on the failure location. The between the two mains, as well as increase purpose of this is to improve the transmission reliability/redundancies in the general area.



Project Title: Wick Road Water Transmission Main

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$240	\$202	\$202	\$42	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$1,069	\$981	\$981	\$123	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-259)	\$977	\$886	\$886	\$120	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1488)	\$247	\$247	\$247	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-306, 1803621)		\$21,261	\$21,261	\$3,071	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (MISC CSX)	\$272	\$272	\$272	\$6	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Merriman Road Water Transmission Main Loop

 Project Status: Future Planned - Ten-Year CIP Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Merriman Rd, Marquette Rd to Lower Rouge River Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Construction on Merriman Rd.
Project Engineer/Manager: Jacob Mangum	Project Score	
Director: Peter Fromm	76.8	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Currently, several member partners (served by master meters WL-08, WL-03, WL-01, WL-12, WY- 01, RS-01, GC-03) are fed by a single 36-inch water transmission main along Michigan Avenue. Construction of this proposed Merriman Road transmission main will provide a second feed to these customers and therefore provide redundancy. In addition, construction of this proposed Merriman Road transmission main improves and reinforces water service delivery to the point where the Michigan Avenue Booster Pump	 This project includes design and construction services associated with the installation of 2 miles of new 30-inch transmission main along Merrimar Road between Lower Rouge River and Marquette Road. Alternatives evaluated included new main on either: 1. Hannon Road (rejected because of its poor route relative to other options) 2. Newburgh Road (rejected because it is not technically feasible as it will not meet contract pressures). 3. Merriman Road (accepted because it is superior in its tran 	



Project Title: Merriman Road Water Transmission Main Loop

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$435	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$54	\$54	\$271
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$5,111	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$954	\$954	\$2,953
Construction (Build) # 1	\$20,663	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$12,190



Project Title: Park-Merriman Road Water Transmission Main

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Venoy Road to Merriman Road to Michigan Ave. Booster Station. Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 	Ū	Updated photo
Project Engineer/Manager: Peter Fromm		Project Sco	pre
Director: Peter Fromm		44.1	

Problem Statement:

Currently, most of the wholesale master meters serving the cities of Wayne and Westland are fed off a single, "dead-end" transmission main, which provides no redundancy in service. Additionally, Wayne, Westland and Inkster have deduct wholesale meters that are fed off the single, "deadend" transmission main. Construction of this new 24-inch water main will create a loop for these member partners and thereby eliminate the single, "dead-end" main. Direct meter connections will be made to the new...

Scope of Work/Project Alternatives:

This CIP project is being delivered under a designbid-build project delivery method and generally includes the following scope of work: 1. Construction of 7,000 linear feet of 24-inch diameter ductile iron water transmission main, which includes 2 directional drills to install this main under the lower Rouge River, and 1 jack-andbore to install this main under Michigan Avenue. 2. Constructing two new wholesale master meters and associated vaults for the city of Wayne. 3. Associated park im...

Other Important Info:

Challenges: Shutdowns to connect the two new meters with the City of Wayne. The water pressure during these two shutdowns will be reducers and coordination will need to take place with the City of Wayne, their residents and local businesses.



Project Title: Park-Merriman Road Water Transmission Main

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$258	\$257	\$257	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$151	\$104	\$104	\$50	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Contractual Professional Services (Water I&E)	\$1,207	\$1,207	\$1,207	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 259, CS-1488)	\$330	\$279	\$279	\$51	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1488)	\$253	\$253	\$253	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (1802775, CON- 268?)	\$9,364	\$6,272	\$6,272	\$3,093	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: 14 Mile Transmission Main Loop

Project Status: Project Execution - Construction Class LvI 1: Water Class LvI 2: Field Services Class LvI 3: Transmission System Lookup Location: 8 Mile Rd/ I-275 to 14 Mile Rd/ Haggerty PS Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizin Redundancy NE WTP Repurposing Linear Assets Outside of Fac Predecessor Project(s) 		Itematical14 Mile Loop Project Location
Project Engineer/Manager: Vittoria Hogue	Pr	roject Score	

Director: Peter Fromm

Problem Statement:

The 14 Mile Transmission Main that currently serves West Bloomfield Township, Farmington Hills, Commerce Township, Novi, Walled Lake, and Wixom is a single feed transmission system. If a disruption to service were to occur on this transmission main, many of the users along this main would experience a complete loss of pressure and flow. This project would provide a transmission main loop to the 14 Mile system to increase redundancy on this branch of the system.

Scope of Work/Project Alternatives:

Install approximately 8 Miles of 54-inch transmission main from 8 Mile Road to 14 Mile Road. It also includes construction of approximately 1 mile of new 24-inch parallel transmission main along 14 Mile from M-5 to west of Decker Road to reinforce the 14 Mile Transmission System.

76

The work will also include connections to the yard piping and reservoir fill line at the Haggerty Booster Station as well as control valves to regulate flows to and from the 14 Mile transmission main.

Other Important Info:

Project History: The 2015 Water Master Plan Update included a recommendation to evaluate options along this branch of the system to increase redundancy. Since that recommendation, GLWA Water Supply Operations Engineering performed a hydraulic analysis of redundancy alternatives for the 14 Mile Transmission System. The results of the hydraulic analysis was presented at the May 15, 2017 and September 19, 2017 Analytical Work Group Meetings and based on the discussion at these meetings, the Hagger...



Project Title: 14 Mile Transmission Main Loop

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,714	\$861	\$861	\$482	\$373	\$0	\$0	\$0	\$0	\$373	\$0
Design & Construction Assistance # 1	\$9,883	\$7,155	\$7,155	\$1,923	\$1,071	\$0	\$0	\$0	\$0	\$1,071	\$0
(1802448)											
Construction (Build) # 1 (1903312)	\$6,567	\$3,766	\$3,766	\$2,801	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 2	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction Phase #3 (1903312)	\$2,718	\$2,325	\$2,325	(\$311)	\$954	\$0	\$0	\$0	\$0	\$954	\$0
Construction Materials (2002038)	\$691	\$691	\$691	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (2004456)	\$92,469	\$19,912	\$19,912	\$46,742	\$31,693	\$0	\$0	\$0	\$0	\$31,693	\$0
Construction Materials (2002047)	\$284	\$284	\$284	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction Materials (2002048)	\$1,178	\$82	\$82	\$598	\$498	\$0	\$0	\$0	\$0	\$498	\$0



Project Title: Downriver Transmission Main Loop

Project Status: Project Execution -Innovation Desian WW Master Plan Class Lvl 1: Water Water Master Plan Right Sizing Class Lvl 2: Field Services Redundancy ~ Class LvI 3: Transmission System **NE WTP Repurposing** Lookup Location: Will be located on Linear Assets Outside of Facilities ~ Inkster between Wick and Pennsylvania **Predecessor Project(s)** Road; on Allen Road/Dixie Highway between Pennsylvania Rd. and Ready Rd; and also at Electric Avenue. **Project New to CIP:**

Project Engineer/Manager: Vittoria Hoque

Director: Peter Fromm

Problem Statement:

The Downriver Transmission Main that currently serves Brownstown, Riverview, Woodhaven, Trenton, Flat Rock, Gibraltar, Rockwood, South Rockwood, Berlin Township, and Grosse Isle is a single feed transmission system. If a disruption to service were to occur on this transmission main. many of the users along this main would experience a complete loss of pressure and flow. The number of users experiencing pressure loss would depend on the location of the break. This project would provide a transmi...



Project Score

76

Scope of Work/Project Alternatives:

This project will be delivered using a design-bidbuild project delivery method. The scope of work generally includes: installing approximately 4 miles of 16-inch transmission main and 5 mile of 24-inch transmission main paralleling the existing Allen Road/Dixie Highway transmission main and 4 miles of 30-inch transmission main along Inkster road between Wick and Pennsylvania road. This will provide redundancy to the Downriver communities of Brownstown, Riverview, Woodhaven, Trenton, Flat Rock,...

Other Important Info:

Completion of the Downriver Transmission main loop was predicated on acquiring ownership of a portion of 24-inch transmission main owned but not used by the City of Trenton. The acquisition of this Trenton main has been completed.

Project History: The 2015 Water Master Plan Update included a recommendation to evaluate options along this branch of the system to increase redundancy. GLWA Water Supply Operations Engineering performed a hydraulic analysis of redundancy alternatives. The results...



Project Title: Downriver Transmission Main Loop

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$607	\$97	\$97	\$62	\$75	\$75	\$75	\$75	\$75	\$374	\$75
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (1803942)	\$5,595	\$2,397	\$2,397	\$225	\$504	\$502	\$502	\$502	\$504	\$2,514	\$502
Construction (Build) # 1	\$61,300	\$0	\$0	\$0	\$10,235	\$10,207	\$10,207	\$10,207	\$10,235	\$51,093	\$10,207



treatment is decommissioned.

Project Title: 7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: City of Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Nick Hoffman	Project Score	
Director: Peter Fromm	81.2	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The primary driver of this project is to provide bar up water service from Springwells WTP to the Water Works and Northeast Service Areas in cas of loss of service to the Water Works Park WTP Northeast WTP. The secondary driver to this project is to support	Mile/Nevada Transmission Main and construction of a new flow control station at Carrie/Nevada. or	This project highlights the need to reinforce the transmission system in order to provide service reliably during existing conditions and after treatment is decommissioned at the Northeast WTP. This project would be completed regardless of whether the Northeast WTP

finished water supply main to the Northeast site to support maximum day demands for the Northeast service area, which can be as high as 190 MGD. With the planned decommissioning of treatm...

Northeast WTP repurposing by providing a second

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$589	\$31	\$31	\$28	\$33	\$33	\$33	\$33	\$33	\$166	\$166
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$86	\$8	\$6,882	\$2,179	\$1,246	\$0	\$0	\$0	\$0	\$1,246	\$0



Project Title: Garland, Hurlbut, Bewick Water Transmission System Rehabilitation

 Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Transmission Mains Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLANA Great Lakes Water Authority
Project Engineer/Manager: Nick Hoffman	Project S	core	
Director: Peter Fromm	85		

Problem Statement:

A large proportion of the water transmission mains (WTMs) within the City of Detroit were constructed between the decades of 1870 and 1930. Mains constructed during this period have exceeded their service life and require replacement in the near term. Several WTM within this age of construction have strategic importance as they can be used to transmit flows between the Water Works Park WTP and the Northeast WTP.

Scope of Work/Project Alternatives:

This project involves rehab of WTM along Garland Street, Hurlbut Street, and Bewick Street between Jefferson Avenue and I-94 within the east side of the City of Detroit. This project will include a detailed condition assessment of these WTM to evaluate the appropriate rehabilitation method.

Other Important Info:

This project will be implemented concurrently with Phase 3 of CIP:122003 WWP to NE Transmision Main Project.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$541	\$4	\$4	\$29	\$34	\$34	\$34	\$34	\$34	\$169	\$169
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (C.A.)	\$60	\$3	\$3	\$29	\$29	\$0	\$0	\$0	\$0	\$29	\$0
Design/Engineering	\$34,821	\$1,713	\$1,713	\$3,211	\$3,055	\$0	\$0	\$0	\$0	\$3,055	\$0



Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: City of Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		GELVAA Great Lakes Water Authority
Project Engineer/Manager: Timothy Kuhns		Project Score	

Director: Peter Fromm

Problem Statement:

The City of Detroit is planning on performing a complete reconstruction of Jefferson Avenue from I -375 to Alter Street in 2023. The existing GLWA 48inch cast iron transmission main that is within Jefferson Avenue from Water Works Park to I-375 was constructed in 1915 and is beyond its service life. Given that Jefferson Avenue will be reconstructed. GLWA would like to replace the 48inch Jefferson Main at the same time as Jefferson Avenue is being reconstructed. Replacing the Jefferson Main now...

Scope of Work/Project Alternatives:

Scope of work for this project involves replacement of approximately 17,650 linear feet of 48-inch transmission main within Jefferson Avenue from Water Works Park to I-375.

37.2

Other Important Info:

This work will be included with the overall Jefferson Avenue Streetscape project. GLWA will cost share for their portion of the work associated with the 48-inch transmission main replacement.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$368	\$0	\$0	\$80	\$96	\$96	\$96	\$0	\$288
Design/Engineering	\$3,481	\$0	\$0	\$454	\$0	\$1,513	\$1,513	\$0	\$3,026
Construction	\$36,287	\$0	\$0	\$0	\$0	\$18,144	\$18,144	\$0	\$36,287



Project Title: Energy Management: Freeze Protection Pump Installation at Imlay Pump Station

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Imlay Pumping Station Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Vittoria Hogue	Project Score	
Director: Peter Fromm	35.1	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
This CIP project will address two principle needs The first is to replace an existing large pumping unit with a smaller pumping unit for the purpose recirculating finished water inside the station's reservoir. Recirculation of reservoir water is required during the low-demand season to maintain water quality. Recirculation of reservoir	project delivery method. The scope of work generally includes replacing one of Imlay Station's 75 MGD pump's and 6,000 HP motor with a smaller 22.5 MGD pump with 1,100 HP motor. The associated VFD, valves, piping and appurtenances	N/A

accommodate the new smaller pump. VHN

7/29/2021

Current Expenses (All figures are in \$1,000's)

water using a smaller suitability sized pumping unit

will reduce operating complexity and the possibility

for damage to the larger pump units. The second

nee...

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$213	\$195	\$195	\$16	\$3	\$0	\$0	\$0	\$0	\$3	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (1900516)	\$5,534	\$911	\$911	\$3,767	\$856	\$0	\$0	\$0	\$0	\$856	\$0



Project Title: West Service Center Pumping Station - Reservoir, Reservoir Pumping, and Division Valve Upgrades

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: West Service Center Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLANA Great Lakes Water Authority
--	---	--	--------------------------------------

Project Engineer/Manager: Andrew Juergens

Director: Peter Fromm

Problem Statement:

Construction of West Service Center Division Valves is needed to convey flows originating from the Lake Huron Water Treatment Plant through the West Service Center to the Springwells highpressure service area while the Springwells raw water tunnel is out of service for repairs. The existing reservoirs at the West Service Center are in poor condition and continue to require periodic structural repairs despite numerous previous repairs. Additionally, half of the existing reservoir pumps experien...

Scope of Work/Project Alternatives:

This project is being delivered using a design-build project delivery method. The scope of work generally involves:

Project Score

62.6

- 1. Rehabilitating Valve Vaults #1, #4, and #7.
- 2. Demolishing existing Valve Vault #3.

3. Constructing a new Valve Vault #3 containing a new 30-inch cone valve.

4. Demolishing two existing 10 MG reservoirs and the associated Reservoir Pump Houses #1 and #2, with associated yard piping.

5. Constructing two new 5 MG reservoirs.

6. Constructing a new Reservoir Pump House,

incl...

Other Important Info:

Challenges: Water storage capacity and reservoir pumping capacity need to be maintained during construction. Sequence of construction and meeting system demands will need to be coordinated with operations. Construction of the new reservoirs is subject to the city of Southfield's zoning ordinances especially related to the height of the reservoirs.



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$410	\$194	\$194	\$96	\$116	\$4	\$0	\$0	\$0	\$120	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (1803312, CS-1772)	\$44,900	\$32,935	\$32,935	\$10,588	\$6,431	\$211	\$0	\$0	\$0	\$6,642	\$0
Miscellaneous	\$311	\$311	\$311	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Ypsilanti Booster Pumping Station Improvements

 Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Water Plants & Booster Pump Stations Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Existing Ypsi station
Project Engineer/Manager: Jorge Nicolas		Project Score	
Director: Peter Fromm		47.6	

Problem Statement:

The Ypsilanti Booster Pumping Station does not have backup power generation and needs it in the event of a power loss so that system pressure loss is avoided during these conditions. The entire station and its pumping and electrical system equipment are are original to the facility and are past their useful service life. The existing electrical system requires substantial maintenance to keep it in service. The existing pumps and motors are in poor condition and require cumbersome maintenance to...

Scope of Work/Project Alternatives:

This project is being delivered using a design-bidbuild project delivery method. The scope of work generally includes building a new booster pumping station that meets current water system demands, current building and electrical codes, and best industry practices for water pumping station design, operation and maintenance. The new station will be equipped with all new pumps, motors, drives, electrical switchgear, power distribution system, building mechanical, station passive bypass, and elec...

Other Important Info:

Impact to member partners



Project Title: Ypsilanti Booster Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$391	\$80	\$80	\$23	\$25	\$25	\$25	\$25	\$25	\$124	\$123
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-267)	\$3,884	\$508	\$508	\$120	\$0	\$0	\$0	\$0	\$0	\$0	\$2,244
Design/Engineering (CS-052)	\$89	\$89	\$89	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1902063)	\$15	\$28	\$28	\$14	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$36,195	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$9,734
Construction Property Acquisition	\$1,580	\$1,596	\$1,596	\$1,580	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Adams Road Pumping Station Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Adams Road BPS	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Erich Klun Director: Peter Fromm	Project Scor 97.8	re
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:

Adams Road booster pumping station was constructed in 1971 and is nearing the end of its service life. Recent condition assessment of the station indicates that there are several needs at the site that need to be addressed due to aging infrastructure. Improvements required at the site include site drive improvements, site valve replacements, building sump replacement, site drain PS replacement, structural improvements, pumping system improvements, flow metering improvements, bypass upgrades, in... This project will be delivered using a design-bidbuild project delivery method. The scope of work generally includes reconstructing a new pumping station next to the existing on the current site. The new station will be designed to current building and electrical codes, industry standards, and best practices for operation and maintenance of pumping stations. N/A



Project Title: Adams Road Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$575	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$72	\$72	\$360
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 052A, TBD)	\$8,500	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,192	\$1,192	\$6,201
Design/Engineering (CS-052)	\$83	\$83	\$83	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$52,600	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$26,318



Project Title: Newburgh Road Booster Pumping Station Improvements

Project Score

58.9

Project Engineer/Manager: Andrew Juergens

Director: Peter Fromm

Problem Statement:

Existing pumps, motors and electrical gear are beyond useful service life. The existing pump manufacturer has discontinued maintenance support of the pumps, increasing the difficulty and cost of maintenance. Additionally, a new transmission main will be designed to allow the Newburgh Station to pump flows to the Haggerty Station reservoir. The Haggerty reservoir fill operation may require additional pumps at the Newburgh Station that are rated to higher discharge pressures.

Scope of Work/Project Alternatives:

Construct a new Newburgh Road Booster Pumping Station, including new pumps, motors, VFDs, electrical gear, building mechanical equipment, and backup power generation. Alternatives include constructing a new Newburgh Road Booster Pumping Station on the existing site, expanding the existing site to accommodate a new station, or construction of the new station on a new site.

Other Important Info:

Challenges: The existing site is not large enough to construct the new Newburgh Station. Coordination with the 14-Mile Road Transmission Main Loop Contract will be required.



Project Title: Newburgh Road Booster Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$411	\$17	\$17	\$30	\$36	\$36	\$36	\$36	\$36	\$182	\$181
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (1901767, CS-052)	\$3,503	\$394	\$394	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,110
Design/Engineering (CS-052)	\$83	\$83	\$83	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$41,693	\$30	\$30	\$30	\$0	\$0	\$0	\$0	\$0	\$0	\$41,663



Project Title: North Service Center Pumping Station Improvements

be addressed. Improvements include site drive improvements, valve replacements, septic tank and well field replacement, electric room improvements, building structure improvements, line and reservoir pump upgrades, interior valve upgrades, station piping improvements, sump

pump upgrades, and various electr...

Project Status: Active - Procurement - Design Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: North Service Center	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority		
Project Engineer/Manager: Mike Garrett	Project Score			
Director: Peter Fromm	98.7			
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:		
The North Service Center was constructed in 1962 and is nearing the end of its service life.	This project includes complete reconstruction of the North Service Center Pumping Station, and replacement of two ten million gallon reservoirs.	Proposed changes focus on optimization of energy efficiency in the system by removing waste and conserving energy already input the		
Recent condition assessment of the station indicates that there are several needs that need to		system.		



Project Title: North Service Center Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,587	\$42	\$42	\$109	\$222	\$222	\$222	\$222	\$222	\$1,109	\$326
Professional Services	\$72	\$72	\$72	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$257	\$257	\$257	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 2 - AECOM	\$7,442	\$0	\$0	\$0	\$0	\$0	\$127	\$2,106	\$2,111	\$4,344	\$3,098
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$66,655	\$0	\$0	\$0	\$0	\$0	\$8,245	\$16,813	\$16,860	\$41,918	\$24,736
Construction # 2 - AECOM	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Schoolcraft Pumping Station Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Booster Pumping Stations Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Eric Kramp Director: Peter Fromm	Project S 58.9	core
Problem Statement:	Scope of Work/Project Alternatives	: Other Important Info:

Following the Pump Station Condition Survey and Needs Assessment, significant issues were observed in the Schoolcraft Pumping Station. This needs assessment has found several significant areas of necessary improvement to the station as described in the project scope of work: This project will be delivered using a design-bidbuild project delivery method. The scope of work will generally include replacing existing pumps, motors, drives, electrical switchgear, motor control centers, valves, valve operators, yard piping, and yard valves with new infrastructure. Additionally, the underdrain system that serves the finished water reservoirs will either be rehabilitated or replaced. This project is scheduled to begin beyond the 10 year time period.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$222	\$0	\$0	\$0
Professional Services	\$3,265	\$0	\$0	\$0
Design/Engineering	\$47	\$47	\$47	\$0
Design/Engineering (CS-052)	\$0	\$0	\$0	\$0
Construction	\$21,156	\$0	\$0	\$0



Project Title: Wick Road Pumping Station Improvements

Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Romulus Project New to CIP:	 WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(s) 	of Facilities	GLAVA Great Lakes Water Authority
Project Engineer/Manager: Vittoria Hogue Director: Peter Fromm		Project Score 67.2	

Problem Statement:

Wick Pump Station is currently oversized based on the demands, has poor valve isolation capabilities and much of its equipment which was installed in 1981 is passed its useful service life. This project's intent is to right size the station and replace valves and other aging equipment.

Scope of Work/Project Alternatives:

This project will be delivered under a design-bidbuild delivery method. This project's scope of work will be rightsizing the station's pumping capacity, improving valve control and isolation, and replacing or upgrading equipment. The improvements to right size the station include replacing reservoir pumping units and installing another small line pump (jockey pump) to accommodate low flow conditions. Valve control and isolation work will involve replacing existing station valves and replacing ...

Other Important Info:

CS-052A Condition Assessment provides additional details on the scope of project.



Project Title: Wick Road Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$372	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$372
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (TBD, CS-052A)	\$4,361	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$6	\$6	\$4,355
Design/Engineering (CS-052)	\$57	\$57	\$57	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$19,990	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$19,990



Project Title: Franklin Pumping Station Improvements

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Franklin Pump Station Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm	Project Score	
Director: Peter Fromm	77.7	
Problem Statement: The Franklin Booster Pumping Station was constructed in 1968 and is nearing the end of its service life.	Scope of Work/Project Alternatives: This project includes complete reconstruction of the Franklin Booster Station.	Other Important Info: Project will include alternatives evaluation to determine building new station versus rehabilitating existing.
Recent condition assessment of the station indicates that there are several needs that need to be addressed due to aging infrastructure. Improvements required at the site include site drive improvements, sanitary holding tank improvements, site valve replacements, mezzanine valve access improvements, electrical room upgrades, building structure improvements, pumping improvements, flow me		



Project Title: Franklin Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$132	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$19	\$19	\$113
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (TBD)	\$4,693	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$704	\$704	\$3,989
Design/Engineering (CS-052)	\$93	\$93	\$93	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Imlay Pumping Station	WW Master Plan Water Master Plan Right Sizing	Great Lakes Water Authority
Project Engineer/Manager: Eric Kramp	Project Score	
Director: Peter Fromm	59.4	
Problem Statement: The 2018 Booster Station Condition Assessment identified several significant issues have been	Scope of Work/Project Alternatives: Significant improvements to the site/civil, mechanical, and electrical systems at the Imlay	Other Important Info: VFD size is unusual in the marketplace and cooling systems are complex for the VFDs.

documented at the Imlay Booster Station. In addition to the updates to the VFD systems identified in the FY 2020 CIP. Site/civil, mechanical, and electrical improvements have been identified far in excess of the initial assessment, including the complete replacement of all outdated electrical switchgear.

It was recently documented that approximately half of the reservoir fill system is working at I...

Significant improvements to the site/civil, mechanical, and electrical systems at the Imlay Booster Station are required as follows: Site/Civil -- Replace crumbling retaining walls. Roofing rehabilitation Pumping -- "Right size" remaining pump and motor units based on 2015 WMPU. Rehabilitate any pumping units that are correctly sized. Mechanical -- Improvements to HVAC. Replacement or rehabilitation of all station isolation gate, butterfly valves and reservoir fill valves. Electrical -- Add...



Project Title: Imlay Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,241	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$385
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design (TBD, CS- 052A)	\$136,500	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$48,771
Design/Engineering (CS-052)	\$227	\$227	\$227	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Joy Road Pumping Station Improvements

station top slab and blocks access to the reservoir

fill line valves. The pump station roof hatches leak

and drip onto equipment below. The discharge

header is h...

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Systems Control Center Class Lvl 3: Pump Station/Reservoir Lookup Location: Joy Rd Water Pumping Station	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Inside Joy Road Pumping Station
Project Engineer/Manager: Jacob Mangum	Project Score	
Director: Peter Fromm	58.9	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The station is undersized with limited space for maintenance and personnel access. The main walkway inside the station is built on top of the discharge header and six stairways connected to in are non-code compliant. There is not enough room to install standard stairs. The electrical room	•	ı
addition was partially built on top of the pump	Installation of a new site drain pump station next	to

existing

A new electrical room addition

maintenance and repair.

The existing building structures require

Rehabilitate the existing line and reservoir pum...



Project Title: Joy Road Pumping Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$469	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (TBD, CS-052A)	\$3,536	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-052)	\$71	\$71	\$71	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$35,781	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: GLWA-CS-187: FK Eng: Raw Water Intake

Project Status: Pending Closeout Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: WTPs and Boosters	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Nick Hoffman Director: Peter Fromm	Project Score 0	
Problem Statement: This allowance is reserved for unplanned, emergency and critical project needs that need to be addressed quickly.	Scope of Work/Project Alternatives: This project is an allowance for unplanned, projects that may occur at the Water Treatu Plants and Booster Pump Stations through system. These projects may include repair replacement or rehabilitation of key assets required to allow the Authority to provide su water quality, quantity and pressure to mee customer demands in accordance with fed state requirements under the Safe Drinking Act.	ment and ability to meet on needs. out the r, as ufficient et eral and

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$225	\$181	\$181	\$43	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$11	\$11	\$11	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-187)	\$506	\$305	\$305	\$201	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1623)	\$1,159	\$1,159	\$1,159	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Water Treatment Plant Automation Program

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Water Treatment Plants Plants Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jeffrey Dorsey	Project Sc	core
Director: Terry Daniel	0	

Problem Statement:

This automation design and construction project comes from recommendations that identified existing station process data conditions and needs, GLWA mission critical assets, alternative improvement options to address identified needs, recommended improvements to address the needs, prioritized projects based on the GLWA CIP scoring tool, and schedule for making the improvements along with budgets for each project established under CS-108.

Scope of Work/Project Alternatives:

The purpose of this project is to implement the recommendations from CS-108 that are prioritized in five (5) year increments with an estimated cost of \$1 million dollars per year over a twenty (20) year span.

Other Important Info:

Challenge: Standardization of multiple different data process equipment already installed throughout the 5 plants is problematic.

Project History: Each water treatment plant has process areas ranging from intake, sedimentation, chlorination, filtration and distribution systems. One of the directives from the organizational objectives is to provide the treatment plants with automation. This automation is one of the main drivers for increased efficiency in data monitoring and regulatory repor...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$243	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$243
Design/Engineering	\$9	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$9
Construction	\$23,065	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$23,065



Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Southwest Water Treatment Plant Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	SW SCADA System Upgrade
Project Engineer/Manager: Jeffrey Dorsey	Project Score	
Director: Terry Daniel	67.4	
Problem Statement: This project will upgrade the Southwest WTP SCADA system.	Scope of Work/Project Alternatives: The upgrade of network devices, controllers and removal of device net for the SCADA system.	Other Important Info: This project will also upgrade Ovation to version 3.8

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
Capital Delivery Salary	\$113	\$3	\$3	\$112
Professional Services	\$306	\$158	\$158	\$170
Design-Build (2001051)	\$7,892	\$1,099	\$1,099	\$6,888



Project Title: Power Monitoring Installation for Water Treatment Plants

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Northeast, Southwest and Water Works Park	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority		
Project Engineer/Manager: Jeffrey Dorsey	Project Score			
Director: Terry Daniel	58.6			
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:		
Looking to achieve efficiency of our power usage at our water treatment plants.	This project will install power monitoring meters on electrical switch gear for critical pumping units at Water Works Park, Northeast, and Southwest.	Power monitoring will be installed on critical pumping units and switchgear mains.		

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window *Design & Construction costs are inclusive of salaries where salaries are not defined

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY28	5 Year Total
GLWA Salaries	\$65	\$0	\$0	\$65	\$0	\$0
Professional Services	\$218	\$193	\$193	\$32	\$0	\$0
Design-Build (2000644)	\$1,624	\$1,802	\$1,802	\$93	\$0	\$0



Project Title: WWP Scada Infrastructure Upgrade

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Water Works Park Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jeffrey Dorsey	Project Scor	re

Director: Terry Daniel

Problem Statement:

Of paramount concern is the need to have a reliable and secure SCADA platform that will satisfy GLWA's needs for the next 10-15 years. The purpose is to upgrade the SCADA system to an Ovation DCS controlled network utilizing Ovation and PLC controllers and I/O (3rd part network design will be supplied) for implementation at WWP. It will include the following:

A. A complete SCADA network, replacement of all field devices at the facility.

B. Complete engineering design of a new process...

Scope of Work/Project Alternatives:

The scope of this project is to provide a design for SCADA upgrade of Water Works Park water treatment plant incorporating the following:

59.5

• Upgrade of all plant PLCs

• Network extension upgrades to integrate new process areas/controllers within the process control network

- Emerson Ovation upgrades
- Implement alarm management.
- Migrate all SCADA graphics, alarms, historical
- data configuration to a single platform
- Upgrade/integration into the central Historians.
- Upgrade network back...

Other Important Info:

This project will upgrade the SCADA network. Project not scored by review committee because it is professional services only.



Project Title: WWP Scada Infrastructure Upgrade

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$32	\$0	\$0	\$32	\$0	\$0	\$0
Professional Services	\$201	\$80	\$80	\$133	\$0	\$0	\$0
Design/Engineering	\$348	\$208	\$208	\$155	\$0	\$0	\$0
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: WWP SCADA Network Upgrade

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Water Works Park Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jeffrey Dorsey	Project Score	
Director: Terry Daniel	65	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Provide a robust SCADA network solution with installed capacity to accommodate future SCADA expansion and fully manageable network capabilities. Adhere to network standards put together in the SGD document.	This project will be the construction phase design done under CIP 170304.	of the This project may be delayed.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY28	5 Year Total	FY29-33
GLWA Salaries	\$157	\$0	\$0	\$0	\$0	\$0	\$157
Design/Engineering	\$187	\$0	\$0	\$0	\$0	\$0	\$187
Construction	\$7,198	\$0	\$0	\$0	\$0	\$0	\$7,198



Project Title: SPW SCADA PLC Network Upgrade

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Springwells Plant Project New to CIP:	Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s)	Great Lakes Water Authority
Project Engineer/Manager: Jeffrey Dorsey	Project Score	
Director: Terry Daniel	78.4	
Problem Statement: This project will upgrade current plant PLCs providing Asset Center management and install network cabinets in strategic locations for future expandability.	Scope of Work/Project Alternatives: Provide a robust SCADA network solution installed capacity to accommodate future S expansion and fully manageable network capabilities. Adhere to network standards together in the SGD document.	SCADA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$100	\$0	\$0	\$29	\$71	\$71
Design/Engineering	\$187	\$0	\$0	\$54	\$133	\$133
Construction	\$3,054	\$0	\$0	\$880	\$2,174	\$2,174



Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Northeast Plant Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jeffrey Dorsey	Project Score	
Director: Terry Daniel	59.6	
Problem Statement: Provide a robust SCADA network solution with installed capacity to accommodate future SCADA expansion and fully manageable network capabilities. Adhere to network standards put together in the SGD document.	Scope of Work/Project Alternatives: This project will update the 3rd party network t this site.	Other Important Info: for This project may be delayed.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY29-33
GLWA Salaries	\$100	\$0	\$0	\$0	\$100
Design/Engineering	\$187	\$0	\$0	\$0	\$187
Construction	\$2,825	\$0	\$0	\$0	\$2,825



Project Title: Water Transmission Improvement Program

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Transmission System Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority			
Project Engineer/Manager: Todd King	Project Score				
Director: Todd King	0				
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:			
Assessing, rehabilitating or replacing aging transmission mains in the water system	This project is a yearly funding allocation for the design and/or construction work for the rehabilitation or replacement of aging water	O&M manuals, GIS, Section Maps and Gate Books are available for reference.			
	transmission lines and all appurtenances, connections and related structures.	Project History: There are many critical assets that are required to be operated in the transmission system and this yearly allowance is needed to meet the critical needs of these assets.			
		Challenges: May require shut down of large pumps and isolation or shutdown of large mains etc.			



Project Title: Water Transmission Improvement Program

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$495	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$52	\$52	\$277
Design/Engineering	\$2,975	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$505	\$505	\$2,524
Construction (Build) # 2	\$10,900	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 6	\$17,664	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Transmission System Valve Rehabilitation and Replacement Program

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Transmission System Gate Valves Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Todd King	Project Score 0	
Director: Todd King	0	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Replacement or rehabilitation of GLWA Transmission System Gate Valves will aid in implementing a regular valve exercising program	Evaluate the existing conditions, provide the necessary replacement/ rehabilitation option, then design and implement them.	GIS, Section Maps and Gate Books are available for reference.
as recommended by AWWA as well as increase the reliability of the transmission system.		Project History: There are critical valves that are required to be closed during a main break or an emergency situation. There has not been a regular valve exercising program in the past 15 years in the DWSD/GLWA System.
		Challenges: May require shutdown of large transmission mains.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$296	\$0	\$0	\$0	\$23	\$23	\$23	\$23	\$23	\$114	\$114
Design/Engineering	\$16,173	\$0	\$0	\$0	\$1,594	\$1,589	\$1,589	\$1,739	\$1,744	\$8,255	\$8,697
Construction (Build) # 3	\$15,000	\$0	\$0	\$0	\$0	\$0	\$0	\$1,499	\$1,503	\$3,002	\$7,498



Project Title: Transmission System Valve Rehabilitation and Replacement Program

 Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Transmission System Gate Valves Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Biren Saparia Director: Todd King	Project Score 25.4	
Problem Statement: Replacement/Rehabilitation of GLWA Transmiss System Gate Valves will aid in implementing a regular valve exercising program as recommende by AWWA as well as increase the reliability of the transmission system.	necessary replacement/ rehabilitation option, then design and implement them.	Other Important Info: GIS, Section Maps and Gate Books are available for reference. Project History: There are critical valves that are required to be closed during a main break or an emergency situation. There has not been a regular valve exercising program during the past 15 years in the DWSD/GLWA System. Challenges: May require shutdown of large transmission mains.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
Capital Delivery	\$51	\$6	\$6	\$8	\$9	\$9	\$9	\$9	\$37
Salary									
Professional Services	\$385	\$385	\$385	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-181)	\$5,218	\$5,218	\$5,218	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Transmission System Valve Replacement

Project Status: Project Execution -Innovation Construction GLWA WW Master Plan Class Lvl 1: Water Water Master Plan Right Sizing Class Lvl 2: Field Services Redundancy Class LvI 3: Transmission System **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: Transmission System Linear Assets Outside of Facilities ~ Gate Valves **Predecessor Project(s) Project New to CIP:** Project Engineer/Manager: Todd King **Project Score** 44.5**Director:** Todd King **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: Replacement/Rehabilitation of GLWA Transmission Evaluate the existing conditions, provide the GIS, Section Maps and Gate Books are available System Gate Valves will aid in implementing a necessary replacement/ rehabilitation option, then for reference. regular valve exercising program as recommended design and implement them. by AWWA as well as increase the reliability of the Project History: There are critical valves that are required to be closed during a main break or an transmission system. emergency situation. There has not been a regular valve exercising program during the past 15 years in the DWSD/GLWA System. Challenges: May require shutdown of large transmission mains.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$166	\$5	\$5	\$141	\$25	\$0	\$0	\$0	\$25
Construction (Build) (1802745)	\$18,324	\$3,163	\$3,163	\$14,456	\$705	\$0	\$0	\$0	\$705



Project Title: Transmission Mains Valves and Urgent

Project Status: Future Planned - Within 5 Innovation Year Plan GLWA WW Master Plan Class Lvl 1: Water Water Master Plan Right Sizing Class Lvl 2: Field Services Redundancy Class Lvl 3: Transmission System **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: Multiple Locations Linear Assets Outside of Facilities ~ **Project New to CIP: Predecessor Project(s)** Project Engineer/Manager: Todd King **Project Score** 34.3 **Director:** Todd King **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: Ongoing project to address water main Work shall be as required by GLWA Field Services na transmission mains, valves, pumping stations, and to address and support maintenance and repairs plants on an emergency or urgent basis. and capital improvements to the water main, valves, booster stations, and/or other urgent tasks.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activ	vity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
Cons	struction	\$11,000	\$9,164	\$9,164	\$1,021	\$448	\$447	\$447	\$122	\$1,465



Project Title: Linear System Integrity Program

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Transmission Mains Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	GLAVA Great Lakes Water Authority

0

Project Score

Project Engineer/Manager: Jody Caldwell

Director: Jody Caldwell

Problem Statement:

Many of the water mains serving the GLWA service area were installed in the early part of the 20th century or the later part of the 19th century, and are now reaching the end of their useful life. This project will pilot and utilize new technologies to accurately identify the condition of these buried assets by constructing access ways for inspection and the installation of sensors and fiber optic cables for real-time monitoring of condition. It's essential for cost-efficient repair and replac...

Scope of Work/Project Alternatives:

Construct access structures and utilize new technology to evaluate the existing conditions of the transmission system. Construction of in place sensors and cables may be necessary to adequately access condition. Provide the necessary recommendation for replacement and rehabilitation.

Other Important Info:

*Innovation Note: Consider new techniques for water main assessment. GIS, Section Maps and Gate Books are available for reference.

Challenges: Gaining access to inspect buried pipes is difficult, disruptive and costly. However, there are ways to monitor and test the condition of the piping and methods of performing condition assessment.

Project History: There are many critical assets that are required to be operated in the transmission main the existing conditions is unknown. For planning p...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$312	\$0	\$0	\$3	\$31	\$31	\$31	\$31	\$31	\$154	\$154
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$27,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,508	\$4,508	\$22,492 744



Project Title: Linear System Integrity Program

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Field Services Class Lvl 3: Transmission System Lookup Location: Entire Linear System - Water & Wastewater Project New to CIP:	Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s)	Great Lakes Water Authority
Project Engineer/Manager: Jody Caldwell	Project Score	
Director: Jody Caldwell	76.8	
Problem Statement: GLWA seeks to apply asset management principles to proactively evaluate and manage the linear system (water transmission and sewer interceptor systems). Because the water transmission system is a closed system gaining access to assess the condition of the pipes is	Scope of Work/Project Alternatives: Scope of work is broken into 6 Tasks: Task 1 - Program Management - Water; Task 2 - Development of Water Program Framework; Tas 3 - Planning of Water Pipeline Condition Assessments; Task 4 - Implementation of Water Pipeline Condition	
challenging requiring coordination with operations and member partners, and the construction of access points to introduce and extract equipment. LSIP is a data and risk-based approach.	Pipeline Condition Assessments; Task 5 - Wastewater Program Planning and Implementation; Task 6 - Program Management Wastewater	:-
This project uses the previous work performed	The overall project consists of both Capital and Operating Budget expenses. The capital portion this project includes the improvements necessar to	

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$249	\$0	\$0	\$47	\$57	\$57	\$57	\$32	\$202
Design/Engineering	\$9,601	\$0	\$0	\$435	\$53	\$52	\$5,792	\$3,269	\$9,166
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: LHP, SPP, SWP, NEP, WWP, Booster Stations	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Lake Huron Plant Reservoir No. 3: Interior concrete repair.
--	---	---

Project Engineer/Manager: John McCallum

Director: Peter Fromm

Problem Statement:

This program CIP merges former reservoir inspection and repair programs and umbrella's all subsequent CIP's associated with the program under the 17080X category. This program manages the continuous inspection and repair required to all 31 active reservoirs on a 5 year year cycle. The program manages the overall repair schedule to mitigate conflicts in the transmission system to minimize the impact for EGLE mandated inspections and repairs to GLWA reservoirs at Booster Stations and Water Tre...

Scope of Work/Project Alternatives:

The program will provide inspection, rehabilitation, and maintenance on all 31 finished (potable) reservoirs in the GLWA system on a ELGE mandated five year revolving inspection cycle.

0

Project Score

Other Important Info:

The CIP 170800 program is broken down into subset CIP numbers starting at 170801. CIP 170801 is currently in construction and is supported by two contracts. Engineering contract CS-151A and construction contract 1900744. The second phase of the program CIP 170802 is in the procurement phase and the engineering contract number will be 2100236. The third phase of the program CIP 170803 will begin pre-procurement activities in 2022.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$127	\$0	\$0	\$12	\$14	\$14	\$14	\$14	\$14	\$72	\$43
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$C
Construction (Build) # 1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title:

Project Status: Project Execution - Design Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: LHP, SPP, SWP, WWP, North Service Center, Imlay Booster Station Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Imlay Booster Station: Sealing interior wall cracks
--	---	---

Project Engineer/Manager: John McCallum

Director: Peter Fromm

Problem Statement:

CIP 170801 is the first in a series of facility improvements to reservoirs at the water treatment plants and booster stations assigned to the System -Wide Finished Water Reservoir Inspection, Design and Rehabilitation Program under CIP 170800.

Scope of Work/Project Alternatives:

This project is specific to inspection, design and construction of improvements to the reservoirs at the Springwells WTP, Southwest WTP, Lake Huron WTP and Imlay Station. It is currently being executed and is expected to be closed in January of 2025.

Project Score

94

Other Important Info:

Inspection, design, and RPR services are performed under contract CS-151A . Construction of improvements are performed under contract 1900744. WWP reservoir 2A and North Service Center reservoirs have been added to contract 1900744 to perform emergency repairs. Project not scored by risk committee since it is far advanced

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$448	\$470	\$470	(\$15)	\$0	\$0	\$0
Professional Services	\$347	\$134	\$134	\$237	\$0	\$0	\$0
Contractual Professional Services	\$2,775	\$0	\$0	\$1,728	\$1,047	\$0	\$1,047
Design/Engineering (CS-151A)	\$2,775	\$2,163	\$2,163	\$459	\$244	\$0	\$244
Construction (1900744)	\$21,598	\$15,934	\$15,934	\$3,904	\$2,259	\$0	\$2,259



Project Title: Reservoir Inspection, Design, and Construction Management Services Phase II

Project Status: Active - Procurement - Design Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: LHP, SPP, SWP, WWP, North Service Center, Imlay Booster Station Project New to CIP:	Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s)	Great Lakes Water Authority
Project Engineer/Manager: John McCallum Director: Peter Fromm	Project Score 74.2	
Problem Statement: CIP 170802 is the second in a series of facility improvements to reservoirs at the water treatment plants and booster stations assigned to the System -Wide Finished Water Reservoir Inspection, Design and Rehabilitation under the umbrella CIP 170800 program.	Scope of Work/Project Alternatives: This project is specific to the inspection, design/engineering, and construction improvements to 15 reservoirs.	Other Important Info: Inspection and design of improvements is being executed under future contract 2100236

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$424	\$0	\$0	\$80	\$96	\$96	\$96	\$56	\$0	\$344
Design/Engineering	\$10,779	\$0	\$0	\$2,234	\$2,389	\$2,383	\$2,383	\$1,390	\$0	\$8,545
Construction	\$35,972	\$0	\$0	\$753	\$9,847	\$9,820	\$9,820	\$5,731	\$0	\$35,219



Project Title: Reservoir Inspection, Design, and Construction Management Services Phase III

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: LHP, SPP, SWP, WWP, North Service Center, Imlay Booster Station Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: John McCallum Director: Peter Fromm	Project Score 90.3	
Problem Statement: CIP 170803 is the third in a series of facility improvements related to reservoirs at the water treatment plants and booster stations assigned to the System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation Program CIP 170800.	Scope of Work/Project Alternatives: This project is specifically related to inspection, design, and construction of improvements to the reservoirs in our system as planned in future contracts.	Other Important Info: n/a

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$849	\$0	\$0	\$0	\$0	\$0	\$24	\$97	\$97	\$217	\$483
Design/Engineering	\$16,214	\$0	\$0	\$0	\$0	\$0	\$873	\$2,764	\$1,671	\$5,308	\$8,339
Construction	\$77,369	\$0	\$0	\$0	\$0	\$0	\$0	\$834	\$10,171	\$11,005	\$50,746



Project Title: Suburban Water Meter Pit Rehabilitation and Meter Replacement

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Various meter locations in Transmission System	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chandan Sood	Project Score	
Director: Chandan Sood	0	
Problem Statement: Improving meter data reliability, ensuring accurate billing, improving customer service enabling high quality analysis of the system	Scope of Work/Project Alternatives: The Proposed improvements should include the following; The replacements of meters that have surpassed their life expectancy, and or the current flow rates exceed the mechanical limits of the meter. Installing entrance hatches that allow safer ingress, and egress, and that can be locked for security. Sand blasting and painting of piping and walls. Waterproofing meter vaults to keep the ground water out. Providing a proper floor slope in meter chambers that allows water to settle. Repairing dama	Other Important Info: Challenges: Requires temporary shutdown of the water supply through the meter. Project History: Currently GLWA provides water service to 126 communities, and measures flows and volumes by the utilization of 290 wholesale water meters now in service; 17 of these meters are venturi-orifice type meters, 26 of these are dual venturi type meters, 48 of these single venturi type meters, 97 of these are magnetic flow type meters, and 102 of these are turbine or mechanical type meters. Meters were

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$301	\$0	\$0	\$0	\$0	\$0	\$0	\$27	\$27	\$55	\$137
Construction	\$27,807	\$0	\$0	\$0	\$0	\$0	\$0	\$2,000	\$4,000	\$6,000	\$13,629



Project Title: Suburban Water Meter Pit Rehabilitation and Meter Replacement

Project Status: Project Execution - Construction Class Lvl 1: Water Class Lvl 2: Metering Class Lvl 3: General Purpose Lookup Location: Various meter locations in Transmission System Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chandan Sood	Project Score	
Director: Chandan Sood	48.7	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Improving meter data reliability, ensuring accurate billing, improving customer service enabling high quality analysis of the system	The Proposed improvements should include the following; The replacements of meters that have surpassed their life expectancy, and or the current flow rates exceed the mechanical limits of the	Challenges: Requires temporary shutdown of the water supply through the meter. Project History: Currently GLWA provides water
	meter. Installing entrance hatches that allow safer ingress, and egress, and that can be locked for security. Sand blasting and painting of piping and walls. Waterproofing meter vaults to keep the ground water out. Providing a proper floor slope in meter chambers that allow water to settle. Repairing damag	service to 126 communities, and measures flows and volumes by the utilization of 290 wholesale water meters now in service; 17 of these meters are venturi-orifice type meters, 26 of these are dual venturi type meters, 48 of these single venturi type meters, 97 of these are magnetic flow type meters, and 102 of these are turbine or mechanical type meters. Meters were

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$113	\$2	\$2	\$111	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) (CON-285)	\$12,409	\$10,309	\$10,309	\$2,395	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Active - Pre-Procurement - Construction Class Lvl 1: Water Class Lvl 2: Metering Class Lvl 3: General Purpose Lookup Location: Brownstown Township Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm Director: Chandan Sood		Project Score 63.8	
Problem Statement: BR-01 is a deduct meter pit that serves Brownstown Charter Township. Deduct meter pits are more difficult to track water usage. BR-01 will be abandoned and BR-08 will be installed as a direct meter pit to Brownstown Charter Township.	serving Brownstown Cha direct meter pit (BR-08) v	BR-01 deduct meter pit direct meter pit BR-08 for arter Township. The new will have a new magnetic valves, and 8-inch check	Other Important Info: None at this time.

and 12-inch piping for the new meter pit. There will be a new water pressure reducing valve vault for Brownstown Charter Township by installing the

necessary piping in the vault.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$46	\$0	\$0	\$46
Professional Services	\$9	\$8	\$8	\$2
Design & Construction Assistance (CS-201)	\$167	\$79	\$79	\$88
Construction (Build)	\$0	\$0	\$0	\$0



Project Title: Wholesale Water Meterpit Rehabilitation and Meter Upgrade - Phase II

Project Status: Active - Procurement - Construction Class Lvl 1: Water Class Lvl 2: Metering Class Lvl 3: General Purpose Lookup Location: V Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chandan Sood Director: Chandan Sood	Project Sc 95.7	core

Problem Statement:

The Great Lakes Water Authority (GLWA) operates two hundred ninety (290) wholesale water metering facilities to collect flow data for correct billing and analysis of the water system and has embarked upon a water metering improvement program. The first project of this program was Contract No. GLWA-CON-285 that started in November 2018 to complete fifty (50) sites. The WHOLESALE WATER METER PIT REHABILATATION AND METER REPLACEMENT PHASE II, is the second contract of the program. This contract is...

Scope of Work/Project Alternatives:

Work includes the demolition and removal of the existing flow metering system and components and replacement with new and upgraded flow metering technology, equipment and instrumentations as well as complete rehab of the existing pits. Flow metering equipment and instrumentation includes new flow meters, check valves, gate valves, reducers, new supports for meter, valves, piping, electrical systems, SCADA systems and cabinets. The work will consist of two main Tasks: Task 1 - Meter upgrade and ...

Other Important Info:

New/advanced metering, accurate billing, impact to Member Partners charges, impact on GLWA's water balance program

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build)	\$16,000	\$0	\$0	\$0	\$3,205	\$3,196	\$3,196	\$3,196	\$3,205	\$16,000



Project Title: Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Water Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: All Water Facilities	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Nick Hoffman	Project Score	
Director: Peter Fromm	0	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
This design build project will replace roofing systems on GLWA water plants, water booster pumping stations and sewage pumping stations that were determined to need replacement over the next 5 to 7 years based on the CS-1674 Roofing Assesment Contract. Replacement is	Remove existing roofing systems and replace with new roofing systems	The total estimated replacement value (2016 dollars) of the 1,682,727 square feet of roofing at the water treatment plants, sewage pumping stations and water booster pumping stations at \$33,142,054.
needed to protect the facilities interigty with regards to interiors, sensitive electrical equipment and process mechanical equipment vital to operations.		Project History: A condition assessment was performed and completed under Contract No. CS -1674 in 2016 that included all roofs located at GLWA's 5 water treatment plants, 19 water

GLWA's 5 water treatment plants, 19 water booster pumping stations and 11 sewage pumping stations. There were 268 separate roof sections totaling 1,682,727 s...



Project Title: Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$407	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$291
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$1,692	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,692
Design-Build # 1 (1803483)	\$33	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$33
Design-Build # 2	\$13,816	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$10,084
Design-Build # 3	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Lake Huron and Southwest Roof Replacement

Project Score

61.3

Project Engineer/Manager: Nick Hoffman

Director: Peter Fromm

Problem Statement:

This Design-Bid-Build project will replace identified roofing systems at GLWA Water Treatment Plants: Lake Huron and Southwest which were determined to need replacement over the next 6 to 8 years based on the CS-1674 Roofing Assessment Contract. Replacement is needed to protect the facilities integrity with regards to interiors, sensitive electrical equipment and process mechanical equipment vital to treatment and distribution operations.

Scope of Work/Project Alternatives:

Remove existing roofing system and replace with new built-up roofing systems as follows: Lake Huron Water Treatment Plant: Flocculator Building A & B, Chlorine Room, Low Lift Building, Chemical Building A & B, Southwest Water Treatment Plant: Lab and Office

Building A & B, Administration Building A & B,

Other Important Info:

A condition assessment was performed and completed under Contract No. CS-1674 in 2016 that included all roofs located at GLWA's 5 water treatment plants, 19 water booster pumping stations and 11 sewage pumping stations. There were 268 separate roof sections totaling 1,682,727 square feet of roof inspected during this condition assessment project.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY29-33
GLWA Salaries	\$99	\$0	\$0	\$0	\$99
Design/Engineering	\$400	\$0	\$0	\$0	\$400
Construction	\$2,211	\$0	\$0	\$0	\$2,211

06 WASTEWATER PROJECTS

WASTEWATER PROJECTS



- 51 ACTIVE
- 7 CLOSED
- 2 RECLASSIFIED








MORE: APPENDIX B

FIND THE FULL BUSINESS CASE EVALUATIONS FOR WASTEWATER PROJECTS IN APPENDIX B.

ty ID Activity Name		Remaining Duration	Actual/Forecasted Start	Actual/Forecastec Finish	FY2023 F F F I	FY2024	FY2025	FY2026
Wastewater Projects		9864	17-Oct-16 A	01-Jul-49		1.1.1.1.		<u>, , , , , , , , , , </u>
211002: WRRF PS No. 2 Pumping Improvements - Phase 1		417	17-Oct-16 A	20-Aug-23				
211005: WRRF PS No. 2 Improvements Phase II		6183	20-Feb-22 A	03-Jun-39				
211006: WRRF PS No. 1 Improvements		2721	30-Jun-21 A	10-Dec-29				
211007: WRRF PS #2 Bar Racks Replacements and Grit Collection	System Improvements	2804	30-Jun-21 A	03-Mar-30				
211008: WRRF Rehabilitation of Ferric Chloride Feed System in PS		458	05-Apr-21 A	30-Sep-23				
211009: WRRF Rehabilitation of the Circular Primary Clarifier Scum	Removal System	3169	30-Jun-21 A	03-Mar-31				
211010: Rehabilitation of Sludge Processing Complexes A and B	•	2191	01-Jul-25	30-Jun-31				
211011: WRRF PS1 Screening and Grit Improvements		4748	21-Aug-20 A	29-Jun-35				J 💶 🗖
212008: WRRF Ae ration Improvements 1 and 2		2864	12-Jan-22 A	02-May-30				
212009: WRRF Aeration Improvements 3 and 4		3713	01 - May-30	29-Jun-40				
212010: WRRF Conversion of Disinfection of all Flow to Sodium Hy	oochlorite and Sodium Bisulfite	3618	05-Feb-27	31-Dec-36				
213006: WRRF Improvements to Sludge Feed Pumps at Dewatering		2004	21-Nov-22	16-May-28				
213007: WRRF Modification to Incinerator Sludge Feed Systems at	Complex -II	366	02-Apr-18 A	30-Jun-23				
213008: WRRF Rehabilitation of the As h Handling Systems	· · ·	3532	30-Jun-21 A	29-Feb-32				
213009: WRRF Biosolids Processing Improvements		6902	11-Mar-23	31-Jan-42				
214001: WRRF Relocation of Industrial Waste Control Division and	Analytical Laboratory Operations	671	25-Jun-18 A	30-Apr-24				
216004: Rehabilitation of Various Sampling Sites and PS#2 Ferric C		366	18-Feb-19 A	30-Jun-23				
216006: As sessment and Rehabilitation of WRRF yard piping and u		1097	28-Dec-20 A	30-Jun-25				
216007: DTE Primary Electric 3rd Feed Supply to WRRF		1	29-Dec-21 A	30-Jun-22				
216008: Rehabilitation of Screened Final Effluent (SFE) Pump Statio	n	1781	05-Apr-21 A	15-May-27				
216011: WRRF Structural Improvements		1812	09-Apr-21 A	15-Jun-27				
222001: Oakwood District Intercommunity Relief Sewer Modification	n at Oakwood District	4203	30-Jun-21 A	31-Dec-33				
222002: Detroit River Interceptor (DRI) Evaluation and Rehabilitation		3867	03-Jul-17 A	29-Jan-33				
222008: North Interceptor East Arm (NIEA) 7 Mile Road Diversion St		550	01-Jan-22 A	31-Dec-23				
232001: Fairview Pumping Station - Replace Four Sanitary Pumps		100	23-Aug-23	30-Nov-23				
232002: Freud & Conner Creek Pump Station Improvements		4780	30-Jun-21 A	31-Jul-35				
232004: CONDITION ASSESSMENT AT BLUE HILL PUMP STATION		154	30-Jun-21 A	30-Nov-22				
233003: Rouge River In-system Storage Devices		2729	31-Dec-32	20-Jun-40				
260200: Sewer and Interceptor Rehabilitation Program		3653	01-Jul-23	30-Jun-33				
260201: CON-149, Emergency Sewer Repair		793	14-Jul-17 A	30-Aug-24				
260204: Conveyance System Engineering Services-1802575		1261	30-Jun-21 A	11-Dec-25				
260205: NWI Rehabilitation		733	01-Jul-21 A	01-Jul-24				-
260206: Conveyance System Repairs (Sewers)		2512	05-Mar-22 A	15-May-29				
260207: Rehabilitation of Woodward Sewer Systems		533	06-Oct-21 A	14-Dec-23				
260209: Sewer Rehabilitation and Repair		1461	01-Jul-22	30-Jun-26				
260210: Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, L	onvo Second Avenue and Shiawassee	3286	01-Apr-22 A	28-Jun-31				
260500: CSO Outfall Rehabilitation	onyo, occontraventic, and oniawassee	3652	01-Jul-25	30-Jun-35				
260508: B-39 Outfall Rehabilitation		665	25-Apr-22 A	24-Apr-24				
260510: Conveyance System Repairs (Outfalls)		2147	05-Dec-21 A	15-May-28				
260600: CSO FACILITIES IMPROVEMENT PROGRAM		9864	01-Jul-21 A	01-Jul-49			•	
260603: Conner Creek CSO RTB Automation Improvements		67	12-Jun-18 A	04-Sep-22	•			
260614: Structural Inspection & Structural Improvements		947	19-Aug-19 A	31-Jan-25				
260615: Puritan Fenkell & Leib Site Improvements		61	01-Oct-21 A	29-Aug-22				
260617: St. Aubin Chemical Disinfection Improvements		1793	15-Feb-23	12-Jan-28				
260618: Oakwood HVAC Project		581	11-Oct-19 A	31-Jan-24		<u> </u>		·
260619: Control System Upgrade - St Aubin, Lieb & Mile		786	15-Aug-22	08-Oct-24				
260620: Baby Creek Roof Replacement		93	21-Jun-21 A	30-Sep-22				
		92	21-Jun-21 A	29-Sep-22				
260621: Conner Creek Dike Improvements		324	30-Jun-21 A	29-Sep-22 19-May-23				
260622: CSO Emergency Generator Improvements				l				
260623: CSO Baby Creek Screen Rehabilitation	tations	562	01-Jul-21 A	12-Jan-24				
260700: Sewer System Infrastructure Improvements and Pumping S		4019	01-Jul-20 A	30-Jun-33		,		
260701: Conveyance System Infrastructure Improvements		1603	12-May-21 A	18-Nov-26				
260702: Pump Station Assets Updates		4017	02-Jul-25	30-Jun-36				
Construction Study Design Work In Progress	CIP 2024 - Integrate	d Master Scl June 2022 Up		Projects		e: 12-Oct-22 e: 30-Jun-22		Page 1 of 2



		Actual/Forecasted		022	FY2023	FY2	024	FY202	.5	FY2026	FY2027	FY202		/2029	FY2030	FY20
	Duration	Start	Finish	FFF	FFF	FF	FF	FFF	FF	FFF	FFF	FFFF	FFF	FFF	FFFF	FF
F REPLACEMENT FOR MULTIPLE FACILITIES PROGRAM	4018	01-Jul-26	30-Jun-37		· · · ·			•				· · · ·				
Roof Improvements Project	1005	17-Jan-22 A	30-Mar-25													
ity Optimization Program	5479	01-Jul-22	30-Jun-37													
on of HAZMAT Facility at WRRF	913	15-May-20 A	28-Dec-24													
loor Renovation	731	15-May-20 A	29-Jun-24				I									
Entrance Rehabilitation	879	15-May-20 A	24-Nov-24													
loor Renovation	1579	15-May-20 A	25-Oct-26													
	1019	01-Jun-22 A	13-Apr-25													
bilitation of the Secondary Clarifiers	3287	01-Jul-28	30-Jun-37													
bilitation of the Secondary Clarifiers Phase 1	3717	28-Feb-22 A	01-Sep-32													
etting Facility	6325	01-Jun-21 A	23-Oct-39													
wer Diversion and VR-15 Improvements	1794	03-Aug-25	01-Jul-30													
SO Control Plan	1097	01-Aug-19 A	30-Jun-25													
d Leib CSO Facilities Improvement Project	2480	30-Jun-21 A	13-Apr-29													
Safety Improvements and Building Rehabilitation	2204	01-Feb-22 A	11-Jul-28													
es Improvements II	2569	15-Dec-21 A	11-Jul-29						1							
System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CS(3018	23-Jan-24	27-Apr-32													
stem Improvements at Conner Creek and St. Aubin CSO Facilities	3017	25-Jan-24	28-Apr-32													
ements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities	2532	19-Jan-26	24-Dec-32													
vements at Puritan Fenkell and Seven Mile CSO Facilities	2532	23-Jan-23	28-Dec-29													
vements at Conner Creek and Belle Isle CSO Facilities	1557	21-Jan-30	26-Apr-34													
tem Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities	2530	21-Jan-26	24-Dec-32													
rovements at Puritan Fenkell and Seven Mile CSO Facilities	2166	20-Jan-27	24-Dec-32													
to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities	3746	22-Jan-25	25-Apr-35				1									
thfield CSO Facility Improvements	3308	01-Jan-22 A	20-Jul-31													
I Southfield VR-8 Gate Improvements	2532	19-Jan-26	24-Dec-32													
nt of Make-up Air Unit No. 2 at Conner Creek CSO Facility	348	14-Mar-22 A	12-Jun-23													
Outfall Improvements Project	1713	01-Jul-21 A	08-Mar-27													
CSO Facility Influent Flushing System	1801	20-Jan-32	24-Dec-36													
Inflation Allowance	2192		30-Jun-28													
ty: Electric Metering Improvement Program	1	01-Dec-21 A	30-Jun-22													
placement and Rehabilitation Program	574	05-Dec-26	30-Jun-28													
Imple CIP Project	2128	27-Apr-23	21-Feb-29													
s - Centralized Services	90	30-Jun-21 A	27-Sep-22													
astructure Improvements for Waste water Facilities	90	30-Jun-21 A	27-Sep-22													
Inflation Allowa ty: Electric Me placement and imple CIP Proje s - Centralize	ance etering Improvement Program Rehabilitation Program ect ed Services	ance2192etering Improvement Program1Rehabilitation Program574ect2128ed Services90	ance 2192 01-Jul-22 etering Improvement Program 1 01-Dec-21 A Rehabilitation Program 574 05-Dec-26 ect 2128 27-Apr-23 ad Services 90 30-Jun-21 A	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 ad Services 90 30-Jun-21 A 27-Sep-22	Ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 ad Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 ad Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 ad Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 d Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 ad Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	ance 2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	2192 01-Jul-22 30-Jun-28 ance 1 01-Dec-21 A 30-Jun-28 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	2192 01-Jul-22 30-Jun-28 etering Improvement Program 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22	2192 01-Jul-22 30-Jun-28 ance 1 01-Dec-21 A 30-Jun-22 Rehabilitation Program 574 05-Dec-26 30-Jun-28 ect 2128 27-Apr-23 21-Feb-29 od Services 90 30-Jun-21 A 27-Sep-22

Construction Study	CIP 2024 - Integrated Master Schedule - WWTP Projects	Run Date: 12-Oct-22	Page 2 of 2
Design Work In Progress	June 2022 Update	Data Date: 30-Jun-22	





Project Title: WRRF Rehabilitation of Primary Clarifiers Rectangular Tanks, Drain Lines, Electrical/Mechanical Building and Pipe Gallery

Project Status: Closed Class LvI 1: Wastewater Class LvI 2: WRRF Class LvI 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	₩ ₩ ₩ ₩ ₩ ₩ ₩ ₩	novation /W Master Plan /ater Master Plan Right edundancy E WTP Repurposing inear Assets Outside o redecessor Project(s)	-			GLANA Great Lakes Water Authority			
Project Engineer/Manager: Nicolas Nicolas			Project Sco	ore					
Director: Philip Kora			0						
Problem Statement: Rehabilitation of primary clarifier rectangular tan drain lines, electrical/mechanical building and pi gallery to meet NPDES Permit and NEC requirements	nks, Ti ipe in co ar R	The work to be completed under this project will include installing ventilation and atmospheric control for the pipe gallery, providing new lighting and installing a new fire alarm system. Rehabilitation of the twelve rectangular primary				Other Important Info: Challenges: N/A - Active Project not scored by review committee because is complete.			
		clarifiers. Rehabilitation c 15 and 16 is also part of							



Project Title: WRRF Rehabilitation of Primary Clarifiers Rectangular Tanks, Drain Lines, Electrical/Mechanical Building and Pipe Gallery

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$799	\$799	\$799	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1802474)	\$202	\$202	\$202	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1432A)	\$51	\$51	\$51	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1484)	\$516	\$516	\$516	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-291)	\$1	\$1	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (PC-757)	\$51,468	\$51,479	\$51,479	(\$11)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Miscellaneous	\$1,702	\$1,702	\$1,702	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: WRRF PS No. 2 Pumping Improvements - Phase 1

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside o Predecessor Project(s)		Great Lakes Water Authority			
Project Engineer/Manager: Vinod Sharma		Project Score				
Director: Philip Kora		0				
Problem Statement: Correct drifting issues of pumps and meet long term wet weather capacity needs	Scope of Work/Project This project involves eva recommending alternativ reliable pumping capacity for Pumps Nos. 11 and 1	luating and es for providing more y at Pump Station No. 2	Other Important Info: Challenges: Unable to improve the drift issues experienced at pump station 2.			

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$313	\$289	\$289	\$25	\$3	\$0	\$0	\$0	\$0	\$3	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 255)	\$220	\$157	\$157	\$63	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1444)	\$64	\$64	\$64	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC)	\$20	\$20	\$20	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1900318)	\$140	\$65	\$65	\$75	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (PC-795)	\$2,971	\$2,044	\$2,044	\$794	\$134	\$0	\$0	\$0	\$0	\$134	\$0



Project Title: WRRF PS No. 2 Improvements Phase II

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Main Raw Sewage Pumps at Pump Station 2
Project Engineer/Manager: Chris Wilson Director: Chris Nastally	Project Scor 77.4	e
Problem Statement: This project will improve the pump reliability of F 2 to meet NPDES permit flow capacity requirements.	 Scope of Work/Project Alternatives: PS- The preliminary scope of this project is to basis of design (study) report for rehabilitation/rebuilding plan for existing p station no. 2 and its control and any asso equipment. The study will evaluate the a VFDs to the three constant speed pumps not be limited to increasing the capacity of the study of the study	rehabilitated will require co-ordination with operations and careful planning to meet NPDES ciated permit requirements for the flow capacity during the construction phase.

pumps to meet the long-term goal for wet weather

rehabilitation/rebuilding of the pumps, replacement

capacity. Provide engineering design for

of HVAC System, ...

Project History: Pump Station No. 2 was built in 1994. Seven out of eight pumps are running since 1994. These pumps never attained the design capacity due to an unidentified drifting problem. The eighth pump (Pump No. 10) was installed under PC-740 with a modified suction elbow that provid...



Project Title: WRRF PS No. 2 Improvements Phase II

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$704	\$0	\$0	\$35	\$42	\$42	\$42	\$42	\$42	\$210	\$210
Professional Services	\$69	\$35	\$35	\$54	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$9,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$7,176
Design/Engineering (Phase #2)	\$428	\$0	\$0	\$77	\$110	\$146	\$94	\$0	\$0	\$350	\$0
Design/Engineering (Phase #3)	\$90	\$0	\$0	\$90	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$60,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,284
Pump Station #2 VFD Replacement	\$7,000	\$0	\$0	\$0	\$1,085	\$3,599	\$2,317	\$0	\$0	\$7,000	\$0
Pump Station #2 Mag Meter Replacement for Raw Sewage Pumps	\$1,000	\$0	\$0	\$197	\$401	\$400	\$1	\$0	\$0	\$803	\$0



Project Status: Active - Pre-Procurement - Construction Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Pump Station 1
Project Engineer/Manager: Jason Williams	Project Sc	ore

Director: Chris Nastally

Problem Statement:

Condition assessment and rehabilitation of all pumps at Pump Station No. 1 to increase efficiency and reliability. Rehabilitate the pump station to extend useful life.

Scope of Work/Project Alternatives:

The study/design work will identify all major parts including impellers and wear rings to be refurbished for each pump and all related appurtenances. The construction services will provide rehabilitation or replacement as determined in the study and design along with the sequencing of pump shutdown throughout the rehabilitation period.

78.6

Investigation and evaluation of all the inlet and outlet gates, associated actuators, Motor Control Centers (MCCs), HVAC system, Control System and provide reco...

Other Important Info:

Challenges: Adequate pumping capacity during construction.

Project History: Raw wastewater (influent) from the collection system flows to this Influent Pumping Station through the Detroit River Interceptor (16'D), Oakwood Interceptor (12.5'D) and North Interceptor East Arm (NIEA). Pumping Station No. 1 (PS-1) was constructed in the 1930s and has eight constant speed pumps of various capacities (six were installed in the 1940s and two more were added in 1956) and has a Firm Capacity (largest...



Project Title: WRRF PS No. 1 Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$828	\$114	\$114	\$84	\$98	\$98	\$98	\$98	\$98	\$491	\$142
Professional Services	\$179	\$136	\$136	\$43	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-102)	\$12,612	\$5,720	\$5,720	\$494	\$1,048	\$1,045	\$1,045	\$1,045	\$1,048	\$5,232	\$1,165
Design/Engineering (1900318)	\$47	\$50	\$50	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$73,922	\$0	\$0	\$2,654	\$12,613	\$12,579	\$12,579	\$12,579	\$12,613	\$62,963	\$8,305
Construction (Build) # 2	\$1,101	\$0	\$0	\$546	\$555	\$0	\$0	\$0	\$0	\$555	\$0
Construction (Build) # 3	\$3,377	\$0	\$0	\$1,675	\$1,702	\$0	\$0	\$0	\$0	\$1,702	\$0



Project Title: WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Pump Station 2, Grit channels
---	---	-------------------------------

Project Engineer/Manager: Jason Williams

Director: Chris Nastally

Problem Statement:

Replacement of all bar racks and associated equipment and addition of fine screens (1/4 inch) for more reliable and efficient screenings removal. Addition of screenings washing and compaction will reduce truck traffic and cost of disposal. Improvement of grit collection system with more efficient, grit collection and pumping system, and grit washing and classification will reduce truck traffic and cost of disposal. Improvements to the grit screenings and grit removal and handling systems will i...

Scope of Work/Project Alternatives:

The work consists of evaluation, design and construction of the replacement of the existing bar racks and ancillary equipment and gates, addition of new fine screens (1/4 inch) downstream of the bar racks, addition of screenings washing and compaction, inclusion of stacked tray grit removal or other technology within the aerated grit tank and grit washing and classification. Work also includes the upgrade and expansion of the existing building that houses the screens and the screenings and grit...

Project Score

75.7

Other Important Info:

*Innovation note: Install new grit removal equipment rather than replacement in kind (cyclonic).

Replacement of Bar Racks at Pump Station No. 2, Rehabilitation of Grit and Screening System at PS-2 and Rehabilitation of Sampling Sites at WWTP were combined into one project. The design of Rehabilitation of Sampling Sites is completed and was bid separately for construction. The previous design for Bar Rack System will not proceed for construction as designed. A new study, design and construction...



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$848	\$56	\$56	\$89	\$106	\$105	\$105	\$105	\$106	\$528	\$176
Professional Services	\$95	\$95	\$95	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1904337)	\$11,307	\$5,464	\$5,464	\$2,516	\$198	\$603	\$603	\$603	\$605	\$2,612	\$1,010
Construction (Build) # 1	\$82,000	\$0	\$0	\$0	\$4,489	\$13,654	\$13,654	\$13,654	\$13,692	\$59,143	\$22,857



Project Title: WRRF Rehabilitation of Ferric Chloride Feed System in PS-1 and Complex B Sludge Lines

Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: WRRF Class LvI 3: Primary Treatment Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilitie Predecessor Project(s) 	s Ferric Chloride Storage and Containment Area
Project Engineer/Manager: Chris Breinling	Projec	t Score

Project Score **78.3**

Problem Statement:

Director: Chris Nastally

The Ferric Chloride Systems at PS-1 is used to reduce phosphorus to the required permit levels. The system, which includes chemical storage tanks, secondary containment, valves, and piping is in need of rehabilitation. The Complex B sludge lines are clogged due to Struvite and need rehabilitation or replacement.

Scope of Work/Project Alternatives:

The scope of work will include study design and construction for the ferric chloride feed system at PS-1. Specifically it will include: a study to evaluate alternative locations for application of ferric chloride, a pilot study to test alternative application points, and inspection of the existing chemical feed systems. It will provide recommendations for system modifications and improvements, design of recommended system improvements, and construction of chemical feed system improvements. Eva...

Other Important Info:

*Innovation note: Align sizing & design with U of M phosphorus & enhanced carbon capture studies, as well as improved mixing of the ferric with primary influent.

Challenges: Maintaining capacity of the existing feed system during construction and determining the simplest system that will meet current and future phosphorous limits for both primary and secondary effluent.

Project History: There are phosphorous effluent permit limits for both primary effluent (during wet weather) and for se...



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$283	\$258	\$258	\$37	\$6	\$0	\$0	\$0	\$0	\$6	\$0
Professional Services	\$173	\$165	\$165	\$5	\$2	\$0	\$0	\$0	\$0	\$2	\$0
Design/Engineering (CS-166)	\$61	\$34	\$34	\$28	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1802543)	\$2,322	\$1,857	\$1,857	\$354	\$111	\$0	\$0	\$0	\$0	\$111	\$0
Design/Engineering (2002190)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC)	\$3	\$3	\$3	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (2002190)	\$9,839	\$4,151	\$4,151	\$5,310	\$1,340	\$0	\$0	\$0	\$0	\$1,340	\$0



Project Title: WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Fimary Circular Scum House, Inside

Project Engineer/Manager: Jason Williams

Director: Chris Nastally

Problem Statement:

The circular clarifiers scum removal system is over 10 years old and needs to be rehabilitated. This will help protect the secondary treatment process by preventing scum from entering the aeration tanks.

Scope of Work/Project Alternatives:

This project will provide for the study, design, and construction of new scum equipment in the Scum Buildings for the circular primary clarifiers (PCs). The study will consist of an evaluation of the existing process and simplified alternative systems for scum removal including the scum removal from the buildings. Future alternatives for scum disposal, such as addition to an anaerobic digestion process, will be considered. All alternatives will be evaluated for energy efficiency (reduction o...

Project Score

76.6

Other Important Info:

*Innovation note: Evaluate alternatives for energy efficiency.

Project History: There are 12 rectangular PCs and 6 circular PCs at the WRRF. PCs remove TSS, BOD, and phosphorous through a chemically enhanced settling process in addition to fats, oils, and grease (FOG or scum) by skimming the surface of the clarifiers and transporting the scum to a SB where it can be concentrated. The SBs for the rectangular clarifiers were recently rehabilitated. The SBs for the circular clarifiers utilize ...



Project Title: WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$351	\$13	\$13	\$35	\$40	\$40	\$40	\$40	\$40	\$199	\$106
Professional Services	\$138	\$44	\$44	\$104	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$2,040	\$252	\$252	\$168	\$0	\$0	\$0	\$1,137	\$265	\$1,402	\$314
Construction (Build) # 1	\$20,200	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$185	\$185	\$20,015



Project Title: Rehabilitation of Sludge Processing Complexes A and B

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Primary Treatment Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Complex B, Basement
Project Engineer/Manager: Chris Wilson Director: Chris Nastally		Project Score 89.7	

Problem Statement:

Both Complex A and Complex B have reached the end of their design life. The majority of the equipment for the two processes are located below grade in areas prone to flooding. Tanks are located above grade and have little or no access around the perimeter. This limits and reduces cleaning effectiveness. Both the valves and the pumps used to transfer sludge to the Biosolids Drying Facility (BDF) are past their design life. Equipment breakage affects the plant ability to process sludge.

Scope of Work/Project Alternatives:

The work consists of evaluation, design and rehabilitation of both Complex A and Complex B with scope to include tank repair to improve tank access and extend life, building and process repair to including structural, mechanical, process, electrical, and instrumentation replacement. Scope should focus on relocating the sludge pumps from below grade to above grade which could include new above grade structures and cross connecting pumps to allow for additional flexibility in feeding the BDF pro...

Other Important Info:

Maintaining the MDEQ-NPDES required capacity during the construction phase of the project.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$460	\$0	\$0	\$0	\$0	\$0	\$77	\$77	\$77	\$230	\$230
Professional Services	\$94	\$94	\$94	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$4,050	\$0	\$0	\$0	\$0	\$0	\$1,608	\$692	\$350	\$2,650	\$1,400
Construction (Build) # 1	\$17,500	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,503	\$3,503	\$13,997



Project Title: WRRF PS1 Screening and Grit Improvements

 ☑ Water Master Plan Righ ☑ Redundancy ☑ NE WTP Repurposing 		Great Lakes Water Authority
	Project Score 77.5	
	Redundancy Redundancy NE WTP Repurposing Linear Assets Outside comparison 	 Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) Project Score

Problem Statement:

Addition of fine screens (1/4 inch) for more reliable and efficient screenings removal is needed. Addition of screenings washing and compaction to reduce truck traffic and cost of disposal. Improvement of grit collection system with more efficient, state-of-the-art, grit collection and pumping system, grit washing and classification to reduce truck traffic and cost of disposal. Improvements to the grit screenings and grit removal and handling systems will improve the performance of all downstre...

Scope of Work/Project Alternatives:

The work consists of evaluation, design and construction of the addition of new fine screens (1/4 inch) downstream of the bar racks, addition of screenings washing and compaction, inclusion of stacked tray grit removal within the aerated grit tank and grit washing and/or classification. Work also includes the upgrade and expansion of the existing building that houses the screens and the screenings and grit handling and load out, including all lighting, HVAC, plumbing, electrical, and architectu...

Other Important Info:

Maintaining the MDEQ-NPDES required capacity during the construction phase of the project. Coordination with the CIP Number 211006



Project Title: WRRF PS1 Screening and Grit Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$882	\$0	\$0	\$41	\$49	\$49	\$49	\$49	\$81	\$278	\$403
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$15,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,428	\$1,428	\$9,003
Design & Construction Assistance # 2	\$210	\$0	\$0	\$210	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$78,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$40,664
Construction (Build) # 2	\$4,000	\$0	\$0	\$278	\$1,588	\$1,584	\$551	\$0	\$0	\$3,722	\$0



Project Title: WRRF Aeration Improvements 1 and 2

Project Status: Active - Procurement - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Secondary Treatment and Disinfection Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside o Predecessor Project(s) 		Aeration Basin 1 and ILP's 1 and 2
Project Engineer/Manager: Charles Reinhart		Project Sco	re

Director: Chris Nastally

Problem Statement:

The Intermediate Lift Pumps (ILPs) convey primary effluent to the secondary bioreactors (aeration decks). These pumps have reached the end of their useful life and are in need of replacement. The pump selection is integrally connected to improvements in the aeration decks related to the conversion to biological phosphorus removal, implementation of step feed and overall improved hydraulic control in the aeration decks and flow control through the secondary system. Implementation of biological p...

Scope of Work/Project Alternatives:

The work consists of evaluation, design and construction of the replacement of ILPs 1 & 2, conversion of aeration decks 1 & 2 to incorporate biological phosphorus removal, (including replacement of mixers in Bays 1, 2 and 3), relocation of the oxygen feed, and installing a new purge blower. Incorporation of step feed includes modification of the influent conditions to allow primary effluent to be directed to Bay 1, as well as two other locations down the length of the tank. Weir length will be ...

76.3

Other Important Info:

Opportunity for a common header system to allow for any ILP to supply any bioreactor. If feasible provide ILPs that can meet the regulatory and dry weather needs without the need for speed control.

Challenges: Maintaining the required wet weather secondary capacity of 930 MGD while operating efficiently during dry weather flows.

Project History: ILP Station No. 1 houses ILP Nos. 1 and 2. The pumps are vertical turbine type each with a maximum capacity of 365 MGD and a motor size of 2,5...



Project Title: WRRF Aeration Improvements 1 and 2

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,337	\$27	\$27	\$33	\$187	\$187	\$187	\$187	\$187	\$934	\$343
Professional Services	\$60	\$99	\$982	\$472	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$1,530	\$0	\$0	\$38	\$219	\$218	\$218	\$218	\$219	\$1,091	\$401
Construction (Build) # 1	\$73,301	\$0	\$0	\$1,831	\$10,472	\$10,443	\$10,443	\$10,443	\$10,472	\$52,272	\$19,198



Project Title: WRRF Aeration Improvements 3 and 4

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Secondary Treatment and Disinfection Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Aeration Basin 4, and ILP's 3, 4, and 7
Project Engineer/Manager: Chris Wilson		Project Score	
Director: Chris Nastally		76.3	

Problem Statement:

The Intermediate Lift Pumps (ILPs) convey primary effluent to the secondary bioreactors (aeration decks). These pumps have reached the end of their useful life and are in need of replacement. The pump selection is integrally connected to improvements in the aeration decks related to the conversion to biological phosphorus removal, implementation of step feed and overall improved hydraulic control in the aeration decks and flow control through the secondary system. Implementation of biological p...

Scope of Work/Project Alternatives:

The work consists of evaluation, design and construction of the replacement of ILPs 3, 4 & 7, conversion of aeration decks 3 & 4 to incorporate biological phosphorus removal, including replacement of mixers in Bays 1 and 2, relocation of the oxygen feed, and installing a new purge blower. Incorporation of step feed includes modification of the influent conditions to allow primary effluent to be directed to Bay 1, as well as two other locations down the length of the tank. An assessment of recon...

Other Important Info:

Maintaining the MDEQ-NPDES required capacity during the construction phase of the project.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$625	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$89
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$10,920	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,233
Construction (Build) # 1	\$57,983	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Secondary Treatment and Disinfection Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Chlorination Building, Inside
Project Engineer/Manager: TBD	Project Score 89.7	
Director: Chris Nastally	09.7	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
With the completion of the RRO Disinfection Project (CIP 212006), storage and feed of sodium hypochlorite to the primary effluent bypass with sodium bisulfite for dechlorination has been enabled. Elimination of the use of gaseous chlorine for disinfection of the secondary effluent and replacement with sodium hypochlorite will increase operator and public safety in and around the plant site.	existing system. The assessment will include	n to nit

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$325	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$191
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$1,398	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,097
Construction (Build) # 1	\$4,509	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,500



sludge from Storage Tanks 3 & 4 supplies the centrifuges on the lower level of Dewatering...

Project Title: WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities

Project Status: Active - Procurement - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Residuals Management Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Field pump in Complex A
Project Engineer/Manager: Jared Buzo		Project Score	
Director: Chris Nastally		76.6	
Problem Statement:	Scope of Work/Project	Alternatives:	Other Important Info:
Improvements to the sludge feed pumping (SFP) system will provide a wide range of operating options. Variable Frequency drive and Hydraulic	construction for the repla	cement of sludge feed	Challenges: Maintaining Plant Operational Capacity during construction.
drive units for SFP 1 and 2 are located below grade and the area has flooded. A single recycle valve for SFP 3 and 4 puts the plant at a higher risk for system outages.	modifications to the pump	bing system at the WRRF.	Project History: Water Resource Recovery Facility (WRRF) has six (6) Sludge Storage Tanks (SST-1, 2, 3, 4, 5 &6), which feed sludge to the dewatering facilities (i.e. belt filter presses complexes and complex II centrifuges.) Typically, sludge from Storage Tanks 1 & 2 supplies the centrifuges on dewatering complex II upper level;

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$259	\$7	\$7	\$7	\$50	\$50	\$50	\$50	\$44	\$244	\$0
Professional Services	\$338	\$291	\$291	\$49	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$2,060	\$0	\$0	\$137	\$1,000	\$363	\$156	\$215	\$189	\$1,923	\$0
Construction (Build) # 1	\$5,000	\$0	\$0	\$0	\$0	\$0	\$1,397	\$1,917	\$1,686	\$5,000	281 ^{\$0}



Project Title: WRRF Modification to Incinerator Sludge Feed Systems at Complex -II

Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: WRRF Class LvI 3: Residuals Management Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GELVAA Great Lakes Water Authority
Project Engineer/Manager: Chris Breinling	Project Sc	ore	
Director: Philip Kora	96.2		

Problem Statement:

GLWA have an ongoing study and design of sludge cake conveyance system improvements project as a result of a fire in March 2016 in the Complex –II Incinerators building. The construction of this project will provide a cleaner, fire resistant, reliable and safe sludge feed to the incinerators.

Scope of Work/Project Alternatives:

The restoration of sludge conveying capacity, which was lost due to the fire damage and to provide improved sludge conveyance from each dewatering facility to the incinerators. Replacement of 19 MCCs and Replacement of the Unit Substation EB-26 in Incineration Complex II is included.

Other Important Info:

Challenges: Maintaining the sludge conveyance capacity to meet permit requirements during the construction of these improvements, will be the most significant challenge.

Project History: The C-II Incineration complex is over 40 years old. Major rehabilitation had been deferred over the years in anticipation of an alternative Biosolids disposal solution to handle all the solids. Complex-II has many major pieces of equipment that are nearing the end of their useful life and require replacemen...



Project Title: WRRF Modification to Incinerator Sludge Feed Systems at Complex -II

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$767	\$753	\$753	\$36	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-060)	\$2,086	\$589	\$589	\$1,497	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-291)	\$58	\$58	\$58	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1432A)	\$29	\$29	\$29	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC)	\$130	\$130	\$130	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-197)	\$19,537	\$18,893	\$18,893	\$743	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Miscellaneous	\$1,458	\$1,458	\$1,458	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: WRRF Rehabilitation of the Ash Handling Systems

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Residuals Management Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Incineration Complex II, Ash System			
Project Engineer/Manager: Chris Wilson	Project Score				
Director: Chris Nastally	59.5				
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:			
The ash systems convey and store ash for ultim disposal. The incinerators cannot be used if bo the systems are not working.		*Innovation note: Due to only 10-15 years remaining useful life on Complex I, reconsider recommissioning wet ash.			
	filters, HVAC, boilers, miscellaneous silo repairs (concrete, access, etc.) site work and drainage, and miscellaneous structural repairs (foot bridge, spalling concrete, etc.) at the dry ash handling system. It will also include the pumps, piping, and sluicing system at the wet ash system.	Project History: The C-I and C-II Incinerators have been the primary source for processing Biosolids at the GLWA WRF since the plant was first built. The original ash handling system was a			

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$264	\$26	\$26	\$0	\$0	\$0	\$36	\$36	\$36	\$107	\$131
Design/Engineering (1803499)	\$1,720	\$125	\$125	\$0	\$0	\$0	\$513	\$513	\$49	\$1,075	\$520
Construction (Build) # 1	\$5,200	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	284 \$5,200



Project Title: WRRF Biosolids Processing Improvements

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Residuals Management Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chris Wilson	Project Scor	e
Director: Chris Nastally	79.6	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The Central Operating Facility (COF) includes three trains of live bottom sludge storage bins, lime silos, sludge/lime mixers and numerous belt and	The project will construct one/or a mix of following alternatives: 1.Mesophilic Anaerobic Digestion (MAD)	from the incinerator feed system, which consists

three trains of live bottom sludge storage bins, lime silos, sludge/lime mixers and numerous belt and screw conveyors for truck loading. Lime can be added for odor reduction and the sludge landfilled or stabilized and land applied.

The Complex I incinerators were constructed in 1940 and include six, 11 hearth units with capacity of 10 wet tons/hr. These were decommissioned in early 2017.

Complex II Incineration was constructed in the 1970s and...

1.Mesophilic Anaerobic Digestion (MAD) of Thickened Primary Sludge (TPS) and Thickened Fermented Sludge (TFS) with centrifuge dewatering and drying at a rehabilitated Biosolids Drying Facility (BDF).

2.Sludge screening, pre-dewatering, and Thermal Hydrolysis Process (THP) of FS and MAD of hydrolyzed sludge and TPS. Centrifuge dewatering and drying of the digested sludge at a rehabilitated BDF.

3.Identical to Alt 2, but...

Sludge cake is discharged into the incinerators from the incinerator feed system, which consists of a live bottom hopper, transfer screw conveyors, a weighing belt conveyor, and a feed screw conveyor. From the incinerator feed system, the sludge enters the top of the incinerator and proceeds downward from one hearth to another as the sludge goes through the various stages of the combustion process, including drying, volatilization, burning of fixed carbon, ash cooling, and final discharge as as...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,703	\$0	\$0	\$0	\$94	\$103	\$103	\$301	\$516
Design/Engineering	\$27,720	\$0	\$0	\$0	\$548	\$1,332	\$1,336	\$3,216	\$7,754
Construction	\$170,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$37,242



Project Title: WRRF Relocation of Industrial Waste Control Division and Analytical Laboratory Operations

Project Status: Closed Class LvI 1: Wastewater Class LvI 2: WRRF Class LvI 3: Industrial Waste Control Lookup Location: System Wide Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLWAA reat Lakes Water Authority
Project Engineer/Manager: Nicolas Nicolas Director: Philip Kora	Project So O	core	

Problem Statement:

Laboratory Optimization, Continued operation of Industrial Waste Control (IWC) and laboratory, lease termination for analytical laboratory, and utilization of available space in WRRF new Administration Building (NAB)

Scope of Work/Project Alternatives:

Relocate the Industrial Waste Control (IWC) Division and Analytical Laboratory to the New Administration Building (NAB) at WRRF. Consolidate the existing Operations Laboratory with Analytical Laboratory.

Other Important Info:

Challenges: Maintaining the laboratory operations during relocation.

Project History: GLWA implements an Industrial Pretreatment Program (IPP). A key component of the IPP includes the performance of analytical testing on wastewater samples collected from industrial and commercial sources. The Industrial Waste Control Division (IWC) is responsible for implementation of the IPP. IWC activities are housed at the Livernois Center Building (LCB) while the Analytical Laboratory leases space on...



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$222	\$222	\$222	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 262, CS-1481, 1901083)	\$986	\$993	\$993	(\$7)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 2 (1803776, CON-280)		\$13,085	\$13,085	\$240	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Rehabilitation of Various Sampling Sites and PS#2 Ferric Chloride System at WRRF

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF Project New to CIP:	WW Master Plan Water Master Plan Right Sizing	Great Lakes Water Authority
Project Engineer/Manager: Ihsan Wahab	Project Score	
Director: Philip Kora	94.7	
Problem Statement: Rehabilitation of the sampling facilities will improve system reliability and allow for consistent and accurate sampling. This will help to facilitate accurate reporting to MDEQ. The rehabilitation of Ferric Chloride system will improve the phosphorous removal to comply with the Permit.	Scope of Work/Project Alternatives: The scope of work includes: Replacement of existing sampling equipment, installing new samplers, pumps, piping, housing and support equipment such as I&C, HVAC, etc. at the various sampling sites. It also includes: Replacement of two existing steel Ferric Chloride tanks at PS#2 with four (4) smaller tanks. Providing new piping layout, gravity feed, and self- cleaning strainer. Rehabilitating the Ferric Chloride Unloading station, associ	Other Important Info: *Innovation note: Rehab may include alternative online/real-time sampling & analysis, as well as improved mixing of the ferric with primary influent. The design for Grit & Screening System and Sampling Station were complete under an As Needed Engineering Services Contract. The construction for Rehabilitation of Sampling Sites will be bid out separately. The Bar Rack System will not proceed for construction as designed. Challenges: Maintaining the MDEQ-NPDES required capacity during the con



Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$317	\$347	\$347	(\$11)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-292)	\$136	\$118	\$118	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-301)	\$889	\$421	\$421	\$470	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1481)	\$271	\$271	\$271	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1499)	\$124	\$124	\$124	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC)	\$49	\$49	\$49	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (1802410)	\$6,556	\$5,407	\$5,407	\$1,582	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (1900744)	\$0	\$56	\$56	(\$56)	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Assessment and Rehabilitation of WRRF yard piping and underground utilities

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Secondary Area
Project Engineer/Manager: Nicolas Nicolas	Project Score	
Director: Philip Kora	79	

Problem Statement:

Yard piping and underground utilities are vital to the operations of the WRRF. The integrity of these systems will be maintained with this project. The Secondary Water system needs to be relocated or completely refurbished to provide uninterrupted water for fire protection and process applications such as seal water to the pumps. Some of the yard piping is original to the plant and requires a condition assessment.

Scope of Work/Project Alternatives:

This project will include the study, design, and construction for the needed improvements to yard piping and underground utilities. This includes right sizing, as-built confirmation and condition assessment of our yard piping and underground utilities. It is possible that the secondary water system may need to be relocated. The distribution models for the water systems will also need to be updated. A redundant potable water feed to the WRRF will also be evaluated.

Other Important Info:

Reliable utility is a critical aspect of O&M for the facility and to avoid outages.

Project History: Some of the pipe lines at the WRRF have been in existence since the plant was built. As the plant has grown, so have the systems. In general, the majority of the changes to the multiple systems occurred when the specific buildings or components to the plant were built or renovated. Therefore, an evaluation and necessary replacement of these pipelines is needed.

Challenges: Maintaining ad...



Project Title: Assessment and Rehabilitation of WRRF yard piping and underground utilities

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$366	\$183	\$183	\$68	\$65	\$65	\$0	\$0	\$0	\$130	\$0
Professional Services	\$142	\$137	\$137	\$6	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1903601)	\$3,348	\$1,305	\$1,305	\$639	\$723	\$721	\$0	\$0	\$0	\$1,444	\$0
Construction (Build) # 1	\$22,449	\$2,629	\$2,629	\$6,245	\$7,016	\$6,996	\$0	\$0	\$0	\$14,012	\$0



Project Title: DTE Primary Electric 3rd Feed Supply to WRRF

Project Status: Closed Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facil Predecessor Project(s) 		Geat Lakes Water Authority
Project Engineer/Manager: Phillip Kora	Pro	oject Score	
Director: Philip Kora	0		

Problem Statement:

The scope of this project includes design and construction of 3rd 120 KV primary electric supply transmission line (design, build and maintain by DTE) tapping into the 120 kv waterman-Zug line in the vicinity of Dearborn St. and Copland St right of way at Tower 1368 per the agreement between DTE and GLWA dated May 2, 2019. GLWA is responsible to secure the property right-of-way from the property owners as well as environmental remediation and cleanup including hauling and disposal of any soil.

Scope of Work/Project Alternatives:

GLWA also is responsible to provide the connection from the service point (last steel pole installed by DTE) to GLWA's equipment on GLWA's property. This primary transmission power line will energize the already installed new 120-13.8 industrial substation owned by GLWA near EB-1.

Other Important Info:

Challenges: Negotiation with private property owners and testing of the automatic switch required co-ordination with operations. GLWA and DTE executed the new agreement in May 2019.



Project Title: DTE Primary Electric 3rd Feed Supply to WRRF

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$583	\$553	\$553	\$30
Professional Services	\$33	\$33	\$33	\$0
Design & Construction Assistance # 1 (CS- 189, CS-1433)	\$118	\$53	\$53	\$65
Design/Engineering (CS-1433)	\$48	\$15	\$15	\$33
Design/Engineering (1900318)	\$65	\$65	\$65	\$0
Construction (Build) # 1	\$5,067	\$3,277	\$3,277	\$1,790



Project Title: Rehabilitation of Screened Final Effluent (SFE) Pump Station

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	SFE Building, Basement

Project Engineer/Manager: Chris Wilson

Director: Chris Nastally

Problem Statement:

The Screened Final Effluent (SFE) Pump Station provides SFE water to many of the GLWA WRRF treatment processes and needs to be completely rehabilitated to maintain uninterrupted supply of SFE water to these processes.

Scope of Work/Project Alternatives:

This project will include the study, design, and construction for the needed improvements to the SFE pump station. This includes required capacity, pumps, strainers, piping, controls, building improvements, and electrical supply. This will also include a study to evaluate the potential for replacing the secondary water with SFE utilization where feasible and an alternative analysis to the existing carrier water at chlorination/dechlorination facility, seal water, recovery needs which may incl...

Project Score

63.2

Other Important Info:

*Innovation note: Optimizing of a valuable resource recovered for facility needs. Project History: The SFE pump station has eight pumps with a total capacity of approximately 135 MGD. Pumps 1,2,4, and 6 were installed in 1973, pumps 3 and 5 in 1980, and pumps 7 and 8 in 1998. The older pumps were rebuilt in 1998. Strainers have been reconditioned over time. Due to the critical nature of the SFE pump station a significant upgrade/rehabilitation is required. In addition, the two 5 kV transformer...



Project Title: Rehabilitation of Screened Final Effluent (SFE) Pump Station

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$574	\$20	\$20	\$99	\$118	\$118	\$118	\$103	\$457
Professional Services	\$903	\$274	\$274	\$670	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1802887)	\$3,960	\$29	\$29	\$2,698	\$54	\$410	\$410	\$358	\$1,232
Design/Engineering (CS-166)	\$238	\$35	\$35	\$41	\$43	\$43	\$43	\$38	\$168
Construction (Build) # 1	\$58,300	\$1,355	\$1,355	\$0	\$2,492	\$18,947	\$18,947	\$16,559	\$56,945



Project Status: Active - Procurement - Negotiation Phase - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF	Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s)	Incineration Building
Project Engineer/Manager: Alfredo Lava Director: Chris Nastally	Project Score 64.4	
Problem Statement: The WRRF facilities are some of the oldest facilities within the GLWA infrastructure and are beyond their original design lives. In order to assure the safety of GLWA personnel working at the WRRF and to increase operational reliability, GLWA is initiating a long-term structural maintenance program. The program will start with a full structural needs assessment and a four-year program of implementing the highest priority repairs in order of priority.	Scope of Work/Project Alternatives: The program will include a complete field assessment and structural condition report, classification of recommended repairs into levels of urgency, estimating quantities and the costs of repairs, developing a three-year repair program to address high priority repairs, design and implementation of repairs, preparation of as-built drawings and final project report. The Work includes improvements to be designed, administered, and constructed by the D/B Contractor including civil/site, architectura	Other Important Info: None

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$371	\$5	\$5	\$62	\$77	\$77	\$77	\$74	\$0	\$305
Professional Services #1	\$116	\$45	\$45	\$96	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services #2	\$2,030	\$0	\$0	\$352	\$425	\$424	\$424	\$406	\$0	\$1,678
Design-Build	\$12,639	\$0	\$0	\$2,105	\$2,666	\$2,659	\$2,659	\$2,550	\$0	\$10,534



Project Title: Oakwood District Intercommunity Relief Sewer Modification at Oakwood District

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: Interceptor Lookup Location: Oakwood District Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Overall Plan for NWI Diversion to Oakwood Facilities
Project Engineer/Manager: Biren Saparia Director: Biren Saparia		Project Score 62.7	

Problem Statement:

The Oakwood PS and CSO basin are currently under-utilized. Surcharging in Northwest Interceptor (NWI) has increased the CSOs and reduced the ability of customers to discharge into the NWI. A concept to isolate the downstream portion of the NWI from the WRRF and divert flow to the Oakwood PS was evaluated and refined under the Wastewater Master Plan Project (WWMP). The purpose of this project is to implement the WWMP recommended relief connection from the NWI to the Oakwood PS.

Scope of Work/Project Alternatives:

The scope of this project involves Study, Design, and Construction Phase Activities. The study phase will consist of determining the feasibility of advancing the project to the Design and Construction stages. Based on the efforts under the Study the Consultants will proceed with design and construction phase activities.

Other Important Info:

Challenges: Maintaining the wet weather contract capacities and adequate CSO treatment during extreme storm events and mitigating basement and street flooding in the District and intercommunity regional districts are the most significant challenges for the project to address. Other Important Info: The Oakwood District is located in the southwest portion of the City of Detroit covering an area of 1,520 acres. Some areas of the District are situated in relatively lowlying, flood prone topograp...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$732	\$11	\$11	\$3	\$0	\$0	\$0	\$0	\$0	\$0	\$615
Design/Engineering (2002655)	\$5,696	\$2,054	\$2,054	\$543	\$0	\$0	\$0	\$0	\$0	\$0	\$2,869
Construction (Build) # 1	\$75,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$64,219



Project Title: Detroit River Interceptor (DRI) Evaluation and Rehabilitation

Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: Field Services Class LvI 3: Interceptor Lookup Location: Detroit River Interceptor Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilitie Predecessor Project(s) 	ies
Project Engineer/Manager: Mini Panicker	Projec	ect Score
Director: Todd King	66.4	I

Problem Statement:

The DRI was constructed under multiple contracts from the 1910's to the 1930's and has been in service since that time. Between 2012 and 2016, a visual inspection was completed of the DRI beginning at Alter Road and extending to near the WRRF. Significant distress was observed in some sections of the DRI during these inspections, and by 2017, it was clear that a major rehabilitation of the interceptor was necessary to prevent further deterioration and to limit the potential for catastrophic fai...

Scope of Work/Project Alternatives:

The Preliminary Scope of Work of the Project is to review the existing records, investigate the existing conditions, provide the necessary cleaning/rehabilitation/replacement to optimize the design capacity of the interceptor and to extend the service life of this asset.

Other Important Info:

Challenges: DRI had significant flow control challenges for both inspection and rehabilitation. As part of this project major flow control structures were constructed to meet these challenges.



Project Title: Detroit River Interceptor (DRI) Evaluation and Rehabilitation

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1,905	\$194	\$194	\$138	\$165	\$164	\$164	\$164	\$165	\$822	\$753
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (DB- 226)	\$86,231	\$39,937	\$39,937	\$12,573	\$12,459	\$12,425	\$11,097	\$0	\$0	\$35,980	\$0
Design-Build # 2 (CON-183)	\$4,408	\$4,408	\$4,408	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
TBD/Unallocated	\$21,015	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,061	\$2,061	\$18,954



Project Title: North Interceptor East Arm (NIEA) 7 Mile Road Diversion Structure

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: Interceptor Lookup Location: ✓ Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizin Redundancy NE WTP Repurposing Linear Assets Outside of Fac Predecessor Project(s) 		GELVAA Great Lakes Water Authority
Project Engineer/Manager: Jody Caldwell Director: Jody Caldwell		oject Score 3.9	

Problem Statement:

Oakland-Macomb Interceptor Drain Drainage District's (OMIDDD) is proposing new flow controls within the NIEA near 7-Mile, as part of the repair work currently being designed by OMIDDD within the NIEA upstream of Meldrum.

There are four sewer connections through which wastewater is discharged into the NIEA. On the upstream end of the NIEA, the OMIDDD discharges wastewater from the NESPS. Downstream of the NESPS, there are three gated drop connections to the NIEA at its crossings with the Firs...

Scope of Work/Project Alternatives:

The scope of work consists of the construction of a new flow control structure and automation of an existing flow control gate at the point of connection between the NIEA and the 7-Mile Relief Sewer.

This project is being undertaken by OMIDDD as part of their planned NIEA rehabilitation work. GLWA is currently considering cost sharing options for this project as GLWA believes this automated gate structure has operational benefit.

GLWA has evaluated the benefit of the automated gate stru...

Other Important Info:

Within Section 6.11 Collection System Redundancy Assessment of the Wastewater Master Plan, identifies the NIEA diversion at 7-Mile Road as a dry weather flow redundancy need.

Project not scored by risk committee since it is critical or for emergency repairs

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$5,000	\$0	\$0	\$2,479	\$2,521	\$2,521



Project Title: Fairview Pumping Station - Replace Four Sanitary Pumps

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: Pump Stations Lookup Location: Fairview Pumping Station Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jorge Nicolas Director: Peter Fromm	Project Score 63.6	
Problem Statement: Replacement and upgrade of pumping equipment's to improve transportation of waste water to the treatment plant	Scope of Work/Project Alternatives: The scope of work consists of the study, design, and construction of four new pumping systems including inlet and discharge valves and wet well hydraulics. This also includes enlarging doorways, revamping roadways, and upgrading electrical and control systems.	Other Important Info: This project replaces all existing old pumping units with a state of the art dry pit pumping units with associated I&C and Ovation control from SCC This project was not scored by risk committee because it is far advanced



Project Title: Fairview Pumping Station - Replace Four Sanitary Pumps

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$432	\$303	\$303	\$79	\$53	\$0	\$0	\$0	\$0	\$53	\$0
Professional Services	\$19	\$19	\$19	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 1747, CON-297, CS- 1488)	\$7,278	\$5,896	\$5,896	\$951	\$573	\$0	\$0	\$0	\$0	\$573	\$0
Design/Engineering (CON-297)	\$41	\$41	\$41	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-1488)	\$30	\$30	\$30	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-297)	\$38,670		\$33,095	\$3,811	\$1,870	\$0	\$0	\$0	\$0	\$1,870	\$0
Miscellaneous (Insurance)	(\$305)	(\$305)	(\$346)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Freud & Conner Creek Pump Station Improvements

 Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: Pump Stations Lookup Location: Conner Creek & Freud Pump Stations Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right S Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 	
Project Engineer/Manager: Mini Panicker Director: Biren Saparia		Project Score 94.1

Problem Statement:

Both Freud and Connor pump stations experience reliability challenges associated with the age of the equipment. Their wet wells cannot be isolated from the influent collection system to allow for inspection and maintenance. Modifications and improvements to these pump stations are necessary to protect the health, safety, and welfare of the residents. The primary objective of this project is the study of the overall performance of Connor Creek and Freud sewage pumping stations developing the des...

Scope of Work/Project Alternatives:

Provide a basis of design, and final design for an operational strategy to optimize the utilization of interconnected piping and operation between Connor Creek and Freud pumping stations and the Connor Creek Retention and Treatment Basin. Provide construction of the project and construction assistance during construction.

Other Important Info:

Challenges: Meeting the collection system transport capacity during the construction.

Project History: The Connor Creek Pump Station (CCPS) was originally built in 1928 with four storm water pumps, each with a rated capacity of 500 cubic feet per second (cfs). The CCPS was expanded in 1940 adding four more pumps of the same capacity. The pump station currently has a total capacity of 4,000 cfs and a firm capacity of 3,500 cfs. The pumps are primed using a vacuum system that relies on the f...



Project Title: Freud & Conner Creek Pump Station Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$7,483	\$2,699	\$2,699	\$304	\$380	\$379	\$379	\$379	\$380	\$1,897	\$1,896
Professional Services	\$49	\$49	\$49	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-120)	\$24,411	\$8,578	\$8,578	\$513	\$549	\$548	\$3,804	\$3,804	\$558	\$9,263	\$4,330
Design/Engineering (MISC)	\$8	\$8	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-109)	\$5,086	\$5,086	\$5,086	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Phase 2) - Freud Pump Station	\$90,460	\$460	\$460	\$2,745	\$16,470	\$16,425	\$16,425	\$16,425	\$16,470	\$82,215	\$5,040
Construction (Phase 3) - Connor Pump Station	\$431,000	\$0	\$0	\$0	\$4,415	\$8,854	\$8,854	\$8,854	\$24	\$31,000	\$273,167



Project Title: CONDITION ASSESSMENT AT BLUE HILL PUMP STATION

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: Pump Stations Lookup Location: Blue Hill Pump Station - Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker	Project Score	
Director: Todd King	60.6	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The condition of the Blue Hill PS has not been accurately established to the metrics being established for other GLWA pumping stations. A new condition assessment is required.	Perform station inspection by a multi-discipline team of specialists in pumps, valves, electrical, HVAC, structural, building envelope I&C, security, and building mechanical systems. Perform wire to water efficiency tests	Performance of this pumping station is connected to flood control objectives for Conner and Freud Pumping Stations.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$58	\$0	\$0	\$58
Professional Services	\$0	\$0	\$0	\$0
Design/Engineering	\$200	\$0	\$0	\$200



Project Title: Rouge River In-system Storage Devices

 Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: In System Devices (Dams, ISD's) Lookup Location: Rouge Riiver Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizin Redundancy NE WTP Repurposing Linear Assets Outside of Faci Predecessor Project(s) 		GLANA Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker Director: Biren Saparia	Pro 88	iject Score .2	
Problem Statement:	Scope of Work/Project Altern	atives: Othe	r Important Info:

The Rouge River receives untreated CSO discharges from GLWA CSO outfalls and outfalls from other Member combined sewer systems during wet weather. CSO control strategies that deal with first flush capture from small storms is typically a cost-effective implementation step in an overall CSO control program. Studies for the Wastewater Master Plan have shown the effectiveness of controlling first flush for small storms using receiving water modeling. Nine (9) locations on DWSD trunk sewers eas...

pe of work/Project Alternatives:

Perform sewer inspections, utility survey, and flow metering to establish and prioritize the siting of 9 new In-System Storage Devices (ISD)

Perform preliminary and final design of the ISDs, including upstream and downstream access points, power supply and instrumentation.

Construct 9 new inflatable dam in-system storage devices (ISD). Modify existing manholes or construct new access points upstream and downstream of each ISD. Provide electrical power, above ground structures for pneum...

Other Important Info:

The new ISD devices would be installed in trunk sewers owned and operated by DWSD. These are not GLWA leased sewers. A legal agreement may need to be prepared for GLWA to construct, operate, and maintain.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$497	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$8,839	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,761
Construction (Build) # 1	\$37,100	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0 306



Project Title: Sewer and Interceptor Rehabilitation Program

 Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker	Project Score	

0

Director: Todd King

Problem Statement:

The GLWA Collection System consists of approximately 185 miles of pipelines and associated manholes. As part of the baseline condition assessment, the trunk sewers and interceptors were inspected for structural integrity and maintenance issues in accordance with the National Association of Sewer Service Companies (NASSCO) standards. Rehabilitation and replacement program of the existing sewers and interceptors is identified after the condition assessment. Sewer rehabilitation program is necess...

Scope of Work/Project Alternatives:

Provide as needed CCTV and/or sonar inspection of the GLWA Collection System Interceptors and Trunk Sewers to assess the existing conditions as per the National Association of Sewer Service Companies' (NASSCO) Pipeline Assessment Certification Program (PACP) standards. Evaluate the existing conditions, and provide the necessary cleaning/rehabilitation/replacement to optimize the design capacity of the collection system and to minimize inflow and infiltration into the collection system.

Other Important Info:

Challengers: Large sewers and interceptors may have flow control challenges for both inspection and rehabilitation.

Project History: The installation of some of these interceptors and sewers dates back to 1912 under various contracts. Condition assessment of sewers to assess the existing conditions are necessary and will be done every 5 to 7 years. Recommendations from these inspections may indicate further need for cleaning, rehabilitation or replacement.



Project Title: Sewer and Interceptor Rehabilitation Program

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$172	\$0	\$0	\$0	\$17	\$17	\$17	\$17	\$17	\$86	\$86
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$5,258	\$0	\$0	\$0	\$0	\$0	\$0	\$1,955	\$1,960	\$3,914	\$1,344
TBD/Unallocated	\$13,687	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,933	\$2,933	\$10,754
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Project Execution -Innovation Construction GLWA WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: Systems Control Center Redundancy Class Lvl 3: General Purpose **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: Sewers and Linear Assets Outside of Facilities ~ Interceptors **Predecessor Project(s) Project New to CIP:** Project Engineer/Manager: Mini Panicker **Project Score** 76.9 **Director:** Todd King **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: Most of the GLWA existing sewers within the This is to address any immediate/urgent Challenges: Large sewers and interceptors may collection system are older than 80 years. Due to rehabilitation/repair needs for the GLWA Collection have flow control challenges for both inspection the age and deterioration of the sewer pipes, System and rehabilitation. immediate repair and/or rehabilitation is often required. This project will encompass all work as

Current Expenses (All figures are in \$1,000's)

as directed by GLWA.

may be necessary to inspect, assess, rehabilitate, replace, and repair large diameter sewers and appurtenances on an emergency or urgent basis

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$724	\$123	\$123	\$251	\$301	\$50	\$0	\$0	\$0	\$351	\$0
Professional Services	\$20	\$221	\$221	(\$200)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-168)	\$4,510	\$2,521	\$2,521	\$850	\$997	\$166	\$0	\$0	\$0	\$1,163	\$0
Construction (CON- 149)	\$35,339	\$33,502	\$33,502	\$3,253	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Conveyance System Engineering Services-1802575

Project Status: Active - Procurement - Construction Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Gescherter Barten Biller Biller
Project Engineer/Manager: Mini Panicker Director: Biren Saparia	Project Score 78.3	
Problem Statement: As part of the baseline condition assessment, the	Scope of Work/Project Alternatives: Evaluate the existing conditions of the Woodward	Other Important Info: Challenges: These are large sewers and may

As part of the baseline condition assessment, the trunk sewers and interceptors were inspected for structural integrity and maintenance issues in accordance with the National Association of Sewer Service Companies (NASSCO) standards. The purpose of this project is to provide Engineering Services to evaluate the inspection results and recommend the best rehabilitation methods and to provide construction assistance for the Woodward Sewer and Connors Creek Sewer Systems. Evaluate the existing conditions of the Woodward Sewer System and Connors Creek Sewer System and provide the design for both projects. In addition, provide for the construction of Conner Creek. Challenges: These are large sewers and may have flow control challenges for both inspection and rehabilitation.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$500	\$31	\$31	\$119	\$143	\$143	\$64	\$0	\$0	\$350	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1802575)	\$5,475	\$1,905	\$1,905	\$915	\$1,091	\$1,088	\$489	\$0	\$0	\$2,667	\$0
Construction (Build) # 1	\$49,576	\$0	\$0	\$12,539	\$15,146	\$15,105	\$6,787	\$0	\$0	\$37,037	\$0



Project Title: NWI Rehabilitation

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside construction Predecessor Project(s) 		GLAVA Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker Director: Biren Saparia		Project Score 60.3	

Problem Statement:

The North West Interceptor (NWI) was constructed between 1928 and 1950 and is unique among the GLWA interceptors in that the NWI diameter reduces in size at certain locations to restrict downstream conveyance to the Water Resource Recovery Facility (WRRF). Review of available CCTV and PACP information and man entry inspection have indicated a need for ongoing maintenance, typically consisting of spot repairs and debris removal.

Scope of Work/Project Alternatives:

Scope of work is the rehabilitation of NWI from Eight Mile to Tireman. The work includes mainly debris removal, deep concrete repairs, brick repairs, tuck pointing etc. to reduce infiltration and to increase the conveyance capacity.

Other Important Info:

Two flow control structures were constructed under CON-149 contract to facilitate condition assessment and rehabilitation for portions of the NWI south of McNichols

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$134	\$6	\$6	\$59	\$70	\$0	\$70
Design/Engineering (CS-168)	\$665	\$331	\$331	\$153	\$183	\$0	\$183
Construction	\$6,935	\$0	\$0	\$3,136	\$3,788	\$10	\$3,799



Project Title: Conveyance System Repairs (Sewers)

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Systems Control Center Class Lvl 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside complete Predecessor Project(s) 			GLANA Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker Director: Biren Saparia		Project Score 57.6		
Broblem Statement:	Scope of Work/Project	Altornativos	Othor Im	nortant Info:

Problem Statement:

Rehabilitation program of the existing sewers and interceptors is identified after the baseline condition assessment. This project is for the rehabilitation of Brush/Bates, Joy Road, & Seven Mile Sewers to extend their service lives and to maximize their transportation capacities.

Scope of Work/Project Alternatives:

Study, design, and construction assistance services associated with reviewing and supplementing information gathered from recent sewer inspections, identifying all required repairs, creating construction documents for repairs, and providing construction phase assistance during the implementation of the repairs for Brush/Bates, Joy Road. & Seven Mile Sewers.

Other Important Info:

This Engineering Services contract also encompasses the remaining CSO outfalls which is being funded by the Outfall Program, 260500

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$407	\$5	\$5	\$122	\$147	\$134	\$0	\$0	\$0	\$280	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering Phase #1 (2003443)	\$1,554	\$435	\$435	\$98	\$325	\$324	\$324	\$92	\$0	\$1,065	\$0
Design/Engineering Phase #2	\$1,554	\$0	\$0	\$599	\$0	\$0	\$161	\$276	\$277	\$714	\$242
Construction Phase #1	\$16,000	\$0	\$0	\$1,283	\$7,695	\$7,022	\$0	\$0	\$0	\$14,717	\$0
Construction Phase #2	\$15,000	\$0	\$0	\$0	\$0	\$0	\$2,520	\$4,338	\$4,350	\$11,208	\$3,792 312



Project Title: Rehabilitation of Woodward Sewer Systems

 Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Righ Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(s) 	of Facilities	Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker		Project Score	
Director: Biren Saparia		76.8	
Problem Statement: During the initial condition assessment, Woodwa Sewer was ranked higher in the rehabilitation liss since there were several grade 3, 4 and 5 defect root intrusions, as well as instances of missing bricks and infiltration throughout the pipe segments. This rehabilitation is essential to optimize the transportation capacity of the Woodward Sewer and the GLWA collection syst and to increase its life expectancy	t includes rehabilitation o ts, Woodward Avenue in D Road at the north end to regulator south of Jeffer includes two segments on Woodward Avenue v em 1.Woodward Extension Highland Park city bord	e performed on this project f existing sewers along etroit, MI from McNichols o the location of the B-21 rson Avenue. In addition it that connect to the sewer	Other Important Info: NA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	5 Year Total
GLWA Salaries	\$362	\$20	\$20	\$222	\$121	\$0	\$0	\$121
Professional Services	\$21	\$147	\$147	(\$126)	\$0	\$0	\$0	\$0
Design/Engineering	\$1,225	\$1,594	\$1,594	(\$312)	\$0	\$0	\$0	\$0
Construction	\$18,695	\$2,758	\$2,758	\$11,157	\$5,663	\$0	\$0	\$5,663



Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: Systems Control Center Class LvI 3: General Purpose Lookup Location: Sewers and Interceptors Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker	Project Sco 61.3	ore
Director: Biren Saparia Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:

GLWA collection system has a network of aging and deteriorated sewers. Due to the age and deterioration, immediate sewer repair/rehabilitation services are often necessary to avoid basement flooding and maintain the flows within the wastewater conveyance system. This contract is to continue the as needed sewer repairs, inspection, and rehabilitations to help GLWA optimize the collection system capacity.

Scope of Work/Project Alternatives:

Scope of work to be performed under this contract includes as needed repair, inspection, heavy cleaning, and rehabilitation to bring back the sewer system to its normal capacity and function and to avoid collapse.

Other Important Info:

This is a replacement contract for the current CON-149.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$225	\$4	\$4	\$55	\$66	\$66	\$34	\$0	\$166
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$12,400	\$0	\$0	\$5,616	\$6,784	\$0	\$0	\$0	\$6,784
Construction (Year 1 Extension)	\$6,200	\$0	\$0	\$0	\$0	\$6,200	\$0	\$0	\$6,200
Construction (Year 2 Extension)	\$6,200	\$0	\$0	\$0	\$0	\$0	\$6,200	\$0	\$6,200



Project Title: Rehabilitation of GLWA Sewers; Ashland Relief, Linwood, Lonyo, Second Avenue, and Shiawassee

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: General Purpose Lookup Location: Multiple Locations ✓ Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Mini Panicker Director: Todd King	Project Scor 0	'e
Problem Statement: Rehabilitation of 5 of the collections system sewers;Ashland Relief, Linwood,Lonyo, Second Avenue, and Shiawassee	Scope of Work/Project Alternatives: NA	Other Important Info: NA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$335	\$1	\$1	\$32	\$38	\$38	\$38	\$38	\$38	\$189	\$113
Design/Engineering	\$6,900	\$0	\$0	\$1,185	\$1,432	\$1,428	\$1,428	\$1,428	\$0	\$5,715	\$0
Construction (Phase #1)	\$15,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$15,000
Construction (Phase #2)	\$15,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$15,000
Construction (Phase #3)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Future Planned - Within 5 Innovation Year Plan GLWA WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: Programs Redundancy ~ Class Lvl 3: Programs **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: CSO Outfalls Linear Assets Outside of Facilities **Project New to CIP: Predecessor Project(s)** Project Engineer/Manager: Mini Panicker **Project Score** 0 **Director:** Biren Saparia

Problem Statement:

Rehabilitation of the CSO outfalls is essential to properly discharge the uncontrolled combined sewer overflows to the receiving waters and to prevent sewer backups in the Conveyance System. Recent inspections of the outfalls revealed structural deficiencies such as fractures, missing mortar from bricks. There are also sediment and debris deposits in many of them.

Scope of Work/Project Alternatives:

The preliminary Scope of Work of the project is construction. The work to review the existing records, evaluate the existing conditions, and provide the necessary design to rehabilitate the outfalls is being done under Contract CS-168. Another Engineering Services contract will be initiated after the CS-168 contract.

Other Important Info:

Projects 222006 AND 233001 have been incorporated into this project.

Project History: The construction of these outfalls dates back to the early 1900s.

Challenges: Some outfalls are below the river elevation and rehabilitation may be challenging.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$136	\$0	\$0	\$0	\$0	\$0	\$14	\$14	\$14	\$41	\$68
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
TBD Future Allocation	\$15,000	\$0	\$0	\$0	\$0	\$0	\$1,499	\$1,499	\$1,503	\$4,502	\$7,500



Project Status: Closed Innovation GLWA Class Lvl 1: Wastewater WW Master Plan Class Lvl 2: Programs Water Master Plan Right Sizing Class Lvl 3: Programs Redundancy Lookup Location: CSO Outfalls **NE WTP Repurposing** Great Lakes Water Authority Linear Assets Outside of Facilities **Project New to CIP: Predecessor Project(s)** Project Engineer/Manager: Mini Panicker **Project Score** 0 **Director:** Biren Saparia

Problem Statement:

Rehabilitation of the CSO outfalls is essential to properly discharge the uncontrollable combined sewer overflows to the receiving waters and to prevent sewer back up into the Conveyance System. Recent inspections of the outfalls revealed structural deficiencies like fractures, missing mortar from bricks etc. There are sediment and debris deposits in many of them.

Scope of Work/Project Alternatives:

Preliminary Scope of Work of the project is construction. Contract CS-168 will review the existing records, evaluate the existing conditions, and provide the necessary design to rehabilitate the outfalls. Another Engineering Services contract will be initiated after the CS-168 contract.

Other Important Info:

PROJECTS 222006 AND 233001 HAVE BEEN INCORPORATED INTO THIS PROJECT.

Project History: The construction of these outfalls are dated back to the early 1900s under various contracts.

Challenges: Some outfalls are below the river elevation; rehabilitation may be challenging.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$13	\$13	\$13	\$0
Professional Services	\$0	\$0	\$0	\$C
Design/Engineering (CS-168)	\$201	\$201	\$201	\$0
Construction (Build) # 1 (CS-168, 1900076)	\$4,915	\$4,710	\$4,710	\$205



Project Status: Project Execution -Innovation Construction GLWA WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: Programs Redundancy Class Lvl 3: Programs **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: CSO Outfalls Linear Assets Outside of Facilities **Project New to CIP: Predecessor Project(s)** Project Engineer/Manager: Mini Panicker **Project Score** 75.3 **Director:** Biren Saparia **Problem Statement:** Scope of Work/Project Alternatives: **Other Important Info:** The B-39 outfall was constructed in 1928. The scope of work to be performed for the Project not scored by risk committee because it Findings from the recent investigations indicated rehabilitation of this outfall mainly included was critical or for emergency repairs isolation and dewatering of the outfall, repairing to that the outfall barrel was structurally compromised, with significant cracking, springline seal the cracks/leaks, and heavy cleaning

Current Expenses (All figures are in \$1,000's)

crushing, and general deterioration of the concrete

liner. Rehabilitation of this CSO outfall was essential to properly discharge the uncontrolled combined sewer overflows to the receiving waters and to prevent sewer back ups in the Conveyance

System.

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$207	\$4	\$4	\$102	\$101	\$101
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$388	\$226	\$226	\$169	\$0	\$0
Construction	\$9,743	\$1,146	\$1,146	\$4,822	\$4,270	\$4,270



Project Title: Conveyance System Repairs (Outfalls)

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: CSO Outfalls	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority			
Project Engineer/Manager: Mini Panicker	Project Score				
Director: Biren Saparia	73.8				
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:			
Rehabilitation program of the CSO outfalls, sewers, and interceptors was identified after the baseline condition assessment. This project is to rehabilitate the remaining CSO outfalls that are not included under Phase 1, 2, 3, and 4 rehabilitations	Evaluate the existing conditions of the remaining CSO outfalls, provide the necessary rehabilitation to optimize the design capacities.	This Engineering Services contract also includes Joy Rd, Seven Mile, and Bates sewers which is being funded by the Sewer and Interceptor Rehabilitation Program, 260200 and this project is combined with 260206			

Current Expenses (All figures are in \$1,000's)

to increase their useful life.

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$421	\$6	\$6	\$88	\$106	\$106	\$106	\$11	\$0	\$328	\$0
Design/Engineering	\$2,120	\$1,166	\$1,166	\$273	\$229	\$275	\$275	\$172	\$0	\$950	\$0
Design/Engineering Phase #2	\$2,120	\$0	\$0	\$817	\$0	\$219	\$377	\$377	\$330	\$1,303	\$0
Construction Phase #1	\$16,000	\$0	\$0	\$0	\$4,542	\$5,453	\$5,453	\$553	\$0	\$16,000	\$0
Construction Phase #2	\$15,000	\$0	\$0	\$0	\$0	\$3,245	\$5,587	\$5,587	\$582	\$15,000	\$0



Project Title: CSO FACILITIES IMPROVEMENT PROGRAM

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Conner Creek, Seven Mile, Puritan-Fenkell, Hubble-Southfield, Belle Isle, Oakwood CSO Basins, Baby Creek, Leib and St. Aubin Screening and Disinfection Facilities Project New to CIP:	InnovationWW Master PlanWater Master Plan Right SizingRedundancyNE WTP RepurposingLinear Assets Outside of FacilitiesPredecessor Project(s)	Conner Creek CSO Facility			
Project Engineer/Manager: Chris Nastally Director: Chris Nastally	Project Score 0				
Problem Statement: This program is being established to facilitate the study, design, construction administration, and construction of improvements necessary to maintain the facilities which contribute to the CSO Control Program and compliance with it.	Scope of Work/Project Alternatives: This program is established to fund projects that arise in the near term of each fiscal year that were not budgeted for previously, and also serves as accounting of future costs in the CSO CIP that may be a part of long term CSO control, or other significant planning projects. Scopes of work will vary from roof replacement, to equipment replacement, to various other facility improvements.	Other Important Info: The Total Lifetime cost of this program includes costs projected all the way out to 2044			

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$2,691	\$0	\$0	\$83	\$100	\$100	\$100	\$100	\$100	\$502	\$501
Design/Engineering	\$91,500	\$0	\$0	\$415	\$501	\$500	\$500	\$500	\$501	\$2,502	\$0
Design-Build	\$16,000	\$0	\$0	\$417	\$1,510	\$1,004	\$1,004	\$1,004	\$1,007	\$5,529	\$5,027
Construction	\$920,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Conner Creek CSO RTB Automation Improvements

Project Status: Pending Closeout Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Conner Creek	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Effluent Relief Gate Repair
Project Engineer/Manager: Ihsan Wahab Director: Chris Nastally	Project Sco 0	re

Problem Statement:

Effluent gates were leaking allowing river water in to the basin. Based on the CS-116 study, seals and seats of some of Effluent Relief gates were found to be damaged. A data network style connection was used (versus hardwired) between the gates and the SCADA system. This network has been unreliable and difficult to maintain. Electrical and control cables were compromised due to their installation on the top of the concrete slab of Retention Treatment Basin (RTB) roof.

Scope of Work/Project Alternatives:

The scope work includes replacement of existing seals and seats of effluent relief gates (ERGs) and effluent launder gates (ELGs), replacement and alignment of stems for ELGs, replacement of ERG stems (based on assessment), existing pull boxes and cover replacement on top of RTB roof, existing fiber optic cable and conduit replacement, hardwiring ELGs and ERGs actuators for reliable operation, secondary power feed for effluent gates, replacement of RIO5 and RIO6, logic modification to allow SC...

Other Important Info:

CS-172 has been closed out as of 09/23/19. Influent flowmeters replacement work is added as part of CCD-A and CO No. 2 of this contract.



Project Title: Conner Creek CSO RTB Automation Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$377	\$346	\$346	\$36	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1 (CS- 172, CS-116, CS-166,	\$76	\$76	\$76	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
CON-234) Design/Engineering (CS-116)	\$542	\$341	\$341	\$201	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-166)	\$24	\$19	\$19	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (MISC)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CON-234)	\$6,900	\$6,900	\$6,900	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Miscellaneous	\$66	\$66	\$66	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Baby Creek HVAC Improvements

Project Status: Closed Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Dearborn Project New to CIP:	 Innovation WW Master Plan Water Master Plan Rig Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(set) 	e of Facilities	Existing Dampers
Project Engineer/Manager: Kashmira Patel Director: Chris Nastally		Project Score 0	
Problem Statement: This project expands on the MAU replacement project (260610) by addressing other HVAC iss through out the facility, such as the control build and the screening building.	sues ventilation system in the ding replacement of dampe screening building, rep dampers in the chemic temperature sensors the	udes modifications to the ne Electrical room, irs and actuators in the placement of actuators for cal room, installation of	Other Important Info: N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$50	\$50	\$50	\$0
Professional Services	\$0	\$0	\$0	\$0
Design/Engineering (1803675)	\$2	\$2	\$2	\$0
Construction (Build) # 1 (1901609)	\$494	\$494	\$494	\$0



Project Title: Structural Inspection & Structural Improvements

Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: Programs Class LvI 3: Programs Lookup Location: Wayne Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Existing Structural Condition
Project Engineer/Manager: Kashmira Patel Director: Chris Nastally	Project Score 53.4	
Problem Statement: A partial structural condition assessment has been performed and structural improvement (types) identified and prioritized. This project will provide Design-Build service to completely inspect all of the CSO Facilities (above and below ground) and prioritize improvements to be carried out over a 3- year period.	includes a complete field assessment and structural condition report, classification of recommended repairs into levels of urgency, estimating quantities and the costs of repairs,	f o

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$141	\$38	\$38	\$38	\$44	\$23	\$0	\$0	\$0	\$66	\$0
Professional Services	\$10	\$10	\$10	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CS-166)	\$1,325	\$874	\$874	\$184	\$200	\$104	\$0	\$0	\$0	\$304	\$0
Design-Build # 1 (1902224)	\$12,492	\$7,372	\$7,372	\$2,866	\$2,189	\$1,118	\$0	\$0	\$0	\$3,307	^{\$0}



Project Status: Closed Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Wayne Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Poor Drainage at Leib
Project Engineer/Manager: Partho Ghosh	Project Score	
Director: Chris Nastally	0	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:

There is an existing site drainage issue at both of these facilities creating standing water on top of the basin. There is no lighting at the outfall at (puritan Fenkell (PF), which is needed for operation at nighttime during a rain event event. The existing sidewalks at both of these facilities are damaged and need replacement. The perimeter fencing at PF is damaged at various locations and there is no fence at the outfall area to secure the facility from intruders. At Leib, the existing o...

The scope of work includes creating positive drainage, installation of trench drains and replacement of existing side walks at both facilities. Additionally, at PF, the scope includes installation of a pathway and lighting at the outfall and includes a perimeter fence replacement. At Leib, the scope also includes the replacement of ornamental fence and brick pavers.

IN/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$41	\$41	\$41	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1803809)	\$8	\$48	\$48	(\$40)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (1902040)	\$369	\$494	\$494	(\$124)	\$0	\$0	\$0	\$0	\$0	\$0	\$0 325



Project Title: St. Aubin Chemical Disinfection Improvements

Project Status: Reclassified Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Existing Screens
Project Engineer/Manager: Kashmira Patel Director: Chris Nastally	Project Sco 0	ore

Problem Statement:

The St. Aubin CSO facility is over 20 years old. A study was conducted on the disinfection system and the screens were assessed by the manufacturer through a separate contract, and resulted in recommendations of needed upgrade of these systems to restore operational control, flexibility, and reliability. The current pumping system for NaOCI is oversized (dose of 38 mg/L) when only 10 mg/l is required based on a sampling study. The over-sized system makes it difficult to dial the pumps down on...

Scope of Work/Project Alternatives:

The scope of work includes replacement of existing chemical feed pumps with better pump technology, modification of the chemical feed piping system and control, installation of overhead trolley for maintenance, relining the chemical storage tanks to extend the life of existing tanks, evaluating different screening technologies if applicable or replacing the control system and hydraulic power-pack of the existing screens, installing new screen flushing sprayer system, replacing existing HVAC wit...

Other Important Info:

Previous study was performed by Hazen and Sawyer. AECOM/DLZ provided a study BOD and 20% Design documents. Project not scored by review committee because it will be absorbed into another CIP project



Project Title: St. Aubin Chemical Disinfection Improvements

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$375	\$4	\$4	\$57	\$69	\$69	\$69	\$69	\$37	\$313
Professional Services	\$363	\$363	\$363	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (1803089)	\$50	\$50	\$50	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build (NO DESIGN-BUILD)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Engineer/Manager: Chris Nastally

Director: Chris Nastally

Problem Statement:

There is heavy corrosion and the gas detection system in the sanitary pump room is constantly turning off causing operators to leave the overhead door open to keep the space ventilated. The HVAC system pulls gases from the sewer as currently operated. The wet-well supply fans have failed functionally and this is also contributing to heavy corrosion in the sanitary pump room.

Scope of Work/Project Alternatives:

The Odor Control unit intake is being reconfigured, various supply and exhaust fans are being replaced, access for the odor control units will be made for all three units to facilitate proper maintenance. The crane and building structural steel will be assessed and re-coated to ensure proper life.

Project Score

20

Other Important Info:

The project is under construction. Project not scored by risk committee because it is far advanced

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$270	\$62	\$62	\$217
Professional Services	\$113	\$113	\$113	\$0
Design/Engineering	\$458	\$391	\$391	\$102
Design-Build	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$5,992	\$4,329	\$4,329	\$1,663



devices at the above facilities.

Project Title: Control System Upgrade - St Aubin, Lieb & Mile

 Project Status: Active - Procurement - Board Approved - Design Class Lvl 1: Wastewater Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: Seven Mile, Leib and St. Aubin Screening and Disinfection Facilities Project New to CIP: 	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		Eieb CSO, PLC Panel
Project Engineer/Manager: Chris Wilson		Project Score	
Director: Chris Nastally		95.1	
Problem Statement:	Scope of Work/Project Alternatives:		Other Important Info:
This project was initiated to facilitate the design build improvements necessary to maintain the facilities which contribute to the CSO Control Program and ensure compliance.	The project will replace the Obsolete/End of Life Allen Bradley PLC5 control systems at 3 CSO Facilities (Leib, St. Aubin, 7-Mile) and upgrade critical Instrumentation. It includes new Controllers,		The intent of this project is to perform field investigation, replace, design, demolish existing, furnish, install and start-up a complete Control system, networks and replacement of all field

Allen Bradley PLC5 control systems at 3 CSO Facilities (Leib, St. Aubin, 7-Mile) and upgrade critical Instrumentation. It includes new Controllers, HMI, network components and controls system integration. It also includes implementation of highperformance graphics and advance alarm management and advanced process control.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$135	\$0	\$0	\$43	\$52	\$39	\$92
Professional Services	\$63	\$63	\$63	\$0	\$0	\$0	\$0
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$7,375	\$0	\$0	\$2,906	\$3,510	\$959	\$4,469



CIP Number: 260620

Project Status: Pending Closeout Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Baby Creek Lookup Location: Baby Creek Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	The previous installment on roof area 2 also failed to follow the required "step-dowr" installation method. As seen in the picture above, the shingle searns fail >4" from each other. This is a very common mistake found on Improper shingle installation.
Project Engineer/Manager: Vinod Sharma Director: Chris Nastally	Project Sco 78.8	pre
Problem Statement: The Baby Creek roof leaks on electrical equipm when it rains. The laps in the shingles are sometimes as little as 2". As identified as part of recent roof inspection the leaking roof has caus the substrate to rot and require replacement. Approximately one third of the roof was previous replaced in 2017. This new portion of roof is sufficient. The remaining two thirds of the roof it exhibiting failure.	matching asphalt shingles. of a ed sly	Other Important Info: Creek with N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$30	\$30	\$30	\$8
Professional Services	\$0	\$0	\$0	\$0
Design/Engineering (CS-299)	\$23	\$34	\$34	(\$12)
Construction	\$999	\$829	\$829	\$445



Project Status: Closed

Class Lvl 1: Wastewater

Class Lvl 2: CSO Facilities

Class Lvl 3: Conner Creek

Project New to CIP:

Lookup Location: Conner Creek

Photo of the berm leaking into Clairpointe

Project Engineer/Manager: Chris Nastally

Director: Chris Nastally

Problem Statement:

The Conner Creek berm was constructed in the early 2000's and was to serve as a landscaping element between Clairpointe Street and the Conner Creek Canal. When the facility was constructed the Great Lakes were at historic low levels and therefore it was never envisioned that this berm would be required to hold back the Detroit River (acting as a dike). Due to historically high Great Lakes levels, the dike is now exhibiting signs of seepage/failure and needs to be repaired before it experience...

Scope of Work/Project Alternatives:

Innovation

WW Master Plan

NE WTP Repurposing

Predecessor Project(s)

Redundancy

Water Master Plan Right Sizing

Linear Assets Outside of Facilities

The work consists of removal of existing trees/vegetation from the berm, installing a sheet pile cutoff wall with a concrete cap, fencing, landscape restoration, and minor security improvements.

Project Score

95.2

Other Important Info:

Project is completed and being closed out.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$20	\$10	\$10	\$10
Design/Engineering (1900318)	\$664	\$638	\$638	\$35
Construction	\$1,590	\$1,590	\$1,590	\$11



Project Title: CSO Emergency Generator Improvements

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 			GLANA Great Lakes Water Authority
Project Engineer/Manager: Ariadna Risher		Project Scor	e	
Director: Chris Nastally		77.5		

Problem Statement:

The reliability of the CSO standby generators and automatic transfer switches is declining. During utility power outages when the standby generators are necessary, either the generators may not start automatically, or the automatic transfer switches may not transfer. Neither the generator control panels, nor automatic transfer switches report any status or alarm signals to the operators through the SCADA Ovation Control system. In many cases, CSO Facilities have automatic transfer switch (ATS)...

Scope of Work/Project Alternatives:

Under this project, the CSO facilities with standby generator systems will be upgraded to have a standardized, dedicated automatic transfer control system. This will include upgrades to the automatic transfer switches, upgrades to some generator control panels, and the addition of several alarm and status signals from both the generator control panels and the ATS controllers, which will be monitored by the Ovation Control system. General Project Objectives are: 1. Replace obsolete Programab... Other Important Info:

None.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$11	\$7	\$7	\$4	\$0	\$0
Professional Services (CS-272 - 72031A.01)	\$130	\$40	\$40	\$101	\$0	\$0
Design/Engineering (CS-299)	\$80	\$60	\$60	\$20	\$0	\$0
Construction	\$1,029	\$91	\$91	\$1,029	\$0	\$0



Project Title: CSO Baby Creek Screen Rehabilitation

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Baby Creek Lookup Location: Dearborn Project New to CIP:	Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s)	Great Lakes Water Authority
Project Engineer/Manager: Partho Ghosh	Project Score 93.2	
Director: Chris Nastally Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
Based on the condition assessment conducted as a part of contract CS-299, the screens require rehabilitation to ensure long term viability.	The rehabilitation of Baby Creek Screens includes replacing/ repairing necessary parts to ensure system reliability and maintainability.	N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$21	\$8	\$8	\$12	\$5	\$0	\$5
Professional Services	\$26	\$8	\$8	\$21	\$0	\$0	\$0
Design/Engineering	\$20	\$14	\$14	\$4	\$2	\$0	\$2
Construction	\$2,326	\$0	\$0	\$1,412	\$914	\$0	\$914



Project Title: Sewer System Infrastructure Improvements and Pumping Stations

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: Interceptor Lookup Location: CSO Outfalls	 Innovation WW Master Plan Water Master Plan Right Si Redundancy NE WTP Repurposing Linear Assets Outside of F Predecessor Project(s) 		Infrastructure
Project Engineer/Manager: Mini Panicker		Project Sco	re
Director: Todd King		0	

Problem Statement:

VR-Gates, ISDs, and backwater gates are operational elements in the collection system that minimize untreated overflows and maximize flow to the WRRF and CSO control facilities. They have reached their life expectancy and need rehabilitation. Need to install Backwater gates at the DRI Outfalls that currently do not have backwater gates to prevent river inflow into the collection system. This program is for the rehabilitation of the infrastructural elements and for the as needed updating of the...

Scope of Work/Project Alternatives:

Evaluate the existing conditions of the VR-Gates, ISDs, Backwater Gates and Access Hatches Provide the necessary design, construction, and Construction Assistance for their installation, replacement or rehabilitation. Update of the collection system pumping station assets on an as needed basis.

Other Important Info:

Google map of VR-3 and VR-9 are included. VR-4, 5, 6, 10, 11 &13 are also part of the project.

Project History: GLWA interceptors and sewers were constructed in the early 1900s. The hatches and access covers secure operations and maintenance access points throughout the system for items such as the backwater gates, ISDs, and VRs. The backwater gates, ISDs, and VRs are all critical elements that control and divert flows throughout the system. Most of them have reached their life expectanc...



Project Title: Sewer System Infrastructure Improvements and Pumping Stations

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
Capital Delivery	\$526	\$0	\$0	\$40	\$49	\$49	\$49	\$49	\$49	\$243	\$243
Salary (was 222004)											
TBD/Unallocated	\$499	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$499
Construction (3 Projects)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
TBD - Future Allocation #3	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
TBD - Future Allocation #4	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Conveyance System Infrastructure Improvements

Project Status: Active - Procurement - Construction Class Lvl 1: Wastewater Class Lvl 2: Field Services Class Lvl 3: Interceptor Lookup Location: City of Detroit, Southfield, and others	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Infrastructure
Project Engineer/Manager: Mini Panicker	Project Score	
Director: Todd King	60.1	
Problem Statement: VR-Gates, ISDs, and backwater gates are operational elements in the collection system that	Scope of Work/Project Alternatives: Assess the structure and functionality of the VR- Gates, ISDs, Regulators, Backwater Gates,	Other Important Info: Rehabilitation will be in 2 different phases. Phase 1 will be the rehabilitation of the

operational elements in the collection system that minimize untreated overflows and maximizing flow to the WRRF and CSO control facilities. They have reached their life expectancy and need rehabilitation. Assess the structure and functionality of the VR-Gates, ISDs, Regulators, Backwater Gates, Access Hatches and provide Design, Construction, and Construction Assistance for their replacement or rehabilitation. Rehabilitation will be in 2 different phases. Phase 1 will be the rehabilitation of the mechanical, structural and electrical equipment at 59 combined sewage outfall (CSO). Most of the work includes replacement of timber backwater gates, modifications to the regulator opening and replacement of regulator gates, and replacement of all instrumentation equipment. Phase 2 will be the rehabilitation of 14 ISDs and 2 DR facilities. These facilities are intended to store and release flow during time...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
Capital Delivery	\$490	\$31	\$31	\$92	\$109	\$109	\$109	\$42	\$369
Salary (was 222004)									
Design/Engineering	\$4,576	\$2,214	\$2,214	\$2	\$573	\$750	\$750	\$290	\$2,362
(1803709)									
Construction	\$16,000	\$0	\$0	\$11,143	\$16,315	\$12,970	\$8,970	\$3,465	\$41,720



Project Status: Active - Pre-Procurement Innovation - Construction GLWA WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: Field Services Redundancy Class Lvl 3: General Purpose **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: N/A Linear Assets Outside of Facilities **Project New to CIP: Predecessor Project(s)** Project Engineer/Manager: Mini Panicker **Project Score** 59.6 **Director:** Biren Saparia **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: Evaluation and upgrade of the Pumping Station Evaluate/upgrade/replace the Sewer Pump Station N/A elements needed to improve the conveyance of elements to maintain the collection system wastewater to the WRRF. transport capacity on an as needed basis.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$65	\$0	\$0	\$0	\$0	\$0	\$0	\$6	\$7	\$13	\$32
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$10,000	\$0	\$0	\$0	\$0	\$0	\$0	\$999	\$1,002	\$2,001	\$4,999



Project Title: WRRF ROOF REPLACEMENT FOR MULTIPLE FACILITIES PROGRAM

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		Formula
Project Engineer/Manager: Chris Wilson		Project Score	9
Director: Chris Nastally		0	

Problem Statement:

Some of the roofs at GLWA WRRF facilities are near the end of their useful life. The roofs help to protect the expensive equipment by preventing rainwater entering into the facilities.

Scope of Work/Project Alternatives:

Inspect the roofing system conditions and assess drainage conditions on all the GLWA wastewater facility buildings. Document the roofing system inspections with high-quality photographs, scaled drawings, sketches, and inspection notes to describe the conditions and deficiencies of the roofing systems. Recommend the extent of roofing repairs and replacements required. Document the roof for each building inspected on the project. Classify the roofs into three main categories, 1) Roofs that requir...

Other Important Info:

Challenges: Roof material testing for asbestos before demolition and flashing will be challenging to manage as low levels of asbestos are very common in the GLWA's old roof type systems.

Project History: Majority of GLWA WRRF facilities have Built-Up-Roof (BUR) membrane systems commonly referred to as "tar and gravel" roofs. The old Administration building, and the Newer Administration building have tar and gravel type roof systems. The CSO RTB's and SDF's have metal and shingle type roofing...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$133	\$0	\$0	\$0	\$0	\$0	\$0	\$19	\$19	\$38	\$95
Design/Engineering	\$2,700	\$0	\$0	\$0	\$0	\$0	\$0	\$500	\$200	\$700	\$1,100
Construction	\$12,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,003	\$2,003	\$5,997



Project Title: 2022 WRRF Roof Improvements Project

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF ☑ Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Jared Buzo Director: Chris Nastally	Project Score 77.9	
Problem Statement: This project stems from the 260800 WRRF Roof Replacement Program. This project will perform assessment on nearly all of the rooves at the WRRF, and prioritize the worst condition rooves fo design of improvements to restore proper function to the rooves.		Other Important Info: N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$44	\$0	\$0	\$14	\$17	\$13	\$30
Professional Services	\$24	\$14	\$14	\$12	\$0	\$0	\$0
Design/Engineering	\$500	\$63	\$63	\$148	\$178	\$141	\$319
Construction	\$4,278	\$0	\$0	\$0	\$2,143	\$2,135	\$4,278



Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Administration Building
Project Engineer/Manager: Chris Wilson	Project Score 0	
Director: Chris Nastally	U	

Problem Statement:

The existing WRRF is a product of numerous construction projects over nearly 90 years and consists of numerous process and other buildings with varying levels of use and practicality. It is critical to convey an image that reflects the pride and importance of the work that is done every day at this facility. This project will create a visitor center focusing on public education to impress the next generation of wastewater engineers, scientists and operators and enhance the facility creating a m...

Scope of Work/Project Alternatives:

The work consists of extending the evaluation performed as a part of Master Planning to design and construct site modifications including a new visitor center, demolition or repurposing of existing structures that are no longer used, consolidation or reconfiguration of administration, operations and maintenance staff and spaces, vehicle and equipment storage spaces, shops, etc. The project also includes site modifications to include improved site circulation, parking and fencing, green infrastr... Other Important Info:

N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$771	\$0	\$0	\$43	\$52	\$52	\$52	\$52	\$52	\$260	\$260
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$85,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,135	\$2,135	\$21,424



Project Title: Rehabilitation of HAZMAT Facility at WRRF

Project Status: Active - Procurement - Construction Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Rig Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(s) 	of Facilities		GLANA Great Lakes Water Authority
Project Engineer/Manager: Jared Buzo		Project Score		
Director: Chris Nastally		52.1		
Problem Statement:	Scope of Work/Projec	t Alternatives:	Other Im	portant Info:
The HAZMAT Security Specialists at the Water Resource Recovery Facility (WRRF) provide ra response for GLWA operations, including site security and emergency response relating to lea or spills of hazardous substances. There are approximately 3-4 specialists occupying the existing HAZMAT building daily, with a maximu 5-6 specialists at certain times. The HAZMAT facility, which is located on the opposite side of Jefferson Road from the WRRF, is a single stor steel framed and concrete b	 pid HAZMAT building to rig •accommodate the GLV •accommodate the park type vehicle, two (2) res response trailer. •demolish and construct accommodate one officient 	ht size the facility to: VA HAZMAT team. king of one (1) pick-up truck sponse vehicles and a	N/A	

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$19	\$0	\$0	\$7	\$8	\$4	\$12
Professional Services	\$22	\$20	\$20	\$5	\$0	\$0	\$0
Design/Engineering (1900318)	\$317	\$219	\$219	\$9	\$66	\$32	\$98
Construction	\$2,000	\$0	\$0	\$0	\$1,338	\$662	\$2,000



Project Status: Project Execution - Construction Class LvI 1: Wastewater Class LvI 2: WRRF Class LvI 3: General Purpose Lookup Location: WRRF Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		New Administration Building
Project Engineer/Manager: Nicolas Nicolas		Project Score	

Director: Chris Nastally

Problem Statement:

The Wastewater Master Plan 'non-process space programming task' for the WRRF provided an overview of space needs, both current and future, to provide GLWA with the knowledge of space needs and a "roadmap" for building improvements utilizing holistic planning principles that yield several benefits including: •Increased efficiencies and space utilizations in the

Admin Building complex, consolidating operations work flows and optimizing the use of existing space. Scope of Work/Project Alternatives:

GLWA plans to renovate a significant portion of the existing fourth floor of the New Administration Building, in order to house Engineering Design & CSO, Construction Engineering, and Local Asset Management groups. The area of renovation is approximately 15,980 gross square feet and will be a combination of enclosed perimeter offices and conference rooms, coupled with furniture cubicles, collaboration space, and a break area.

59.5

Other Important Info:

N/A

Current Expenses (All figures are in \$1,000's)

Standardization of office and...

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	5 Year Total
GLWA Salaries	\$30	\$29	\$29	\$20	\$0	\$0
Design/Engineering	\$95	\$56	\$56	\$26	\$12	\$12
Construction	\$3,175	\$0	\$0	\$2,157	\$1,018	\$1,018



Project Status: Project Execution -Innovation Desian WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: WRRF Redundancy Class Lvl 3: General Purpose **NE WTP Repurposing** Lookup Location: WRRF Linear Assets Outside of Facilities **Project New to CIP: Predecessor Project(s)** WRRF Front Entrance Project Engineer/Manager: Charles Reinhart **Project Score** 52.4 **Director:** Chris Nastally **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info: The Great Lakes Water Authority's (GLWA) Water The project will re-design the Front Entrance at N/A WRRF to accommodate the traffic flow at the

Resource Recovery Facility (WRRF) is the largest single wastewater treatment facility in the United States with nearly five hundred individuals that report to the facility on a regular basis including team members, visitors, and contractors. The main entry point to the facility is the entrance from Jefferson closest to the Rouge River bridge which handles the majority of the traffic entering the plant. Team members and Contractors with badge acces... The project will re-design the Front Entrance at WRRF to accommodate the traffic flow at the entrance, provide visitor parking prior to the automated barrier gate arm, improvement to the turnstiles and the Guard House. This may require relocation of existing infrastructure to provide the best workflow at the entrance. The scope of work includes the following: •Re-design the parking and traffic flow at the front entrance. •Minimize the pedestrian-vehicle conflicts at the north entrance to ...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$36	\$1	\$1	\$13	\$15	\$6	\$22
Design/Engineering	\$634	\$226	\$226	\$168	\$236	\$95	\$331
Construction	\$3,330	\$0	\$0	\$224	\$2,216	\$890	\$3,106



Project Status: Active - Procurement -Innovation Design GLWA ~ WW Master Plan Class Lvl 1: Wastewater Water Master Plan Right Sizing Class Lvl 2: WRRF Redundancy Class Lvl 3: General Purpose **NE WTP Repurposing** Great Lakes Water Authority Lookup Location: WRRF Linear Assets Outside of Facilities **Project New to CIP:** ~ **Predecessor Project(s)** Project Engineer/Manager: Alfredo Lava **Project Score** 40.5 **Director:** Chris Nastally **Problem Statement:** Scope of Work/Project Alternatives: Other Important Info:

GLWA is in the process of renovating the 4th floor of the New Administration Building. This renovation will consolidate document management, the CIP/Asset Management Teams, and Engineering. As a result of this renovation, and the previous renovation to the 2nd Floor, the 3rd floor is now ready for the next phase of renovation in accordance with the Wastewater Masterplan. The plan is to renovate the 3rd floor to permit relocation of administration staff, OD, safety, and facilities teams to the 3rd floor to make room on the 1st floor (the last floor to be renovated). This plan will also make the 3rd floor more secure and in line with renovations performed on the 2nd floor and being performed on the 4th floor. Project is currently in procurement.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	5 Year Total
GLWA Salaries	\$31	\$4	\$4	\$6	\$7	\$6	\$6	\$2	\$22
Design/Engineering	\$215	\$0	\$0	\$168	\$7	\$31	\$10	\$0	\$47
Construction	\$3,175	\$0	\$0	\$0	\$0	\$372	\$2,122	\$680	\$3,175



Project Title: WRRF Plumbing Shop Renovation - 260905

Project Status: Project Execution - Design Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: General Purpose Lookup Location: N/A V Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority			
Project Engineer/Manager: Chris Nastally	Project Score				
Director: Chris Nastally	0				
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:			
The plumbing shop building is approximately 35 years old. It requires renovations to ensure prope function of the building for the next 20 years.	Do noting is not an option. Rehab is recommended and while performing these renovations, we will ensure the building's function will be sufficient to suit the needs of the WRRF for the next 20 years. By renovating the building and providing a proper space for logistics and materials team to properly store and access items frequently used at the plan for operations and maintenance to ensure continuity of operations. This will include demolition of interior floor space, establishment of storage r	Repurpose of a building that is not being properly utilized to a space that can best serve the WRRF.			

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-272)	\$18	\$0	\$0	\$18	\$0	\$0	\$0
Design/Engineering	\$170	\$0	\$0	\$59	\$83	\$28	\$111
Consruction	\$2,000	\$0	\$0	\$0	\$1,502	\$498	\$2,000



Project Title: WRRF Rehabilitation of the Secondary Clarifiers

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Secondary Treatment and Disinfection Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chris Wilson Director: Chris Nastally	Project Score O	
Problem Statement: The secondary clarifiers need to be inspected and rehabilitated for certain components such as the rake arms.	Scope of Work/Project Alternatives: This project will provide for inspection, study, design, and construction for refurbishing the secondary clarifiers. A key component will be the inspection of the concrete and the rake arms. Once the condition of these components is determined, alternatives will be evaluated, and the selected alternative will be designed and constructed. The scope will also include evaluating and designing isolation gates for the individual clarifiers. The B Houses have energy intensive HVAC units. These w	Other Important Info: Challenges: This will be a long-term project because only one or two clarifiers can be taken out of service at a time. Also, there may be different levels of rehabilitation for each clarifier depending upon the results of the inspection. Project History: There are 25 secondary clarifiers at the WRRF. They have been rehabilitated in the past for other components such as RAS pumps, troughs and weirs, and center drives. It is time to refurbish some of the other key components.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$337	\$0	\$0	\$0	\$0	\$0	\$0	\$187
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$39,000	\$0	\$0	\$0	\$0	\$0	\$0	\$7,796



Project Title: WRRF Rehabilitation of the Secondary Clarifiers Phase 1


Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: WRRF Class Lvl 3: Secondary Treatment and Disinfection Lookup Location: WRRF	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Chris Wilson Director: Chris Nastally	Project Scor 72	re
Problem Statement: The secondary clarifiers need to be inspected an rehabilitated for certain components such as the rake arms.	d Scope of Work/Project Alternatives: This project will provide for inspection, st design, and construction for refurbishing two secondary clarifiers. A key component the inspection of the concrete and the ral Once the condition of these components determined, alternatives will be evaluated selected alternative will be designed and constructed. The scope will also include evaluating and designing isolation gates individual clarifiers. The B Houses have intensive HVAC units	the first ent will be ke arms.because only one or two clarifiers can be taken out of service at a time. Also, there may be different levels of rehabilitation for each clarifier depending upon the results of the inspection.d, and theProject History: There are 25 secondary clarifiers at the WRRF. They have been rehabilitated in the past for other components such as RAS pumps,

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$170	\$0	\$0	\$0	\$13	\$19	\$19	\$19	\$19	\$90	\$80
Professional Services	\$597	\$0	\$0	\$597	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$3,174	\$0	\$0	\$0	\$149	\$223	\$223	\$389	\$424	\$1,408	\$1,766
Construction	\$15,000	\$0	\$0	\$0	\$0	\$0	\$0	\$2,067	\$2,505	\$4,571	\$10,429





Problem Statement:

This problem statement has been revised based on updates and negotiations currently taking place between MDOT, DWSD, and GLWA for the I-94 Modernization project planned by MDOT. The use of the drainage system and negotiations between the three entities has resulted in the pilot location for netting facilities to be shifted to Outfalls B-3, B-4, and B-5. These outfalls are on the GLWA list for outfalls that require treatment to satisfy long term CSO control. This project is anticipated to be ...

Scope of Work/Project Alternatives:

Inspect the 3 outfalls, perform a study to establish requirements for the netting facilities with respect to screening, disinfection, flow measurement, sampling, hydraulic gradeline, and bypass. Perform design services to carry the elements identified in the study forward for construction drawings and specifications. Perform services to establish locations for the required facilities, and assistance in land and easement acquisition to facilitate the improvements. Provide bidding, constructi...

Other Important Info:

GLWA staff conducted a field inspection in 2019 of CSO outfall netting facilities constructed in Cleveland in 2004. There are different types of CSO net installations, and GLWA believes that inline nets provide for the most efficient operation and maintenance.



Project Title: Pilot CSO Netting Facility

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$412	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$6,015	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (CA)	\$2,607	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1	\$26,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: Meldrum Sewer Diversion and VR-15 Improvements

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Sewers and Interceptors Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	GLANA Great Lakes Water Authority
	1	

Project Score

88.7

Project Engineer/Manager: Mini Panicker

Director: Biren Saparia

Problem Statement:

The Meldrum Sewer is an uncontrolled CSO that discharges through outfall B-07. Currently, this is an untreated CSO discharge. Untreated CSO discharges allow debris and bacteria make their way into fresh water bodies and are damaging to public health and the environment. The NPDES permit requires control of this outfall to Michigan water quality standards. The Leib Screening and Disinfection Facility was designed with capacity to screen and disinfect the Meldrum Sewer CSO flow, but current...

Scope of Work/Project Alternatives:

The scope of work involves connecting the Meldrum sewer to the Conant-Mt. Elliot Sewer with a diversion pipe that is 5 feet in diameter. New gates will be installed in the Meldrum sewer which direct flow through this diversion and into the Conant-Mt. Elliot sewer, which would then be processed through the Leib Screening and Disinfection Facility. These gates would allow dry weather flow to pass through the Meldrum sewer to the DRI, and would divert wet-weather to Leib SDF. This would reduce ...

Other Important Info:

Recommended in DWSD LTCSO Plan of 2008. This project is driven by recommendations from the Long Term CSO Control Plan from 2008 and further evaluation and recommendation from the Wastewater Masterplan Project (2019).

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$354	\$0	\$0	\$0	\$0	\$0	\$0	\$88	\$89	\$177	\$177
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design & Construction Assistance # 1	\$1,047	\$0	\$0	\$0	\$0	\$0	\$0	\$208	\$280	\$488	\$558
Construction (Build) # 1	\$4,453	\$0	\$0	\$0	\$0	\$0	\$0	\$640	\$1,272	\$1,912	\$2,541 350



Project Title: Long Term CSO Control Plan

Project Score

88

Project Engineer/Manager: Tim Kuhns

Director: Tim Kuhns

Problem Statement:

The NPDES permit which governs CSO Discharges for GLWA requires GLWA to provide for prohibition, elimination, or adequate treatment of combined sewer discharges containing raw sewage. The current plans of 2008 and 2010 were approved by the EGLE (formerly MDEQ) and are the current plans of record. The new NPDES permit issued in July of 2019 opened the door for GLWA to refresh the Long Term Plan and submit to EGLE for review and approval by 11/15/2022. There are 56 total untreated outfalls ope...

Scope of Work/Project Alternatives:

This project will be a predecessor project to executing a long term CSO control plan, as required by the NPDES permit. This project will include evaluation of the requirements and work done under the 2008 and 2010 current plans of record, evaluation of elements within the Wastewater Masterplan aimed at CSO Control, evaluation of affordability, evaluation and siting of specific projects to be executed, and evaluation and programming of recommended projects to address affordability. The RFP for...

Other Important Info:

The wastewater masterplan, has identified elements that are a part of the Long Term Plan, including a new storage conduit on the west-side for first flush capture, in-system storage dams, system diversions, and some strategically selected netting facility locations. These will need to be evaluated further under this project and also evaluated against current system requirements, and former Long Term requirements and plans set forth in 2008 and 2010.



Project Title: Long Term CSO Control Plan

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	5 Year Total
GLWA Salaries	\$105	\$0	\$0	\$31	\$37	\$37	\$74
Professional Services	\$1,422	\$1,122	\$1,122	\$300	\$0	\$0	\$0
Contractual Professional Services (CS-200)	\$2,146	\$240	\$240	\$1,906	\$0	\$0	\$0
Contractual Professional Services (1904197)	\$7,749	\$3,169	\$3,169	\$1,751	\$2,114	\$716	\$2,830
Contractual Professional Services (U of M 2001434)	\$637	\$312	\$312	\$348	\$0	\$0	\$0
Design & Construction Assistance	\$548	\$0	\$0	\$161	\$194	\$194	\$388



Project Title: Oakwood and Leib CSO Facilities Improvement Project

Project Status: Active - Procurement - Board Approved - Design Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Oakwood/Leib Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Oakwood / Leib Cover photo			
Project Engineer/Manager: Scott Worth	Project Sco	pre			
Director: Chris Nastally	79.4	79.4			

Problem Statement:

The Leib CSO Facility has been under utilized for the last 20 years. The WWMP recommended a diversion to the facility which will increase utilization and close an untreated CSO outfall. To prepare for this increased utilization, improvements to the facility are required. The chemical system has functionally failed and the screening system presents operational and maintenance difficulties (pilot facility with different types of screens requiring different maintenance and having different fail...

Scope of Work/Project Alternatives:

To be prepare for the Meldrum Diversion project, the following are needed. Replacement of fine screens, the chemical feed system, improved automation for chemical dosing, improved access, miscellaneous electrical/HVAC and I&C improvements, a new road to improve safety, as well as various safety improvements to facility hatches. The scope of work was refined under CS-299 (CSO Facilities Assessment Project). The following improvements will be planned for: The manual screening in the pump stati...

Other Important Info:

This is a predecessor project to the Meldrum diversion project and should be constructed prior to completion of the Meldrum Diversion to permit use and testing of equipment installed as a part of that project. This project is intended to be completed within a 24 month window from the completion of the NWI diversion project. Given anticipated difficulties of that project, it is likely that this project will be completed much earlier than the NWI diversion and ideally before the NWI diversion to...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$187	\$19	\$19	\$21	\$26	\$26	\$26	\$26	\$26	\$128	\$20
Professional Services	\$31	\$51	\$51	(\$20)	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering (NEW to CIP 2023)	\$7,333	\$0	\$0	\$1,756	\$2,157	\$1,291	\$507	\$582	\$583	\$5,120	\$457
Construction	\$9,000	\$0	\$0	\$0	\$0	\$0	\$2,142	\$2,459	\$2,466	\$7,067	\$1,933



Project Title: CSO Facility Safety Improvements and Building Rehabilitation

Project Status: Reclassified Class LvI 1: Wastewater Class LvI 2: CSO Facilities Class LvI 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Ariadna Risher	Project Score	

0

Project Engineer/Manager: Ariadna Risher

Director: Navid Mehram

Problem Statement:

Project was reclassified with 270006.

A safety inspection of GLWA's nine CSO facilities was conducted under CS-299. A list of safetyrelated issues and corrective actions was generated. Most of the issues are related to the lack of proper fall protection around the numerous hatch openings at each facility. An assessment of building-related issues was also conducted under CS-299. These include damaged sealant around doors, windows, other wall penetrations, control/expansion joints; corrosion ...

Scope of Work/Project Alternatives:

This project provides proper fall protection and address fall/trip hazards for all the nine CSO facilities with the addition of features such as temporary railings, nets, chains, portable davit and ladders with retractable safety posts. It also addresses various building/architectural issues with doors, windows, room finishes, floors and ceiling coating systems, stairways, and corrosion of visible steel members for all nine CSO facilities. The goal of this rehabilitation is to prevent the issu...

Other Important Info:

The building rehabilitation work is bring combined with the safety issues because of the similarity of the design disciplines and the similar nature of construction work.

Primary Driver: Public Health and Safety



Project Title: CSO Facility Safety Improvements and Building Rehabilitation

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1	\$0
Professional Services (CS-166)	\$41	\$41	\$41	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-272)	(\$41)	(\$41)	(\$41)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: CSO Facilities Improvements II

makes for unsafe working conditions. At Baby Creek, there is a need for additional flow meters,

level sensors, process cameras, and local control

for the screens. At Belle Isle, there is a need to

have the ability to control this facility from the

Conner Creek...

Project Status: Active - Procurement - Design Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	
Project Engineer/Manager: Ariadna Risher	Project Score	
Director: Chris Nastally	61	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
There is a need to update the Ovation control system to the latest version and increase monitoring capabilities at Baby Creek and Belle Isle CSO Facilities. The lighting at these facilities is poor or non-existent in some locations, which	This project addresses O&M and safety issues at Baby Creek and Belle Isle to make them more reliable. This project updates the Ovation control system to the latest version which will enhance the overall performance of these facilities. Additional	N/A

lighting will be provided at selected locations at

sensors will be removed and additional flow

Isle,...

both the facilities. At Baby Creek, redundant level

meters, level sensors, process cameras and local

control for the screens will be provided. At Belle



Project Title: CSO Facilities Improvements II

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$133	\$8	\$8	\$10	\$20	\$19	\$19	\$19	\$20	\$98	\$20
Professional Services (CS-272)	\$130	\$62	\$62	\$76	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services (CS-166)	\$45	\$0	\$0	\$45	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$2,891	\$0	\$0	\$322	\$867	\$542	\$0	\$216	\$465	\$2,091	\$478
Construction	\$11,598	\$0	\$0	\$0	\$0	\$0	\$0	\$2,162	\$4,655	\$6,816	\$4,782



Project Title: Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell CSO Facilities

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Wayne Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 		Great Lakes Water Authority				
Project Engineer/Manager: Kashmira Patel		Project Score					
Director: Chris Nastally		57					
Problem Statement:	Scope of Work/Project	Alternatives:	Other Important Info:				
facilities are expensive to maintain and there is a lack of automation of the feed systems. Each facility has a different type of chemical pump, making O&M more difficult and site specific.each facility with stan systems. Other impro sloped floor with a co the Baby Creek Chem a ladder and railing systems		chemical feed systems at dized and automated feed ments include providing a sion resistant coating in al Room and installation of em to access the top of the le Isle odor control system	None				

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$75	\$0	\$0	\$0	\$2	\$11	\$11	\$11	\$34	\$41
Design/Engineering	\$4,323	\$0	\$0	\$0	\$199	\$1,071	\$1,071	\$1,074	\$3,415	\$909
Construction	\$3,893	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$3,893



Project Title: Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 		GLAVA Great Lakes Water Authority
Project Engineer/Manager: TBD	Project Sc	core	
Director: Chris Nastally	74.4		

Problem Statement:

At Conner Creek, a significant amount of solids accumulate in the influent area just upstream of the bar screens. The original flushing system is ineffective and is non-functional. Currently, GLWA staff use a bobcat to fill a dumpster to remove some of the solids and rely on fire hoses to remove the rest - both of which are labor intensive, costly, and involve safety issues.

Also at Conner Creek, the flushing reservoirs in the basin require the use of potable water (after the initial flus...

Scope of Work/Project Alternatives:

This project provides improvements in the influent area of Conner Creek to allow for more efficient removal of accumulated solids and to make the entire influent area more accessible for bobcat maneuverability throughout the entire influent area.

This project also provides for river water as a source of flushing water in the basin, which will provide water savings and will significantly reduce the time to fill the reservoirs.

At St. Aubin, the project includes a new effluent conduit f...

Other Important Info:

The Conner Creek flushing work is being combined with St. Aubin because of the similarity of the design and nature of construction.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$64	\$0	\$0	\$0	\$0	\$2	\$9	\$9	\$9	\$29	\$35
Design/Engineering	\$1,401	\$0	\$0	\$0	\$0	\$58	\$315	\$315	\$154	\$841	\$561
Construction	\$5,605	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$5,605 359



Project Title: Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Wayne Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Kashmira Patel	Project Sc	core
Directory Chris Nastelly	54.6	

Director: Chris Nastally

Problem Statement:

A number of site-related improvements were identified at St. Aubin, Belle Isle and Baby Creek CSO Facilities under CS-299. At the St. Aubin outfall these include: 1) poor drainage in the access drive area between Atwater St. and the fenced area; 2) fencing in disrepair; 3) difficulty in removing hatch plates and 4) limited access to the backwater gates. Poor drainage of the access drive has damaged the road surface and created issues with accessibility to the secured area. In addition, the conc...

Scope of Work/Project Alternatives:

This project includes site improvements at these three CSO facilities. At St. Aubin, various site improvements will be made to address the problems noted above. At Belle Isle, the concrete pavement will be extended to provide an adequate turning radius for the chemical delivery trucks, and other site improvements will be made to address drainage issues. At Baby Creek, a new stop log storage shelter will be constructed to provide protection from UV light for the stop log seals. Other Important Info:

None

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$12	\$0	\$0	\$0	\$0	\$2	\$3	\$10
Design/Engineering	\$276	\$0	\$0	\$0	\$15	\$76	\$91	\$184
Construction	\$1,102	\$0	\$0	\$0	\$0	\$0	\$0	\$1,102



Project Title: HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Rig Redundancy NE WTP Repurposing Linear Assets Outside Predecessor Project(set) 	e of Facilities	Great Lakes Water Authority
Project Engineer/Manager: Brooke Ballard Director: Chris Nastally		Project Score 57.8	
Problem Statement: A number of HVAC-related improvements were identified as needed at Puritan-Fenkell and Seve Mile CSO Facilities under CS-299. The improvements at both facilities require replacement of a large amount of HVAC equipment, due to ag of the equipment or need to improve access for maintenance, and to provide monitoring for code compliance in the Odor Control and Headworks area.	-3, SF-1, SF-2, and executive ent Fenkell and Seven Mile project includes improv- in the Odor Control and the facilities to comply includes removal of H	eplacement of HVAC ACU-1, HVU-1, HVU-2, HVU khaust fans at both Puritan- e CSO Facilities. Also, the vements to enhance safety d Headworks areas at both with NFPA 820. It also /AC equipment from the uent channel since it is not	Other Important Info: NA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$14	\$0	\$0	\$0	\$0	\$2	\$2	\$2	\$2	\$10	\$4
Design/Engineering	\$302	\$0	\$0	\$0	\$15	\$83	\$82	\$8	\$45	\$234	\$67
Construction	\$1,207	\$0	\$0	\$0	\$0	\$0	\$0	\$80	\$452	\$532	\$674



Project Title: HVAC Improvements at Conner Creek and Belle Isle CSO Facilities

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Detroit Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Redundancy NE WTP Repurposing Linear Assets Outside of Predecessor Project(s) 	of Facilities	Great Lakes Water Authority
Project Engineer/Manager: Kashmira Patel		Project Score	
Director: Chris Nastally		70.5	
Problem Statement: A number of HVAC-related improvements were identified at Conner Creek and Belle Isle CSO Facilities under the CS-299 Facilities Assessment. Most of the improvements are related to ventilation, access to HVAC equipment and heating/cooling systems.	to HVAC equipment in the Odor Control Area. Other Isle include the replacer and improvements in the Room and Sample Room project includes improve	orovements to enhance fol area at Belle Isle to as well as improve access the Chemical Room and er improvements at Belle nent of the unit heaters the cooling of the Control m. At Conner Creek, the ements to the heating of the ctrical Room, and Control	Other Important Info: None

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY29-33
GLWA Salaries	\$4	\$0	\$0	\$0	\$3
Design/Engineering	\$107	\$0	\$0	\$0	\$89
Construction	\$307	\$0	\$0	\$0	\$118



Project Title: Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities

 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Score	
59	
Scope of Work/Project Alternatives: This project addresses control system and I&C	Other Important Info: N/a
	WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) Project Score 59 Scope of Work/Project Alternatives:

system to the latest version of Ovation in order to standardize equipment and increase monitoring capabilities at Conner Creek, Oakwood, and Puritan-Fenkell CSO Facilities. In addition, lighting at these facilities is poor or non-existent in some locations, which makes for unsafe working conditions. There is a need for additional flow meters, level sensors, and process cameras at these facilities. Similar issues related to lighting, remote control ... This project addresses control system and I&C issues at Conner Creek, Oakwood, and Puritan-Fenkell. The Ovation control system will be updated to the latest version, which will enhance overall performance. Additional lighting will be provide at these facilities to improve worker safety. At Conner Creek, redundant level sensors will be removed, a new flow meter for dewatering flow downstream of the junction chamber will be provided, and chemical tank level indication and process cameras will be ...

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$54	\$0	\$0	\$0	\$0	\$2	\$9	\$11	\$42
Design/Engineering	\$1,184	\$0	\$0	\$0	\$0	\$63	\$328	\$391	\$794
Construction	\$4,737	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,737



Project Title: Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	GLANA Great Lakes Water Authority

Project Score

56.8

Project Engineer/Manager: TBD

Director: Chris Nastally

Problem Statement:

At Puritan Fenkell and Seven Mile, there are various issues that need to be addressed based on the CS-299 Facilities Assessment. There is poor accessibility to the bearing assemblies of the basin's tipping buckets and to the dewatering forcemain for inspection and cleaning. There are drainage issues at both facilities, which become a safety concern for personnel accessing the buildings during the winter months due to ice. At Puritan Fenkell, there is no means to isolate the dry and wet weather ...

Scope of Work/Project Alternatives:

This project improves surface access to the tipping buckets and dewatering forcemains to facilitate O&M at both the facilities. Similarly, the project will improve the drainage of water at both facilities. At Puritan-Fenkell, isolation of the wet weather and dry weather wet wells will be provided and a stop log removal system will be provided. At Seven Mile, the hatch cover plates will be replaced with lighter-weight hatches. The effluent stop log and effluent hatch replacement would not be nee...

Other Important Info:

The stop log and hatch replacement will not be needed if these basins are converted to complete capture.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$8	\$0	\$0	\$0	\$0	\$0	\$0	\$8
Design/Engineering	\$179	\$0	\$0	\$0	\$0	\$18	\$18	\$161
Construction	\$715	\$0	\$0	\$0	\$0	\$0	\$0	\$715



Project Title: Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities

Project Status: Future Planned - Ten- Year CIP Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Multiple CSO Facilities Lookup Location: Various CSO Facilities Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Brooke Ballard	Project Score	
Director: Chris Nastally	72	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The Wastewater Master Plan identified that Purit Fenkell and Seven Mile can be operated in complete capture mode for flows up to the 10-ye 1-hour design storm. These facilities have not experienced the originally anticipated level of flo and, in fact, the facilities had no discharge for 3 years from 2016 to 2018 and only a few discharges from Puritan Fenkell in 2019 and 202	Seven Mile Facilities to capture-only facilities. ear	NA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$40	\$0	\$0	\$0	\$0	\$0	\$1	\$1	\$29
Design/Engineering	\$888	\$0	\$0	\$0	\$0	\$0	\$38	\$38	\$666
Construction	\$3,554	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,710



Project Title: Hubbell Southfield CSO Facility Improvements

Project Status: Active - Procurement - Design Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Hubbell Southfield Lookup Location: Dearborn Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Kashmira Patel	Project Score)

75.7

Director: Chris Nastally

Problem Statement:

The Hubbell Southfield CSO Basin was constructed in the late 1990s and is in need of major capital improvements. The spray-flushing system is ineffective for removing solids and debris from the floor of the basin and shunt channel after a storm event. Currently, operators must manually use fire hoses and lower a bobcat into the basin after storm events, which is a safety concern due to the confined space, sloped and slippery floors, and poor lighting. The dewatering pumps are unable to handle h...

Scope of Work/Project Alternatives:

A new basin flushing system was recommended by the CS-299 Facilities Assessment consisting of flushing gates and reservoirs (similar to those installed at Conner Creek, Oakwood and Belle Isle CSO Facilities). The project will include new dewatering pumps to replace the existing and new basin sump pumps with a solids system to fluidize accumulated grit to replace non-functional pumps. The project also includes chemical feed system improvements, including pump replacement to standardize pumping s...

Other Important Info:

Additional required repairs were identified in preliminary BODR performed by AECOM under CS272 Task 7-2-030-A.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$654	\$11	\$11	\$3	\$7	\$90	\$90	\$90	\$90	\$368	\$275
Professional Services	\$518	\$417	\$417	\$102	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design/Engineering	\$11,537	\$0	\$0	\$0	\$221	\$2,881	\$2,431	\$0	\$1,419	\$6,952	\$4,586
Construction	\$40,229	\$0	\$0	\$0	\$0	\$0	\$0	\$2,992	\$9,202	\$12,194	\$28,035



Project Title: CSO Hubbell Southfield VR-8 Gate Improvements

Project Status: Future Planned - Within 5 Year Plan Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Hubbell Southfield Lookup Location: Dearborn Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Brooke Ballard	Project Score	
Director: Chris Nastally	50.2	
Problem Statement: The VR-8 Regulator is located upstream of the Hubbell-Southfield CSO Facility in the center median of Michigan Avenue east of the Southfie Freeway. The regulator consists of two stainless steel slide gates that are adjusted by SCADA control to regulate flow from the Hubbell-Southfie sewer to the NWI. A rehabilitation project was designed in 2013, but not implemented. Rehabilitation of the VR-8 Regulator is still need.	near the gates and the control panel. The improvements will help maintain system reliability and functionality.	Other Important Info: n/a

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$16	\$0	\$0	\$0	\$1	\$3	\$3	\$13
Design/Engineering	\$354	\$0	\$0	\$0	\$19	\$98	\$117	\$237
Construction	\$1,416	\$0	\$0	\$0	\$0	\$0	\$0	\$1,416



Project Title: Replacement of Make-up Air Unit No. 2 at Conner Creek CSO Facility

Project Status: Project Execution - Construction Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Conner Creek Lookup Location: Detroit ☑ Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Partho Ghosh	Project Score	
Director: Chris Nastally	92.5	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
The existing Make-up Air Unit No. 2 (MUA 2) at the Conner Creek CSO facility is original installation since the facility was put in operation in 2005. The fan/blower sections have catastrophically failure. Rebuilding/repairing damage of this unit is not cos	No.2 (MUA-2) and associated appurtenances with replaced-in-kind unit and its appurtenances. The purpose of this project includes furnishing,	N/A

the new unit to provide successful and complete

operational system as intended and accepted by

Current Expenses (All figures are in \$1,000's)

effective due to the age and extent of the repair

Therefore, this unit needs a replacement for the

needed. The unit's overall condition is poor.

reliable and efficient operation.

"Total Costs" include costs outside of the 10 year planning window

*Design & Construction costs are inclusive of salaries where salaries are not defined

GLWA.

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23
GLWA Salaries	\$12	\$12	\$12	\$4
Construction	\$301	\$0	\$0	\$301



CIP Number: 277001

Project Status: Active - Procurement - Negotiation Phase - Construction Class Lvl 1: Wastewater Class Lvl 2: CSO Facilities Class Lvl 3: Baby Creek Lookup Location: Baby Creek CSO Facility Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Example of Proposed Facility
	1	

Project Engineer/Manager: Ariadna Risher

Director: Chris Nastally

Problem Statement:

A facility is required to be constructed in order to ensure continued access to the Baby Creek Outfall. In addition system improvements which address sediment accumulation are needed to ensure the CSO can meet NPDES requirements. This system improvement will likely be a flushing system installed inside the outfall, but the best solution is not known at this time. The triple barrel Baby Creek Outfall consists of (3) 14'-6" wide by 17'-6" tall concrete box culverts which extend from the Baby Cree...

Scope of Work/Project Alternatives:

This project consists of a study and design. Construction is anticipated but since the flushing system solution is not known at this time this phase is not included in the project due to the variability in alternatives and their associated costs. The study and design will assess the proper ways to clean the pipes, facilitate future maintenance, flushing of the pipes after rain events, and perform assessments of the backwater gates ensuring proper instrumentation is installed in the outfall to...

Project Score

80.1

Other Important Info:

The current outfall cannot be flushed and the solids level builds up after each rain event. Furthermore, the rising river level continues to impact this facility and its outfall capacity. The build up of sludge inhibits does not favor Baby Creek in passing the necessary flows because the capacity of the pipes are reduced due to the reduction in cross-sectional area.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total
GLWA Salaries	\$1,773	\$427	\$427	\$243	\$302	\$301	\$301	\$207	\$0	\$1,112
Professional Services	\$1,067	\$1,145	\$1,145	(\$68)	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1	\$12,995	\$0	\$0	\$2,335	\$2,897	\$2,889	\$2,889	\$1,986	\$0	\$10,661



Project Title: Baby Creek CSO Facility Influent Flushing System

Project Status: Future Planned - Ten- Year CIP Innovation Class Lvl 1: Wastewater WW Master Plan Class Lvl 2: CSO Facilities Water Master Plan Right Class Lvl 3: Baby Creek Redundancy Lookup Location: Baby Creek NE WTP Repurposing Project New to CIP: Predecessor Project(s)			Great Lakes Water Authority		
Project Engineer/Manager: Brooke Ballard Director: Chris Nastally		Project Score 72.3			

Problem Statement:

A significant amount of solids can accumulate in the Baby Creek influent channel area, immediately upstream of the weir wall at the Headworks. Significant solids buildup can cause hydraulic restrictions and impede inspection of the influent flow meters. There is no flushing system at this location and solids removal must be performed periodically by a contractor which is costly. In addition, the S-2-1 sluice gate opening does not extend to the bottom of the influent channel to allow for complet...

Scope of Work/Project Alternatives:

This project includes evaluation and construction of a new flushing system in the influent area. The project will also include modifying the opening of the sluice gate S-2-1 to make the bottom of the gate opening at a lower elevation which would allow the flushed solids to enter the dewatering well. **Other Important Info:**

NA

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY29-33
GLWA Salaries	\$7	\$0	\$0	\$0	\$0
Design/Engineering	\$148	\$0	\$0	\$0	\$15
Construction	\$591	\$0	\$0	\$0	\$0

O7 CENTRALIZED SERVICES

CENTRALIZED SERVICES PROJECTS



- 1 FUTURE PLANNED
- 2 ACTIVE
- 2 CLOSED
- 0 RECLASSIFIED



MORE: APPENDIX C

FIND THE FULL BUSINESS CASE EVALUATIONS FOR CENTRALIZED SERVICES IN APPENDIX C



PROJECTS ARE FUNDED BY THE WATER OR WASTEWATER SPEND PLANS, OR IN THE PAST COULD BE SPLIT BETWEEN THE TWO.





Project Title: Security Infrastructure Improvements on Water Facilities

Project Status: Closed Class Lvl 1: Centralized Services Class Lvl 2: Security Class Lvl 3: General Purpose Lookup Location: System Wide Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Project Photo
---	---	---------------

Project Engineer/Manager: Charnele Sanders

Director: W. Barnett Jones

Problem Statement:

basis for ini...

GLWA facilities have been designated as "Critical Infrastructure" by the United States Department of Homeland Security (OHS). Critical Infrastructure is considered as exposed to constant threat. GLWA is engaged in a continual process of threat and vulnerability assessment to our facilities, operations, and staff. Using several assessment tools including, OHS Site Assessments, incorporating AWWA security recommendations, and utilizing GLWA's historical assessment data provides the

Scope of Work/Project Alternatives:

Water Works Park: Additional coverage where boats dock and by the screening house. Video assessment wherever there are alarm points. Primary Building needs to be secured. Need video coverage. Switchgear room needs to be secured. Exterior video coverage of oxygen tanks and entrance lo chlorine room. Secure transformer enclosures at the Raw water Booster Station. Interior intrusion detection devices need to be installed at high lift building- glass break, motion sensors, etc. Install Card...

Project Score

0

Other Important Info:

GLWA has a responsibility in what is a layered approach to critical infrastructure security; partnering with Federal, State, and Local law enforcement entities to minimize and respond to threats. This partnership required GLWA to maintain a minimum security posture equating to the Critical Infrastructure designation. Implementation of the security protocols where none existent, and improving the GLWA security foot print can reduce our vulnerabilities and enhance our response to known threats.



Project Title: Security Infrastructure Improvements on Water Facilities

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$220	\$220	\$220	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$740	\$739	\$739	\$1	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (SOQ-135A)	\$12,758	\$12,758	\$12,758	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Water) (CS-201)	(\$2,379)	(\$2,379)	(\$2,379)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Miscellaneous	(\$6,081)	(\$6,081)	(\$6,081)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Status: Closed Class Lvl 1: Centralized Services Class Lvl 2: Security Class Lvl 3: General Purpose Lookup Location: System Wide Project New to CIP:	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Froject Photo
---	---	---------------

Project Engineer/Manager: Charnele Sanders

Director: W. Barnett Jones

Problem Statement:

GLWA facilities have been designated as "Critical Infrastructure" by the United States Department of Homeland Security (OHS). Critical Infrastructure is considered exposed to constant threat. GLWA is engaged in a continual process of threat and vulnerability assessment to our facilities, operations, and staff. Using several assessment tools including, OHS Site Assessments, incorporating AWWA security recommendations, and utilizing GLWA's historical assessment data, provides the basis for initi...

Scope of Work/Project Alternatives:

AWWA security recommendations, and utilizing GLWA's historical assessment data, provides the basis for initiating a strategic plan for security infrastructure improvements. The resulting data from these assessments helps formulate recommendations for mitigating vulnerabilities.

0

Project Score

Other Important Info:

GLWA has a responsibility in the layered approach to critical infrastructure security; partnering with Federal, State, and Local law enforcement entities to minimize and respond to threats. This partnership required GLWA to maintain a minimum security posture equating to the Critical Infrastructure designation. Implementation of the security protocols where none existent, and improving the GLWA security foot print can reduce our vulnerabilities and enhance our response to known threats.

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$7	\$7	\$7	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$109	\$95	\$95	\$18	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Design-Build # 1 (SOQ-135A)	\$2,247	\$2,247	\$2,247	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0



Project Title: As-Needed Geotechnical and Related Engineering Services

Project Status: Project Execution - Design Class Lvl 1: Centralized Services Class Lvl 2: Programs Class Lvl 3: Programs Lookup Location: System-wide	 Innovation WW Master Plan Water Master Plan Right Sizing Redundancy NE WTP Repurposing Linear Assets Outside of Facilities Predecessor Project(s) 	Great Lakes Water Authority
Project Engineer/Manager: Peter Fromm	Project Score	
Director: Peter Fromm	0	
Problem Statement:	Scope of Work/Project Alternatives:	Other Important Info:
GLWA engineering and operations needed a contract mechanism to obtain professional engineering services in a timely manner to investigate environmental, geotechnical and specialized engineering problems that occur on a regular basis throughout the system.	This engineering/technical services contract involves as-needed engineering and technical services related to geotechnical investigations, related geotechnical engineering, construction materials sampling and testing, environmental media sampling and testing, soils sampling and testing, land surveying, corrosion testing and inspection, computer-aided design, and construction inspection. This contract includes design, construction services, and resident project representation for the follow tr	N/A

Current Expenses (All figures are in \$1,000's)

"Total Costs" include costs outside of the 10 year planning window

Activity Name	Total Costs	Actual Costs	Prior FYs	FY23	FY24	FY25	FY26	FY27	FY28	5 Year Total	FY29-33
GLWA Salaries	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Professional Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
Construction (Build) # 1 (CS-259)	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

Placeholder for Image

APPENDICES



