

FY2022 Drinking Water Revolving Fund Public Hearing June 23, 2021

*96-inch Water Transmission Main
Relocation Project*



Topics

1. Overview
 - a) Background Information
 - b) Project Objectives and Overview
 - c) Project Schematic and Location
2. Implementation Alternatives
3. Engineer's Opinion of Cost Breakdown
4. Recommended Alternative
5. Implementation Schedule

Highlights: 96-inch Water Transmission Main



Project Objectives

Primary Objectives:

- Relocate 96-inch water transmission main (WTM) outside of closed G&H Industrial Landfill, Detroit Sportsmen's Congress Gun Club, and residential properties to improve access for future operations and maintenance.
- Continue providing essential, uninterrupted drinking water throughout construction.

Other Project Objectives Include:


- Coordinate with other area infrastructure projects to minimize impacts.
- Improve traffic flow and pedestrian safety by making transportation enhancements.
- Design and construct infrastructure to support temporary shutdown of 96-inch WTM.

Project Overview

Project includes the following components:

- Construct approximately 2.5 miles of 96-inch diameter water transmission main
- Construct 4 valve vault stations equipped with 84-inch diameter isolation valves at locations along existing 96-inch water transmission main
- Design, build and operate a temporary water booster pumping station to maintain uninterrupted water service during construction
- Build and operate 3 water discharge facilities during construction
- Construct roadway improvements, including a new roundabout in coordination with road authorities having jurisdiction
- Abandon approximately 2.2 miles of existing 96-inch diameter transmission main
- Rehabilitate or replace air/vacuum relief valves and blow off valves on existing 96-inch water main to facilitate its draining and filling

Project Overview Schematic




ID / Description			
A	PLUMBROOK DRAIN DISCHARGE FACILITY (PDDF)	H	INTERTIE WATER MAINS IMLAY CITY, ALMONT AND IMLAY TOWNSHIP
B	NEW NSC VALVE	I	72" WTM DISCHARGE FACILITY
C	96" WTM HAMLIN TIE-IN	J	CHESTERFIELD LOOP TEMPORARY BOOSTER PUMP STATION (CLTBPS)
D	NEW 96" WTM	K	ABANDONED 96" WTM
E	24 MILE VALVE WITH BYPASS TO ROCHESTER BOOSTER PUMP STATION	L	26 MILE VALVE WITH BYPASS TO METERED CONNECTIONS
F	96" WTM 24 MILE TIE-IN	M	ROMEO VALVE WITH BYPASS TO METERED CONNECTIONS
G	96" WTM CRITICAL APPURTENANCES (MULTIPLE LOCATIONS NSC TO DDV)	N	EAST POND CREEK DISCHARGE FACILITY (EPCDF)

LEGEND:

EXISTING WATER MAIN (WATER TRANSMISSION MAIN OR "WTM")	EXISTING WATER TREATMENT PLANT (WTP)	FLOW DIRECTION DURING SHUTDOWN	NEW TIE IN
ABANDONED WATER MAIN	BOOSTER PUMP STATION WITH RESERVOIR	NEW ISOLATION VALVE	NEW DISCHARGE FACILITY
NEW WATER MAIN	EXISTING BOOSTER PUMP STATION	ABANDONED ISOLATION VALVE	EXISTING METERED CONNECTION

New 96-inch Water Transmission Main

- Approximately 2.5 miles (13,500 LF)
- Tie-ins at 24 Mile Road and Hamlin Road
- Mostly in roadway and Maccomb Orchard Trail right of ways
- Open cut crossing of Clinton River



Implementation Alternatives

Eleven (11) implementation alternatives were developed and narrowed to four (4) considered for final selection:

Component	Alternative 2 (CLBPS with 26 Mile Road Pump Station)	Alternative 7 (Parallel Main)	Alternative 10 (96-inch Relocated Main "NSC Feed")	Alternative 11 (Extended Adams to Rochester Loop)
Relocate 96-inch WTM	X	X	X	X
Abandon Existing 96-inch WTM	X	X	X	X
96-Inch Main Appurtenances Rehabilitation	X	X	X	X
East Pond Creek Discharge Facility (EPCDF)	X		X	X
Plumbrook Drain Discharge Facility (PDDF)	X	X	X	X
South Branch Flint River Discharge Facility (SBRDF)	X	X	X	X
Temporary Chesterfield Loop Booster Station		X	X	
Permanent Chesterfield Loop Booster Station	X			
Isolation Valve: Romeo	X	X	X	X
Isolation Valve: 26 Mile Road	X		X	X
Isolation Valve: North Service Center	X	X	X	X
Full Parallel Main - Rochester BPS to BU-01		X		
Rochester Loop/Adams Rd Pipeline				X
Rochester West and WG-02 Laterals-Main				X

Engineer's Opinion of Cost Breakdown

Project Costs of Final Implementation Alternatives:

Category	Alternative 2	Alternative 7	Alternative 10	Alternative 11
Total Project Cost	\$186,803,000	\$253,921,000	\$170,361,000	\$269,262,000
Selected Alternative	No	No	Yes	No

Estimated Planning-level Cost of Selected Implementation Alternative 10 (96-inch Relocated Main "NSC Feed"):

Item	Alternative 10 Estimated Planning-level Cost (\$)
Member Partner Backup Systems	\$2,169,000
Design, Permitting, Assistance During Construction	\$26,635,000
CMAR Pre-Construction Services	\$500,000
Opinion of Probable Construction Cost	\$141,057,000
Total Project Cost	\$170,361,000

Implementation Schedule

Following is list of key project milestones:

- Award of Construction Contract (CMAR): Q4 2021
- Pipeline Construction Start: March 2022
- Final Design Package to GLWA: Q3 2022
- Start First Pipeline Shutdown: October 15, 2024
- New, Relocated Pipeline in Full Service: April 15, 2025
- Contract Completion: November 2027 (includes 1 year of project closeout)



GLWA

Great Lakes Water Authority