



**DRAFT NO.1
GLWA's
FY2023- 2027
Capital
Improvement
Plan**



**Asset Management Leadership Team (AMLT)
October 14, 2021
1:00 p.m.**

AGENDA


- ◆ **OVERVIEW OF FIRST DRAFT OF 2023-2027 CIP – DIMA EL-GAMAL**
- ◆ **HIGHLIGHTED WASTEWATER PROJECTS – DAN ALFORD**
- ◆ **HIGHLIGHTED WATER PROJECTS – GRANT GARTRELL**
- ◆ **HIGHLIGHTED FIELD SERVICES AND SYSTEMS CONTROL PROJECTS - TODD KING**
- ◆ **NEXT STEPS & CLOSING REMARKS – DIMA EL-GAMAL**

DESIRED OUTCOME

- 💧 Review and discuss FY23-27 CIP summary
- 💧 Familiarize the CIP Committee with the FY23-27 CIP document
- 💧 Identify schedule milestones
- 💧 Next steps

GOALS AND OBJECTIVES

- ◆ Address projects that promote improved redundancy, system resiliency, and health & safety
- ◆ Conformance with recommendations of long-term master plans
- ◆ Share information and solicit stakeholders input
- ◆ CIP alignment with the financial plan
- ◆ Meet regulatory and operational needs



The goal of the CIP is to provide regional collaboration & planning to balance capital expenditures demands without compromising our mission "implement best practices in the treatment and transmission/conveyance of water and wastewater".


CIP IMPROVEMENTS FY2023 – 2027

- ◆ CIP REPORT
 - ◆ Streamlined TOC
 - ◆ Project Breakdown
 - ◆ Acknowledgement Page
- ◆ Validation Updates
- ◆ Scoring Methodology



CIP SUMMARY

5-Year Outlook



| WATER | (\$1,000's) |
|----------------------|--------------------|
| 5-Year Total | \$977,264 |
| 5-Year Average | \$195,453 |
| 10-Year Total | \$1,893,299 |
| 10-Year Average | \$189,330 |

| WASTEWATER | (1,000's) |
|----------------------|--------------------|
| 5-Year Total | \$761,764 |
| 5-Year Average | \$152,353 |
| 10-Year Total | \$1,381,808 |
| 10-Year Average | \$138,181 |



36 New Projects*

14 Closed Projects

181 Projects**

5-Year Total \$1.74 Billion
5-Year Annual Average \$348 Million

10-Year Total \$3.28 Billion
10-Year Annual Average \$328 Million

**18 NEW PROJECTS FROM PROGRAM*

*** IN ADDITION TO THE 181 PROJECTS, THERE ARE:
+4 RECLASSIFIED PROJECTS
+1 CANCELLED PROJECT*

WATER SUMMARY

NEW PROJECTS

PROJECTS WITH SIGNIFICANT ADJUSTMENTS

HIGH LEVEL SUMMARY OF SPENDING PLAN

PROJECTS FROM WATER MASTER PLAN RIGHT SIZING



WATER: NEW PROJECTS WITHIN 5 YEARS

| CIP # | Title | Total Project \$ | Design Start | Construction Start | Construction End |
|---------|--|------------------|--------------|--------------------|------------------|
| 115008 | Jefferson Main Replacement Project | \$ 29,700,001 | FY22 | FY26 | FY28 |
| 116007 | System Electrical Power Improvements | \$ 4,000,000 | FY24 | TBD | TBD |
| 170802* | Reservoir Inspection, Design, and Construction Management Services Phase II | \$ 41,500,000 | FY22 | FY23 | FY27 |
| 170304* | WWP Scada Infrastructure Upgrade | \$ 318,626 | FY22 | FY23 | FY25 |
| 170306* | SPW SCADA PLC Network Upgrade | \$ 3,146,000 | FY23 | FY23 | FY24 |
| 170601* | Linear System Integrity Program | \$ 9,081,824 | FY21 | FY24 | FY26 |
| 170803* | Reservoir Inspection, Design, and Construction Management Services Phase III | \$ 93,916,000 | FY27 | FY29 | +FY33 |

**From Programs*

WATER: NEW PROJECTS FUTURE PLANNED WITHIN 10 YRS

| CIP # | Title | Total Project \$ | Design Start | Construction Start | Construction End |
|---------|---|------------------|--------------|--------------------|------------------|
| 113008 | SWP Reservoir Replacement | \$ 45,000,001 | FY28 | FY30 | +FY33** |
| 115009 | Water Works Park Sedimentation Basins Structural Upgrades | \$ 18,339,223 | FY28 | FY28 | FY31 |
| 170305* | WWP SCADA Network Upgrade | \$ 7,336,000 | FY28 | FY28 | FY30 |
| 170307* | NE SCADA Network Upgrade | \$ 2,917,000 | FY30 | FY30 | FY31 |
| 171502* | Lake Huron and Southwest Roof Replacement | \$ 2,703,038 | FY29 | FY29 | FY30 |

***From Programs**

**** End Date Beyond Planning Period**

WATER: PROJECTS W/SCHEDULE SHIFT 2 YRS OR MORE (1/3)

- 31 Total water projects with a schedule change of 2 years or more
- Shifts impacted by changing asset conditions, organizational priorities and financial alignment

| CIP# | Title | CIP 2022 | | CIP 2023 | | Impact (yrs) | |
|--------|--|----------|------|----------|-------|--------------|-----|
| | | Start | End | Start | End | Start | End |
| 111001 | Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements | FY19 | FY29 | FY20 | +FY33 | 1 | |
| 111006 | Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements | FY16 | FY24 | FY16 | FY28 | 0 | 3 |
| 111008 | Lake Huron Water Treatment Plant, Architectural Programming for Laboratory and Admin Building | FY26 | FY30 | FY28 | FY29 | 2 | -1 |
| 111010 | Filtration Improvements | FY24 | FY31 | FY28 | +FY33 | 4 | |
| 112006 | Northeast Water Treatment Plant Flocculator Replacements | FY19 | FY25 | FY19 | FY27 | 0 | 2 |
| 113003 | Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration | FY27 | FY31 | FY29 | FY31 | 2 | 0 |
| 114005 | Springwells Water Treatment Plant, Administration Building Improvements & Underground Fire Protection Loop | FY18 | FY24 | FY19 | FY32 | 1 | 8 |
| 114010 | Springwells Water Treatment Plant, Yard Piping and High-Lift Header Improvements | FY19 | FY31 | FY28 | +FY33 | 1 | |
| 115001 | Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement | FY16 | FY28 | FY16 | FY26 | 0 | -2 |
| 115005 | WWP WTP Building Ventilation Improvements | FY19 | FY27 | FY21 | FY25 | 2 | -2 |
| 115007 | Water Works Park High Lift Pumping Station Modernization | FY22 | FY31 | FY28 | +FY33 | 6 | |



WATER: PROJECTS W/SCHEDULE SHIFT 2 YRS OR MORE (2/3)

| CIP# | Title | CIP 2022 | | CIP 2023 | | Impact (yrs) | |
|---------|--|----------|------|----------|-------|--------------|-----|
| | | Start | End | Start | End | Start | End |
| 116006 | Belle Isle Intake System Rehabilitation and Improvements | FY23 | FY24 | FY28 | FY32 | 5 | 8 |
| 122007 | Merriman Road Water Transmission Main Loop | FY20 | FY31 | FY28 | +FY33 | 8 | |
| 122016 | Downriver Transmission Main Loop | FY18 | FY27 | FY20 | FY28 | 2 | 1 |
| 132007 | Energy Management: Freeze Protection Pump Installation at Imlay Pump Station | FY18 | FY23 | FY20 | FY23 | 2 | 0 |
| 132012 | Ypsilanti Booster Pumping Station Improvements | FY18 | FY27 | FY20 | FY29 | 2 | 2 |
| 132014 | Adams Road Pumping Station Improvements | FY20 | FY30 | FY20 | +FY33 | 0 | |
| 132015 | Newburgh Road Booster Pumping Station Improvements | FY19 | FY27 | FY20 | FY32 | 1 | 5 |
| 132016 | North Service Center Pumping Station Improvements | FY20 | FY29 | FY21 | FY31 | 1 | 2 |
| 132018 | Schoolcraft Pumping Station Improvements | FY38 | FY47 | FY35 | +FY33 | -3 | |
| 132019 | Wick Road Pumping Station Improvements | FY20 | FY31 | FY28 | +FY33 | 8 | |
| 132021 | Imlay Pumping Station Improvements | FY30 | FY31 | FY20 | +FY33 | -10 | |
| 132022 | Joy Road Pumping Station Improvements | FY20 | FY31 | FY20 | +FY33 | 0 | |
| 170109* | GLWA-CS-187: FK Eng: Raw Water Intake | FY16 | FY20 | FY16 | FY23 | 0 | 3 |
| 170300 | Water Treatment Plant Automation Program | FY21 | FY22 | FY21 | ** | 0 | |
| 170400 | Water Transmission Improvement Program | FY19 | FY31 | FY21 | ** | 2 | |



WATER: PROJECTS W/SCHEDULE SHIFT 2 YRS OR MORE (3/3)

| CIP# | Title | CIP 2022 | | CIP 2023 | | Impact (yrs) | |
|---------|--|----------|------|----------|------|--------------|-----|
| | | Start | End | Start | End | Start | End |
| 170600 | Water Transmission Main Asset Assessment Program | FY21 | FY27 | FY21 | ** | 0 | |
| 170801* | Reservoir Inspection, Design and Construction Project at Imlay Station, Lake Huron Water Treatment Plant, SPWTP, SWWTP | FY21 | FY28 | FY19 | FY24 | -2 | -4 |
| 170900 | Suburban Water Meter Pit Rehabilitation and Meter Replacement | FY21 | FY31 | FY21 | ** | 0 | |
| 171500 | Roof Replacement at WWP, SP, LH, NE, SW, NSC, Orion, Franklin, and Conner Creek Facilities | FY18 | FY31 | FY21 | ** | 3 | |
| 381000 | Power Quality: Electric Metering Improvement Program | FY24 | FY28 | FY20 | ** | -4 | |

WATER: PROJECTS FROM WATER MASTER PLAN RIGHT SIZING

| CIPNumber | Title | Sum of CIP 2023 5 Yr Total | Sum of CIP 2023 10 Yr Total |
|--------------------|--|-------------------------------|--------------------------------|
| 111001 | Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements | \$6,113,460 | \$55,064,815 |
| 111010 | Filtration Improvements | \$0 | \$14,661,120 |
| 111011 | Lake Huron WTP Pilot Plant | \$1,617,809 | \$1,617,809 |
| 112003 | Northeast Water Treatment Plant High-Lift Pumping Station Improvements | \$20,000,000 | \$71,748,677 |
| 113003 | Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System Improvements | \$0 | \$21,811,843 |
| 114002 | Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements | \$108,952,140 | \$254,491,128 |
| 115001 | Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement | \$37,502,196 | \$37,502,196 |
| 115007 | Water Works Park High Lift Pumping Station Modernization | \$0 | \$38,350,000 |
| 122003 | Water Works Park to Northeast Transmission Main | \$100,233,422 | \$119,355,002 |
| 122007 | Merriman Road Water Transmission Main Loop | \$0 | \$11,446,942 |
| 122017 | 7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station | \$39,994,888 | \$58,251,433 |
| 132007 | Energy Management: Freeze Protection Pump Installation at Imlay Pump Station | \$115,188 | \$115,188 |
| 132019 | Wick Road Pumping Station Improvements | \$0 | \$5,072,323 |
| Grand Total | | \$314,529,103 | \$689,488,476 |

FY 23-27

Water:

\$977,263,932

Master Plan:

\$314,529,103: 32%

FY 28-32

Water:

\$916,035,555

Master Plan:

\$374,959,373: 41%

FY2023-2027 WATER SUMMARY

Financial figures in table are in \$1,000s and rounded

| CIP Document | FY2022 | FY2023 | FY2024 | FY2025 | FY 2026 | FY 2027 | 5-Year Total |
|---------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|--------------|
| Approved Water CIP FY 2022-2026 | \$179,210 | 200,713 | \$199,165 | \$170,936 | \$182,430 | \$232,796 | \$932,454 |
| Draft Water CIP FY 2023-2027 | | \$196,693 | \$227,768 | \$223,934 | \$176,999 | \$151,870 | \$977,264 |
| Difference (\$) | | (\$4) | \$29 | \$53 | (\$5) | (\$81) | \$45 |
| Difference (%) | | -2% | 14% | 31% | -3% | -35% | 5% |

(Figures are shown in \$1,000's.)


- 5% Increase 5-year total between FY22-FY26 & Proposed FY23-27 CIP
- Total 5-year projected expenditures (FY23-27 is \$977,263,932)
- 5-year annual average \$195,452,786 FY23 (compared to \$187,058,558 from FY22)

WATER: FY2023-2032 DRAFT 10-YEAR OUTLOOK

Financial figures in \$1,000s and rounded

| | FY 2023 | FY 2024 | FY 2025 | FY 2026 | FY 2027 | FY 2028 | FY 2029 | FY 2030 | FY 2031 | FY 2032 |
|--------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Projects | \$178,617 | \$221,140 | \$219,382 | \$172,454 | \$148,633 | \$208,594 | \$195,313 | \$144,658 | \$146,377 | \$128,010 |
| Programs | \$18,076 | \$6,628 | \$4,552 | \$4,545 | \$3,237 | \$9,760 | \$23,190 | \$24,595 | \$20,059 | \$15,479 |
| Total | \$196,693 | \$227,768 | \$223,934 | \$176,999 | \$151,870 | \$218,354 | \$218,503 | \$169,253 | \$166,436 | \$143,489 |

10- Year Water CIP Outlook



- 4% increase in 10-year total from FY2022 CIP

WASTEWATER SUMMARY

NEW PROJECTS

PROJECTS WITH SIGNIFICANT ADJUSTMENTS

HIGH LEVEL SUMMARY OF SPENDING PLAN



WASTEWATER: NEW PROJECTS WITHIN 5 YEARS (1/2)

| CIP # | Title | Total Project \$ | Design Start | Const. Start | Const. End |
|---------|---|------------------|--------------|--------------|------------|
| 213009 | WRRF Biosolids Processing Improvements | \$ 180,000,002 | FY26 | FY30 | +FY33 |
| 260209* | Sewer Rehabilitation and Repair | \$ 12,200,000 | FY23 | FY24 | FY25 |
| 260900* | WRRF Facility Optimization Program | \$ 428,948 | TBD | TBD | TBD |
| 270005 | CSO Facility Safety Improvements and Building Rehabilitation | \$ 6,481,200 | FY23 | FY26 | FY29 |
| 270006 | Control System Upgrades at Baby Creek and Belle Isle CSO Facilities | \$ 1,915,600 | FY23 | FY26 | FY29 |
| 270007 | Disinfection System Improvements at Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell | \$ 8,216,300 | FY25 | FY29 | FY32 |
| 270008 | Flushing System Improvements at Conner Creek and St. Aubin CSO Facilities | \$ 7,006,500 | FY25 | FY29 | FY32 |
| 270009 | Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities | \$ 1,377,500 | FY27 | FY30 | +FY33 |
| 270010 | HVAC Improvements at Puritan Fenkell and Seven Mile CSO Facilities | \$ 1,508,590 | FY24 | FY27 | FY30 |

WASTEWATER: NEW PROJECTS WITHIN 5 YEARS (2/2)

| CIP # | Title | Total Project \$ | Design Start | Const. Start | Const. End |
|---------|--|------------------|--------------|--------------|------------|
| 270012 | Control System Upgrades at Conner Creek, Oakwood, and Puritan Fenkell CSO Facilities | \$ 5,921,080 | FY27 | FY30 | FY33+ |
| 260207* | Rehabilitation of Woodward Sewer Systems | \$ 19,160,077 | FY20 | FY22 | FY25 |
| 260621* | Conner Creek Dike Improvements | \$ 2,541,534 | FY21 | FY22 | FY22 |
| 260622* | CSO Emergency Generator Improvements | \$ 2,060,893 | FY22 | FY23 | FY24 |
| 260623* | CSO Baby Creek Screen Rehabilitation | \$ 2,174,900 | FY22 | FY23 | FY24 |
| 260701* | Conveyance System Infrastructure Improvements | \$ 55,630,839 | FY22 | FY23 | FY26 |
| 260702* | Pump Station Assets Updates | \$ 2,000,000 | FY24 | FY24 | FY26 |
| 260902* | WRRF 4th Floor Renovation | \$ 2,720,566 | FY19 | FY20 | FY23 |
| 260903* | WRRF Front Entrance Rehabilitation | \$ 1,004,587 | FY19 | FY20 | FY23 |
| 273001* | Hubbell Southfield CSO Facility Improvements | \$ 38,576,300 | FY23 | FY27 | FY31 |
| 273002* | CSO Hubbell Southfield VR-8 Gate Improvements | \$ 1,769,780 | FY27 | FY30 | FY33+ |



WASTEWATER: NEW PROJECTS FUTURE PLANNED WITHIN 10 YEARS

| CIP # | Title | Total Project \$ | Design Start | Const. Start | Const. End |
|--------|---|------------------|--------------|--------------|------------|
| 270011 | HVAC Improvements at Conner Creek and Belle Isle CSO Facilities | \$ 383,600 | FY31 | FY33 | +FY33 |
| 270013 | Facility Improvements at Puritan Fenkell and Seven Mile CSO Facilities | \$ 894,020 | FY28 | FY30 | +FY33 |
| 270014 | Conversion to Complete Capture Basin at Puritan Fenkell and Seven Mile CSO Facilities | \$ 4,442,170 | FY28 | FY32 | +FY33 |
| 277002 | Baby Creek CSO Facility Influent Flushing System | \$ 738,260 | FY33 | FY35 | +FY33 |

WASTEWATER: PROJECTS W/SCHEDULE SHIFT 2 YRS OR MORE (1/2)

| CIP# | Title | CIP 2022 | | CIP 2023 | | Impact (yrs) | |
|--------|---|----------|------|----------|-------|--------------|-----|
| | | Start | End | Start | End | Start | End |
| 211005 | WRRF PS No. 2 Improvements Phase II | FY19 | FY31 | FY20 | FY33+ | 1 | |
| 211007 | WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements | FY19 | FY27 | FY20 | FY29 | 1 | 2 |
| 211009 | WRRF Rehabilitation of the Circular Primary Clarifier Scum Removal System | FY20 | FY25 | FY20 | FY28 | 0 | 3 |
| 211011 | WRRF PS1 Screening and Grit Improvements | FY20 | FY31 | FY28 | FY33+ | 8 | |
| 212007 | WRRF Rehabilitation of the Secondary Clarifiers | FY20 | FY31 | FY20 | FY33+ | 0 | |
| 212008 | WRRF Aeration Improvements 1 and 2 | FY20 | FY27 | FY21 | FY30 | 1 | 3 |
| 212009 | WRRF Aeration Improvements 3 and 4 | FY25 | FY31 | FY30 | FY33 | 5 | |
| 212010 | WRRF Conversion of Disinfection of all Flow to Sodium Hypochlorite and Sodium Bisulfite | FY21 | FY31 | FY29 | FY33+ | 8 | |
| 213006 | WRRF Improvements to Sludge Feed Pumps at Dewatering Facilities | FY20 | FY24 | FY20 | FY26 | 0 | 2 |
| 213008 | WRRF Rehabilitation of the Ash Handling Systems | FY19 | FY27 | FY20 | FY32 | 1 | 5 |
| 216006 | Assessment and Rehabilitation of WRRF yard piping and underground utilities | FY19 | FY26 | FY21 | FY25 | 2 | -2 |
| 216007 | DTE Primary Electric 3rd Feed Supply to WRRF | FY19 | FY22 | FY17 | FY22 | -2 | 0 |
| 232002 | Freud & Conner Creek Pump Station Improvements | FY16 | FY29 | FY16 | FY31 | 0 | 2 |
| 260200 | Sewer and Interceptor Rehabilitation Program | FY21 | FY27 | FY21 | ** | 0 | |

- 19 Total Wastewater projects with a schedule shift of 2 years or more.



WASTEWATER: PROJECTS W/SCHEDULE SHIFT 2 YRS OR MORE (2/2)

| CIP# | Title | CIP 2022 | | CIP 2023 | | Impact (yrs) | |
|---------|--|----------|------|----------|------|--------------|-----|
| | | Start | End | Start | End | Start | End |
| 260510* | Conveyance System Repairs (Outfalls) | FY20 | FY27 | FY20 | FY29 | 0 | 2 |
| 260600 | CSO FACILITIES IMPROVEMENT PROGRAM | FY21 | FY31 | FY21 | ** | 0 | 13 |
| 260619* | Control System Upgrade - St Aubin, Lieb & Mile | FY20 | FY21 | FY20 | FY25 | 0 | 4 |
| 270002 | Meldrum Sewer Diversion and VR-15 Improvements | FY22 | FY29 | FY25 | FY30 | 3 | 1 |
| 270003 | Long Term CSO Control Plan | FY20 | FY25 | FY20 | FY25 | 0 | -3 |



WASTEWATER: FLOOD MITIGATION PROJECTS

| CIP No | Title | Sum of CIP 2023 5 Yr Total | Sum of CIP 2023 10 Yr Total |
|--------|---|----------------------------|-----------------------------|
| 211006 | WRRF PS No. 1 Improvements | \$48,645,384 | \$65,949,998 |
| 211007 | WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements | \$54,878,238 | \$84,261,425 |
| 222001 | Oakwood District Intercommunity Relief Sewer Modification at Oakwood District | \$40,311,307 | \$51,808,793 |
| 222002 | Detroit River Interceptor (DRI) Evaluation and Rehabilitation | \$21,614,223 | \$29,614,223 |
| 232002 | Freud & Conner Creek Pump Station Improvements | \$126,094,513 | \$248,458,530 |
| 260204 | Conveyance System Engineering Services-1802575 | \$47,833,293 | \$47,833,293 |
| 260205 | NWI Rehabilitation | \$10,074,425 | \$10,074,425 |
| 260206 | Conveyance System Repairs (Sewers) | \$20,610,660 | \$30,099,091 |
| 260207 | Rehabilitation of Woodward Sewer Systems | \$14,559,187 | \$14,559,187 |
| 260701 | Conveyance System Infrastructure Improvements | \$48,472,812 | \$48,472,812 |
| | | \$433,094,042 | \$631,131,777 |

FY 23-27

Wastewater:

\$761,764,137

Flood Mitigation:

\$433,094,042: 57%

FY 28 – 32

Wastewater:

\$620,043,920

Flood Mitigation:

\$198,037,735: 32%

FY2023-2027 WASTEWATER SUMMARY

| CIP Document | FY2022 | FY2023 | FY2024 | FY2025 | FY 2026 | FY 2027 | 5-Year Total |
|---|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Approved Wastewater CIP FY 2022-2026 | \$106,050 | \$123,190 | \$160,940 | \$173,024 | \$175,200 | \$210,615 | \$738,403 |
| Draft Wastewater CIP FY 2023-2027 | | \$125,932 | \$162,313 | \$184,523 | \$157,689 | \$131,307 | \$761,764 |
| Difference (\$) | | \$3 | \$1 | \$11 | (\$18) | (\$79) | \$23 |
| Difference (%) | | 2% | 1% | 7% | -10% | -38% | 3% |

(Figures are shown in \$1,000's.)


- 3% Increase 5-year total between FY22-26 & proposed FY23-27 CIP
- Total 5-year projected expenditures (FY23-27 is \$761,764,137)
- 5-year annual average \$152,352,827 (compared to \$147,875,352 from FY 22)

WASTEWATER: FY23-27 DRAFT 10-YEAR OUTLOOK

Financial figures in \$1,000s and rounded

| | FY 2023 | FY 2024 | FY 2025 | FY 2026 | FY 2027 | FY 2028 | FY 2029 | FY 2030 | FY 2031 | FY 2032 |
|--------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|-----------------|
| Projects | \$63,531 | \$100,953 | \$132,258 | \$137,670 | \$116,012 | \$150,285 | \$131,172 | \$102,649 | \$109,590 | \$72,232 |
| Programs | \$62,402 | \$61,361 | \$52,265 | \$20,019 | \$15,295 | \$20,783 | \$19,787 | \$9,058 | \$3,894 | \$594 |
| Total | \$125,932 | \$162,313 | \$184,523 | \$157,689 | \$131,307 | \$171,068 | \$150,958 | \$111,707 | \$113,484 | \$72,826 |

10-Year Wastewater CIP Outlook



- 2% decrease in 10-year total from FY22 CIP

PROJECT STATUS CHANGES



WASTEWATER: PROJECT CHANGES – PENDING CLOSEOUT OR CLOSED (1/2)

| DEPT | ProjectStatus | CIPNumber | Title | Sum of Project Totals |
|--------------------|-------------------------------|-----------|---|-----------------------|
| WATER | Closed | 111002 | Lake Huron Water Treatment Plant, Miscellaneous Mechanical HVAC Improvements | \$8,736,720 |
| | | 112005 | Northeast Water Treatment Plant - Replacement of Covers for Process Water Conduits | \$937,879 |
| | | 113002 | Southwest Water Treatment Plant, High-Lift Pump Discharge Valve Actuators Replacement | \$5,798,925 |
| | | 114001 | Springwells Water Treatment Plant, 1958 Filter Rehabilitation and Auxiliary Facilities Improvements | \$99,764,892 |
| | | 115004 | Water Works Park Water Treatment Plant Chlorine System Upgrade | \$6,966,596 |
| | | 132003 | West Service Center Pumping Station, Isolation Gate Valves for Line Pumps | \$1,742,479 |
| | | 170200 | As-Needed Construction Materials, Environmental Media and Special Testing Services, Construction Inspection, and Other Technical Services | \$0 |
| | Closed Total | | | \$123,947,490 |
| | Pending Closeout | 111007 | Lake Huron Water Treatment Plant, Raw Sludge Clarifier and Raw Sludge Pumping System Improvements | \$9,098,977 |
| | | 114008 | Springwells Water Treatment Plant 1930 Sedimentation Basin Sluice Gates, Guides & Hoists Improvements | \$13,980,071 |
| | | 114013 | Springwells Water Treatment Plant, Reservoir Fill Line Improvements | \$4,720,158 |
| | | 132006 | Ford Road Pumping Station, Pressure and Control Improvements | \$3,226,045 |
| | | 132026 | Franklin Pumping Station Valve Replacement | \$986,376 |
| | | 341001 | Security Infrastructure Improvements on Water Facilities | \$4,238,914 |
| | Pending Closeout Total | | | \$36,250,541 |
| WATER Total | | | | \$160,198,031 |

WASTEWATER: PROJECT CHANGES – PENDING CLOSEOUT OR CLOSED (2/2)

| DEPT | ProjectStatus | CIPNumber | Title | Sum of Project Totals |
|--------------------|-------------------------------|-----------|---|-----------------------|
| SEWER | Closed | 211004 | WRRF PS #1 Rack & Grit and MPI Sampling Station 1 Improvements | \$28,459,565 |
| | | 212006 | WRRF Rouge River Outfall (RRO) Disinfection (Alternative) | \$43,788,731 |
| | | 260601 | Oakwood CSO Control Facility Drain Valve Improvements | \$804,574 |
| | | 260609 | Seven Mile RTB - Parking Lot Replacement & Misc. Site Work | \$429,557 |
| | | 260610 | Baby Creek SDF - HV Units Replacement | \$275,151 |
| | | 260611 | Leib SDF- HVAC System Improvements | \$412,590 |
| | | 260616 | Baby Creek Towards Treatment Sewer Improvements | \$770,114 |
| | Closed Total | | | \$74,940,282 |
| | Pending Closeout | 212004 | WRRF Chlorination and Dechlorination Process Equipment Improvements | \$5,642,328 |
| | | 216007 | DTE Primary Electric 3rd Feed Supply to WRRF | \$3,912,283 |
| | | 260505 | Phase 4 Outfalls | \$5,707,478 |
| | | 260509 | B-40 Outfall Rehabilitation | \$83,621 |
| | | 341002 | Security Infrastructure Improvements for Wastewater Facilities | \$1,900,797 |
| | Pending Closeout Total | | | \$17,246,508 |
| SEWER Total | | | | \$92,186,790 |
| Grand Total | | | | \$92,186,790 |

WASTEWATER: PROJECT CHANGES – RECLASSIFIED OR CANCELLED


| DEPT | ProjectStatus | CIPNumber | Title | Sum of Project Totals |
|--------------------|---------------|-----------|--|-----------------------|
| WATER | Cancelled | 351001 | LED Lighting and Lighting Control Improvements | \$6,667 |
| SEWER | Reclassified | 216010 | WRRF Facility Optimization | \$0 |
| | | 274001 | Leib Improvements for Meldrum Diversion | \$0 |
| | | 278001 | Oakwood Improvements for NWI Diversion | \$0 |
| Grand Total | | | | \$6,667 |

| CIP | TITLE | 2022 STATUS | 2023 New Project # |
|--------|--|-------------------------------------|------------------------|
| 216010 | WRRF Facility Optimization | Active - Pre-Procurement - Design | 260901, 260902, 260903 |
| 260208 | Rehabilitation of Conner Creek Sewer Systems | | 260204 |
| 274001 | Leib Improvements for Meldrum Diversion | Future Planned - Within 5 Year Plan | 274004 |
| 278001 | Oakwood Improvements for NWI Diversion | Future Planned - Within 5 Year Plan | 274004 |



RECAP & NEXT STEPS


WATER & WASTEWATER FY23-32 (10-YEAR PROJECTIONS)



| FY 23-27 | |
|----------|---------------|
| Water: | \$977,263,932 |
| WW: | \$761,764,137 |

| FY 28-32 | |
|----------|---------------|
| Water: | \$916,035,555 |
| WW: | \$620,043,920 |

FY23-27 CIP SCHEDULE



DESIRED OUTCOME RECAP

- 💧 Review and discuss FY23-27 CIP summary
- 💧 Familiarize the CIP Committee with the FY23-27 CIP document
- 💧 Identify schedule milestones
- 💧 Next steps

A dynamic splash of clear blue water against a white background, with various droplets and streams of water captured in motion. The water is bright blue and highly reflective.

Wastewater Operations CIP Presentation

*Dan Alford, Director of
Wastewater Engineering and
Maintenance*





Capital Improvement Plan (CIP) Project Updates

- 211006, PS No. 1 Improvements
- 211007, PS #2 Bar Racks Replacements and Grit Collection System Improvements
- 213009, WRRF Biosolids Processing
- 216006, Assessment and Rehabilitation of WRRF Yard Piping and Underground Utilities
- 216008, Rehabilitation of Screen Final Effluent Pump Station
- CS-299
 - 270004, Oakwood and Leib CSO Facility Improvements
 - 270005, CSO Facility Safety and Facility Improvements


CIP Project Update, 211006

(PS No. 1 Improvements)

❑ Project Information

- Type of Project: Design-Bid-Build

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------------------|------------|-----------------|--------------|------------|------------|-----------|----------------|
| •CS-102 | •Wade Trim | •\$4,986,249 | •\$3,411,173 | •68.4% | •5/7/2019 | •5/7/2024 | •48.6% |
| •Future Construction | •TBD | •\$65,250,000 | •\$0 | •0.0% | •10/1/2022 | •3/1/2029 | •0.0% |



CIP Project Update, 211006

(PS No. 1 Improvements)

Risk Driver (Reliability)



Main Lift Pump System failure

EVENT



Wetwell levels increase causing levels within in-system storage interceptors to rise. Rising levels lead to street flooding and complete failure of collection system.




Rehabilitation of facility will improve system reliability. The improved reliability minimizes possible system interruptions and reduces the likelihood of a complete collection system shutdown.

CIP Project Update, 211006


(PS No. 1 Improvements)

Risk Driver (Resiliency)




CIP Project Update, 211006

(PS No. 1 Improvements)



New Discharge Piping



Wetwell Section

(PS No. 1 Improvements, Cont'd)



(PS No. 1 Improvements, Cont'd)




CIP Project Update, 211007

(PS #2 Bar Racks Replacements & Grit Collection System Improvements)

❑ Project Information

- Type of Project: Design-Bid-Build

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------------------|-------------------|-----------------|--------------|------------|-------------|------------|----------------|
| •1904337 | •Hazen and Sawyer | •\$11,307,128 | •\$2,055,375 | •18.2% | •10/20/2020 | •5/19/2027 | •14.8% |
| •Future Construction | •TBD | •\$82,000,000 | •\$0 | •0.0% | •4/1/2023 | •7/2/2029 | •0.0% |




August 2022

CIP Project Update, 211007

(PS #2 Bar Racks Replacements & Grit Collection System Improvements)

Risk Driver (Reliability)



(PS #2 Bar Racks Replacements & Grit Collection System Improvements, Cont'd)



(PS #2 Bar Racks Replacements & Grit Collection System Improvements, Cont'd)




CIP Project Update, 213009

(WRRF Biosolids Processing)

❑ Project Information

- Type of Project: Study-Design-Bid-Build

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------------------|------------|-----------------|--------------|------------|-----------|-----------|----------------|
| •Future Design | •TBD | •\$20,000,000 | •\$0 | •0.0% | •2/1/2026 | •2/1/2031 | •0.0% |
| •Future Construction | •TBD | •\$160,000,000 | •\$0 | •0.0% | •1/1/2031 | •1/1/2040 | •0.0% |



CIP Project Update, 213009


(WRRF Biosolids Processing)

Risk Driver (Reliability)




CIP Project Update, 213009

(WRRF Biosolids Processing)



THP + Mesophilic Digestion + Drying



Simple Schematic of Solids Handling

CIP Project Update, 213009

(WRRF Biosolids Processing)



CIP Project Update, 213009

(WRRF Biosolids Processing)




CIP Project Update, 216006

(Assessment and Rehab of WRRF Yard Piping and Underground Utilities)

❑ Project Information

- Type of Project: Construction Management-At-Risk


| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------|-------------------|-----------------|--------------|------------|-------------|------------|----------------|
| •1903601 | •CDM Smith | •\$1,647,815 | •\$534,305 | •36.0% | •12/28/2020 | •2/27/2023 | •36.4% |
| •1903598 | •Chrisman Company | •\$4,863,051 | •\$493,444 | •34.0% | •1/15/2021 | •3/17/2023 | •34.1% |



CIP Project Update, 216006

(Assessment and Rehab of WRRF Yard Piping and Underground Utilities)

Risk Driver (Reliability)



CIP Project Update, 216006

(Assessment and Rehab of WRRF Yard Piping and Underground Utilities)




CIP Project Update, 216008

(Rehabilitation of Screened Final Effluent (SFE) Pump Station)

❑ Project Information

- Type of Project: Progressive Design-Build


| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------|------------|-----------------|---------------|------------|-----------|------------|----------------|
| •2000970 | •Noresco | •\$3,399,730.00 | •\$574,185.30 | •16.8% | •4/5/2021 | •2/20/2024 | •5.7% |



CIP Project Update, 216008


(Rehabilitation of Screened Final Effluent (SFE) Pump Station)

Risk Driver (Resiliency)



CIP Project Update, 216008

(Rehabilitation of Screened Final Effluent (SFE) Pump Station)



Preliminary Conceptual SFE Pump Station and Auxiliary Buildings Site Plan

| Use | Typ No. of Units In Service | Firm No. of Units In Service | Total No. of Units | Flow Per Unit | | Typical SFE Usage | Firm SFE Usage | Source of Flow Information |
|--|-----------------------------|------------------------------|--------------------|---------------|------|-------------------|----------------|---|
| | | | | gpm | MGD | | | |
| C-II Incineration Scrubber Water | 4 | 7 | 8 | 2120 | 3.1 | 12.2 | 21.4 | Scrubber manufacturer P&ID; review of SCADA |
| C-II Incineration Strainer Backwash | -- | -- | -- | -- | -- | 0.6 | 1.1 | 5% of C-II Incineration Scrubber Water |
| Complex A Thickener Make-Up Water | 4 | 6 | 6 | 500 | 0.7 | 2.9 | 4.3 | Site observation and O&M staff input |
| Complex B Thickener Make-Up Water | 4 | 6 | 6 | 500 | 0.7 | 2.9 | 4.3 | Site observation and O&M staff input |
| Biosolids Drying Facility Scrubber Water | 3 | 3.25 | 4 | 600 | 0.9 | 2.6 | 2.8 | 90 percentile of flow rate for each train from SCADA data |
| C-I BFP Washwater | 0 | 8 | 10 | 100 | 0.1 | 0.0 | 1.2 | From BFP manufacturer specs |
| C-I BFP Conveyor Washwater | 0 | 1 | 1 | 50 | 0.1 | 0.0 | 0.1 | Estimate of usage |
| C-II BFP (Upper Level) Washwater | 6 | 10 | 12 | 100 | 0.1 | 0.9 | 1.4 | From BFP manufacturer specs |
| C-II (Dewater & Incin) Conveyor Washdown | 4 | 6 | 6 | 50 | 0.07 | 0.3 | 0.4 | Estimate of usage |
| C-II BFP (Upper Level) Strainer Backwash | -- | -- | -- | -- | -- | 0.04 | 0.07 | 5% of C-II Dewatering Washwater |
| RRO Hypo Carrier Water | 0 | 1 | 1 | 700 | 1.0 | 0.0 | 1.0 | Maximum observed flow for RRO carrier water from SCADA data |
| RRO Bisulfite Carrier Water | 0 | 1 | 1 | 700 | 1.0 | 0.0 | 1.0 | Maximum observed flow for RRO carrier water from SCADA data |
| SFE Pump Station Strainer Backwash | -- | -- | -- | -- | -- | 1.0 | 2.0 | 5% of Current Use Flow |
| Subtotal of Current Uses | | | | | | 23.4 | 41.1 | |
| Future Uses | | | | | | | | |
| Chlor & Dechlor Carrier Water | | | | | | | 0.0 | To be pumped by separate system |
| Replacement of Secondary Water | | | | | | | 0.0 | To be pumped by separate system |
| PS-2 Screenings Sluice Water | 2 | 2 | 2 | 400 | 0.6 | 1.2 | 1.2 | 400 gpm maximum per sluice trough |
| Subtotal of Future Uses | | | | | | | 1.2 | |
| Safety Factor | | | | | | | 4.1 | 10% of firm capacity |
| Total | | | | | | | 46.4 | |

CIP Project Update, 216008

(Rehabilitation of Screened Final Effluent (SFE) Pump Station)



CS-299 Facilities Assessment

Schedule: July 2019 – Present (completes end of 2021)

Scope: Assess all nine CSO Facilities

- Multi-disciplinary facilities and equipment assessment
- O&M and condition assessment

Deliverables:

Updated Scheduled Replacement Plan to inform Capital Outlay (I&E) (repair programs)

- Informed CIP Plan based on facility, operational, and regulatory needs
- Asset audit, FMEAs, risk assessment of assets, GIS, 3-D scanning, etc.
- Quick win deliverables – to address most critical items found right away.
 - Baby Creek roof replacement (260620), Generator improvements (260623)

2023 – 2027 CIP Update includes CS-299 Projects

- 270004 – Oakwood and Leib CSO Facility Improvements
- 270005 – CSO Facility Safety and Building Improvements
- 270006 – Baby Creek and Belle Isle Instrumentation / Controls Improvements
- 270007 – Disinfection System Improvements @ Baby Creek, Belle Isle, Conner Creek, and Puritan Fenkell
- 270008 – Flushing System Improvements at Conner Creek & St. Aubin
- 270009 – Site Improvements at St. Aubin, Belle Isle, and Baby Creek CSO Facilities
- 270010 – HVAC Improvements at Puritan Fenkell & Seven Mile
- 270011 – HVAC Improvements @ Conner Creek and Belle Isle Facilities
- 270012 – Conner Creek, Oakwood and Puritan Fenkell Instrumentation / Controls Improvements
- Others added to CIP: 270013, 270014, 273001, 273002, 277002



Jacobs

CS-299 CSO Facilities Assessment
Volume 2 – Multi-Disciplinary Facilities Assessment




CIP Project Update, 270004

(Oakwood & Leib CSO Facility Improvements)

❑ Project Information

- Type of Project: Design-Bid-Build

| Contract | Contractor | Contract Estimates | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------------------|------------|--------------------|--------------|------------|------------|------------|----------------|
| •Future Design | •TBD | •\$4,830,000 | •\$0 | •0.0% | •6/15/2022 | •5/1/2025 | •0.0% |
| •Future Construction | •TBD | •\$10,300,000 | •\$0 | •0.0% | •2/18/2026 | •9/11/2030 | •0.0% |



CIP Project Update, 270004

(Oakwood & Leib CSO Facility Improvements)

Risk Driver (Reliability)



Oakwood Pump System
Failure or Leib Screen
System Failure

EVENT



Present

Facility HGL levels increase causing levels within the collection system to rise. Rising levels lead to street flooding and complete failure of collection system.





Future

Rehabilitation of the pumps, screens, and various processes at each facility will improve system reliability. The improved reliability minimizes possible system interruptions and reduces the likelihood of high system HGL due to the future diversion projects for the NWI Diversion to Oakwood and the Meldrum Diversion to Leib.

CIP Project Update, 270004

(Oakwood & Leib CSO Facility Improvements)



CIP Project Update, 270004

(Oakwood & Leib CSO Facility Improvements)



CIP Project Update, 270005

(CSO Facility Safety & Facility Improvements)

❑ Project Information

- Type of Project: Design-Bid-Build

| Contract | Contractor | Contract Estimates | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------------------|------------|--------------------|--------------|------------|-------------|------------|----------------|
| •Future Design | •TBD | •\$1300,000 | •\$0 | •0.0% | •12/15/2022 | •2/15/2025 | •0.0% |
| •Future Construction | •TBD | •\$5,185,000 | •\$0 | •0.0% | •12/18/2025 | •2/19/2028 | •0.0% |



December 2022

CIP Project Update, 270005

(CSO Facility Safety & Facility Improvements)

Driver (GLWA Team Member Safety)



Open hatch or utilize ladder

EVENT



Operator opens heavy hatches, potentially loses balance and falls in. Or operator utilizes facility ladders with no fall-arrest mechanisms and if they fall they fall the whole way down.



Opening heavy hatches and losing your balance means you fall onto a lighter net or walkable grating below the hatch and avoid injury or death. The grating or netting is much easier to open safely than a heavy hatch. Utilizing a ladder with fall-arrest mechanisms will have a braking system and during a fall will not allow the operator to fall the entire distance, preventing serious injury or death.

CIP Project Update, 270005

(CSO Facility Safety & Facility Improvements)



A dynamic splash of clear blue water against a white background, with various droplets and streams of water captured in motion. The water is bright blue and highly reflective.

Water Supply Operations Highlighted CIP Projects

Grant Gartrell

Director of Water Engineering





**1803312 West Service Center
Reservoirs, Reservoir Pump
House & Division Valve
Replacement**

Project Manager: Andrew Juergens

*Design-Build: Kokosing Industrial
Inc. and Arcadis*



Project Description

The existing reservoirs at the West Service Center were constructed in the early 1960's and are past their intended service life. The existing reservoirs are in poor condition and continue to require periodic repairs despite numerous past repairs. Additionally, half of the existing reservoir pumps experience suction hydraulic issues when the reservoir level falls below half full.

Additionally, construction of new of West Service Center Division Valves is needed to convey flows originating from the Lake Huron Water Treatment Plant through the West Service Center to the Springwells high-pressure service area while the Springwells raw water tunnel is out of service for repairs.



Project Team

GLWA Team:

Director of Engineering: Grant Gartrell, P.E.

Project Manager: Andrew Juergens



Design-Build Team:

Design-Build Project Manager: Jim Miller, Kokosing

Deputy Project Manager: Bob Gittinger, Kokosing

Project Superintendent: Adam Kolwicz, Kokosing

Design Manager: Tim Harmsen PE, Arcadis

Kokosing = Kokosing Industrial, Inc.

Project Cost and Timeline

Cost:

Total Contract Amount= \$44,900,000

Total Billed to Date= \$11,773,385.85

Total Amount % Complete= 26%

Time:

Contract Start Date: March 15, 2020

Substantial Completion Date: March 14, 2024

Final Completion Date: July 12, 2024



Existing Conditions Prior to Project Start

Existing Reservoir No. 1 East Exterior Wall



Existing Reservoir Condition – Exterior




Existing Conditions Prior to Project Start

Existing Reservoir Pump Houses No. 1 and No. 2



Ponding between Pump House No. 1 and Reservoir No. 1



Existing Conditions Prior to Project Start

Existing Valve Well No. 3



Existing Valve Well No. 1



April 2021

Excavation Underway for New Reservoir Pump House



Sheet Piling Installed at Valve Well No. 3



May 2021

New Reservoir Pump House Base Slab Progress



Valve Well No. 3 Excavation Complete



June 2021

New Reservoir Pump House Progress



Valve Well No. 3 Demolition Progress



July 2021

New Reservoir Pump House Progress



Valve Well No. 3 Formwork Installation



August 2021

*New Reservoir Pump House –
Pump Suction Piping Installed*



*New Reservoir Pump House – Fill
Valve Slab Forms and
Reinforcement*



A dynamic splash of clear blue water against a white background, with various droplets and streams of water captured in motion. The water is bright blue and highly reflective.

1803538 – Ford Road Station Control and Isolation Valve Improvements

Project Manager: Eric Kramp

Contractor: Weiss Construction Company

Engineer: A. Benesch and Co.



Project Description

Contract No. 1803835 addresses two primary concerns at the Ford Road Station, including (1) pump suction isolation valves failed to isolate, and (2) discharge pressure control valves were not readily controllable. All pump suction isolation and control valves, and the reservoir fill system in the Ford Road Station Building have been replaced with much more reliable equipment. The hydraulically-controlled valves were replaced with electrically-operated valves. A new backup generator was installed to close control valves during a power failure.



Project Team

GLWA Team:

Director of Engineering: Grant Gartrell, P.E.

Project Manager: Eric Kramp



Contractor Team:

Project Manager: Rick Tagliaferri

Project Engineer: Jack Weiss

Project Superintendent: Dan Baranyai

Safety Manager: Keven Clarey

Weiss Construction Company

Project Cost and Timeline

Cost:

Total Contract Amount= \$2,650,866

Total Billed to Date= \$2,575,677

Total Amount % Complete= 97%

Time:

Contract Start Date: July 13,2019

Substantial Completion Date: August 24, 2020

Final Completion Date: October 3, 2021



Line Pump Isolation Valves

Original Isolation Butterfly Valves



New Triple Offset Butterfly Valves (TOBV)



Line Pump Isolation Valves

Original Isolation Butterfly Valves



New TOBV Isolation Valves



Reservoir Pump Isolation Valves

Original Isolation Butterfly Valves



New TOBV Isolation Valves



Reservoir Fill System

Existing Elevated Reservoir Fill System



New Reservoir Fill System



New Sleeve Valve



Pump Control Valves

Original Control Butterfly Valves and Hydraulic Control Panels



New Control Ball Valve and Electric Control Panel



Pump Control Valves

Original Hydraulic Control Panels



New Control Panel Interior



A dynamic splash of clear blue water against a white background, with various droplets and streams of water captured in motion. The water is bright blue and highly reflective.

Highlighted Field Services and Systems Control Projects

Todd King, P.E., BCEE

Director of Field Services



Highlighted SCC and Field Projects

DB-226 Detroit River Intercept Rehab – CIP 222002

*DB-150 Springwell, Northeast and Pennsylvania Raw Water Tunnel
Rehab – CIP 116002*

CS-120 Conner and Freud Pump Station Design – CIP 232002





GLWA
Great Lakes Water Authority

**Contract DB 226:
Rehabilitation of
Detroit River
Interceptor**

Project Manager

Mini Panicker



CIP 222002 Related Contracts

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------|------------|-----------------|--------------|------------|---------|---------|----------------|
| DB-226 | Jay Dee | \$47,993,835 | \$33,790,547 | 70% | 5/24/18 | 5/24/23 | 70% |


- Currently, negotiating GMP for Reach 3 – Approximately \$30 million and two-year extension
- Total cost expected to be \$80 million +/- in alignment with FY22-26 CIP

Detroit River Interceptor (DRI)


- 13 miles long from Alter Rd. to WRRF
- Interceptor ranges from 8 ft near Alter Rd to 16 ft at WRRF
- DRI was constructed in parallel to the Detroit River



CONNOR CREEK ACCESS STRUCTURE CONSTRUCTION




SEWER REPAIRS



NIEA “GRAND CONNECTOR” TUNNEL DETAILS

- TBM excavation of 980 linear feet
- 9'-2" Internal Diameter Hobas Pipe grouted in tunnel with 12 ft Diameter rib and lagging tunnel liner between Fort St. and Jefferson
- Hand mine Tunnel excavation from North structure to NIEA about 80 ft under Fort Street
- TBM Launch Shaft at W. Grand Blvd East of Fort St
- TBM Retrieval Shaft and DRI gate shaft at W. Grand Blvd and Jefferson



NIEA “GRAND CONNECTOR” STATUS



- North Shaft excavation started 8-10-2020
- North Shaft Concrete mud mat was placed on 9-3-2020
- Structures and Gates completed summer 2021



GLWA
Great Lakes Water Authority

**Contract DB 150:
Rehab/Repair of Raw
Water Tunnels for
Northeast,
Springwells, and
Pennsylvania Tunnels**

Project Manager

Todd King, Nick Hoffman




CIP 116002 Related Contracts

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------|------------|-----------------|--------------|------------|---------|---------|----------------|
| DB-150 | Ballard | \$94,577,477 | \$30,791,013 | 33% | 1/29/18 | 3/28/25 | 45% |


- Pennsylvania Tunnel Repairs – complete
- Northeast Tunnel Repairs – access shaft – complete
- Springwells Tunnel Repairs – utility relocations - complete
- Total costs expected to be \$95 million +/- in alignment with FY22-26 CIP

Conner Creek PS



Storm Wet Well
Floor – El. 55

Freud PS



Storm Wet Well
Floor – El. 20

**Contract CS-120:
Freud and Conner
Pump Station
Rehabilitation and
Replacement**

Project Manager

Mini Panicker

CIP 232002 Related Contracts

| Contract | Contractor | Contract Amount | Earned Value | % Complete | Start | End | % Elapsed Time |
|----------|------------|-----------------|--------------|------------|----------|-----------|----------------|
| CS-120 | Arcadis | \$24,410,947 | \$4,871,686 | 20% | May 2017 | July 2028 | 41% |

- Property acquisition – Freud and Conner - underway
- Design of Freud Sanitary Pump Station – to be completed 1Q22
- Design of Conner Creek Pump Station replacement - underway
- Total costs expected to be \$248 million +/-
 - \$18 million – study/design/construction assistance
 - \$72 million –construction – Freud
 - \$158 million – construction - Conner

| Stage | Freud | Conner |
|--------------------|-------|--------|
| Design complete | 1Q22 | 4Q23 |
| Construction start | 1Q23 | 4Q24 |
| Complete | 3Q26 | 4Q29 |



CLOSING REMARKS



GLWA
Great Lakes Water Authority

Questions?



GLWA

Great Lakes Water Authority

Have a Great Day!