



Procurement Form (FOR)

Effective Date: 5/1/2019	Document #: FSA_PRO_FOR_0033	Revision Date: N/A	Revision#: 0
------------------------------------	--	------------------------------	------------------------

Document Title: Cost Tabulation/Notice of Respondents	Document Owner/Department: Procurement Team
---	---

Contract No./Title: 2201101 Incinerator 11 Rehabilitation
Date: 12/8/2022

2201101 - Incinerator 11 Rehabilitation - Bid Tab	Commercial Contracting Corporation		F.H. Paschen		Hankin Environmental Systems, Inc		
	Quantity Required	Unit Price	Total Cost	Unit Price	Total Cost	Unit Price	Total Cost
Task 1 - Emergency Bypass Damper Replacement (1)							
Emergency Bypass Damper Replacement, including bypass stack modifications shown on the drawings and as specified. The lumpsum price to include: demolition; and new work, including startup. Also see Item 2h.	1	\$ 812,150.0	\$ 812,150.0	\$ 800,966.0	\$ 800,966.0	\$ 938,520.0	\$ 938,520.0
Task 2 - Internal Refractory and Other Improvements (8)							
Item 2a: In-Hearth Replacement as shown on the drawings and as specified. The unit price to include: demolition; new hearth construction using existing skewbacks	2	\$ 82,000.0	\$ 164,000.0	\$ 120,000.0	\$ 240,000.0	\$ 181,090.0	\$ 362,180.0
Item 2b: Out-Hearth Replacement as shown on the drawings and as specified. The unit price to include: demolition; new hearth construction using existing skewbacks	1	\$ 75,000.0	\$ 75,000.0	\$ 112,000.0	\$ 112,000.0	\$ 210,060.0	\$ 210,060.0
Item 2c: Sidewall Replacement as shown on the drawings and as specified. The unit price to include, demolition; new sidewall consisting of new refractory wall and insulation. Use existing skewbacks	13	\$ 1,200.0	\$ 15,600.0	\$ 1,700.0	\$ 22,100.0	\$ 2,840.0	\$ 36,920.0
Item 2d: Sidewall Replacement with new skewbacks as shown on the drawings and as specified. The unit price to include: demolition; new skewbacks, new sidewall consisting of new refractory wall and insulation	22	\$ 1,500.0	\$ 33,000.0	\$ 1,900.0	\$ 41,800.0	\$ 2,250.0	\$ 49,500.0
Item 2e: Rabble Arm Insulation as shown on the drawings and as specified. The unit price to include: demolition; new insulation consisting of new anchors and castable insulation. Match existing thickness for insulation. For estimation, use 3" thick average.	60	\$ 700	\$ 42,000.0	\$ 785	\$ 47,100.0	\$ 2,330.0	\$ 139,800.0
Item 2f: Work door Repair as shown on the drawings and as specified. The unit price to include: demolition; and new insulation consisting of castable insulation. Match existing thickness for insulation.	4	\$ 1,200.0	\$ 4,800.0	\$ 1,200.0	\$ 4,800.0	\$ 8,950.0	\$ 35,800.0
Item 2g: All remaining repair work as shown on the drawings and as specified. The lumpsum price to include: demolition; and new work. Match existing.	1	\$ 26,000.0	\$ 26,000.0	\$ 72,000.0	\$ 72,000.0	\$ 84,460.0	\$ 84,460.0
Item 2h: Startup, Dryout and Warmup as specified. This item to be coordinated with the dryout of refractory work under Item 1. It is assumed the entire dryout will take place at once for all 4 tasks.	1	\$ 82,000.0	\$ 82,000.0	\$ 81,600.0	\$ 81,600.0	\$ 29,950.0	\$ 29,950.0
Task 3 - Hearth 1 and 2 Sludge Feed Drop Hole Enlargement (1)							
Item 3: Hearth 1 and 2 Sludge Feed Drop Hole Enlargement as shown on the drawings and as specified. The lumpsum price to include: demolition; and new dropholes	1	\$ 120,000.0	\$ 120,000.0	\$ 182,600.0	\$ 182,600.0	\$ 72,690.0	\$ 72,690.0
Task 4 - Breech Modifications (1)							
Item 4: Breech Modifications as shown on the drawings and as specified. The lumpsum price to include: demolition; and new work	1	\$ 206,000.0	\$ 206,000.0	\$ 275,000.0	\$ 275,000.0	\$ 314,860.0	\$ 314,860.0
Miscellaneous (4)							
Item 5: Mobilization/Demobilization of entire work	1	\$ 110,000.0	\$ 110,000.0	\$ 120,000.0	\$ 120,000.0	\$ 115,890.0	\$ 115,890.0
Item 6: Photographic Documentation per Specification Section 01 32 33.	1	\$ 45,000.0	\$ 45,000.0	\$ 21,000.0	\$ 21,000.0	\$ 34,290.0	\$ 34,290.0
Item 7: Subcontractor Work markup, Overhead and Profit, and any other items not listed above. Note: this item shall include up to 200 digital photographs taken by handheld devices copied to a USB drive. This item shall not include Photographic Documentation per Specification Section 01 32 33, which shall be a separate Bid item as noted above.	1	\$ 550,450.0	\$ 550,450.0	\$ 323,017.0	\$ 323,017.0	\$ 273,830.0	\$ 273,830.0
Item 8: Project Allowance	1	\$ 200,000.0	\$ 200,000.0	\$ 200,000.0	\$ 200,000.0	\$ 200,000.0	\$ 200,000.0
Total Bid Price			\$2,486,000.00		\$2,543,983.00		\$2,898,750.00

Approved: Gladys Cannon 12/8/22