



GLWA FY 2020 – 2024 Capital Improvement Plan and 10-Year Outlook

*GLWA CIP Committee Meeting
October 29, 2018
3:00 p.m. – 5:00 p.m.*



Agenda


- **Where We've Been & What We're Trying To Accomplish** – Jody Caldwell
- **Overall 2020-2024 CIP** – Jody Caldwell
 - Significant Project Changes
 - Project Priorities & Risk
 - High Level Water Summary
 - High Level Wastewater Summary
- **Highlighted Water CIP Projects** – Grant Gartrell / Tim Kuhns / Erich Klun
- **Highlighted Wastewater CIP Projects** – Ali Khraizat / Dan Alford / Todd King / Biren Saparia / Chris Nastally
- **CIP Schedule & Closing Remarks** – Jody Caldwell
 - CIP Roll-out Schedule
 - Questions & Answers




Where We've Been and What We're Trying To Accomplish




2018-2022 Capital Improvement Plan Modifications



Report
Format



One-page
Summaries



Excel table

CIP Project ID	Project Title	Contract No.	Year Added	Status	Project Category 1	Project Category 2	Project Category 3	Project Type
382	Southwest Water Treatment Plant, Sludge Treatment & Waste Wastewater Treatment Facilities	SW-548		Pending Close-out	Water	Treatment Plants & Facilities	Southwest	Project
917	Springwells Water Treatment Plant - 1958 Filter Rehabilitation and Auxiliary Facilities Improvements	SP-563	2002	Active	Water	Treatment Plants & Facilities	Springwells	Project
917	Springwells Water Treatment Plant 1958 Filter Rehabilitation and Auxiliary Facilities	CS-1425	2002	Active	Water	Treatment Plants & Facilities	Springwells	Project
	Implementation Assistance and General Engineering Services on (1)	CS-1433	2002	Active	Water	General Purpose	NA	Allowance
		CS-1499	2004	Active	Water	General Purpose	NA	Allowance
	ng Services (1)	CS-1432A	2004	Active	Water	General Purpose	NA	Allowance
	Rehabilitation	DW-828		Pending Close-out	Water	SCC	Pump Station Rehabilitation	Project
	Treatment Plant - Low Lift and Pump	NA	2004	New	Water	Treatment Plants & Facilities	Springwells	Project
	in 34 Mile Road from to Romeo Plank Road	WS-681	2005	Pending Close-out	Water	Field Services	Transmission System	Project
	Testing Services for Concrete and Soil Borings, other Testing and Services (1)	CS-1185	2006	Active	Water	General Purpose	NA	Allowance


2019-2023 Capital Improvement Plan Modifications



Refinement
of Project
Schedules &
Expenditures

11	
Dates	
er	
re Planned Start	

Risk Matrix &
Cost
Estimation



Database

2019 CIP

LH WTP Low and High Lift Pumping, and Filter Backwash Pumps Improvements

oring Project Changes

Project Documents

Project Phases

High Lift Pumping, and Filter Backwash Pumps Improvements

Project Status

Future Planned

Category No. 111

CIP Type

Project

CIP Budget

Water

Project Class Level 1

Water

Project Class Level 2

Treatment Plants and Facilities

Project Class Level 3

Lake Huron

Fund and Cost Center

Water - 5519-882111

Project Jurisdiction

Saint Clair County

Lookup Location

Lake Huron WTP

FY22

FY23

FY24

FY25 and Beyond

Total

3,169

4,450

10,000

32,757

52,388

2020-2024 Capital Improvement Plan Modifications




WATER					
All Figures are in \$1,000's					
FY 19	FY 20	FY 21	FY 22	FY 23	FY 24
66,038	137,583	155,734	178,300	175,174	N/A
68,746	143,247	166,599	182,595	169,006	190,866
2,708	5,664	10,865	4,295	-6,168	
4.4%	4.1%	7.0%	2.4%	-3.5%	

WASTEWATER				
All Figures are in \$1,000's				
FY 20	FY 21	FY 22	FY 23	FY 24
111,155	111,952	136,411	168,458	N/A
139,480	107,430	139,677	156,884	130,159
28,325	-4,522	3,266	-11,574	
25.5%	-4.0%	2.4%	-6.9%	

Refinement of projects with sharp financial focus

Water & Wastewater 10-Year Outlook



More Efficient & Functional Database

GLWA FY 2020-2024 CIP

Find

2019 CIP

Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements

at Scoring Project Changes Project Documents Project Phases

RED INTO THIS PROJECT. Improvements needed to align the existing low lift pumping rate with the Lake Huron rate per the 2015 WMF. Currently, constant speed pumping forces the WTP to operate in a batch electrical gear for low and high lift pumping units and filter backwash pumps are original to plant, beyond and need to be replaced to improve reliability, serviceability, maintainability, and efficiency. phosphoric acid chemical storage tanks and fill piping. Flocculation moved to new project proposed CIP rehabilitation and flocculators.

nt speed pumping forces the Lake Huron WTP to
 • lift pump capacities exceed
 vements needed to align the
 • Lake Huron WTP production
 th new:

ping unit and motor required
 is may show pump
 if reduced speeds. Uncovering
 to minimize maintenance of

Project History

Other Important Info *Innovation note: Ensure energy
 Updated project expenses to
 moved contract start back on
 costs. Portions of project were
 Master Plan.

Related Project

	FY22	FY23	FY24	FY25 and Beyond	Total
1,611	3,169	4,450	10,000	32,757	52,388

What We're Trying To Accomplish

- Increased redundancy, reliability & resiliency of water and wastewater systems
- Adherence with long-term planning document recommendations
- Provide opportunity for Board, Authority Members and stakeholders to provide input
- Best-in-class planning and execution of capital program
- Sharp financial focus in coordination with Financial Services Area.



Overall 2020-2024 CIP

Jody Caldwell



Significant Project Changes



New Projects – 8 Water & 1 Wastewater

2020-2024 CIP New Water & Wastewater Projects

(all figures in \$1,000's)

CIP#	Title	FY19	FY20	FY21	FY22	FY23	FY24	FY25+	Total	Overall Total
111009	Lake Huron Water Treatment Plant, Two New High-Lift Pumps, Water Production Flow Meter, and Select Yard Piping Improvements	16	9,030	10,030	7,030	-	-	-	26,106	63,898
112005	Northeast Water Treatment Plant - Replacement of Covers for Process Water Conduits	-	166	647	-	-	-	-	813	
112006	Northeast Water Treatment Plant Flocculator Replacements	3	1,356	1,356	3	-	-	-	2,718	
114016	Springwells Water Treatment Plant 1958 Settled Water Conduits Concrete Pavement Replacement	-	206	656	-	-	-	-	862	
114017	Springwells Water Treatment Plant Flocculator Drive Replacement	-	-	-	10	2,314	4	-	2,328	
115005	Waterworks Park Water Treatment Plant Building Ventilation Improvements	7	507	3,907	650	-	-	-	5,071	
122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow Control Station	-	1,040	6,050	6,910	3,750	2,750	-	20,500	
132025	Northwest Booster Station Yard Piping Improvements	-	-	50	1,700	3,750	-	-	5,500	
216008	Rehabilitation of Screened Final Effluent (SFE) Pump Station	51	1,091	991	9,475	7,805	5,535	-	24,948	*NA

*NA = This project was included in the FY2019-2023 CIP under CIP 216006.

Projects With Significant Year-To-Year Adjustments – WATER Summary

CIP#	Project Status	Title	Total Difference Between 2019 and 2020 CIP	Reasoning
111006*	Active	Lake Huron Water Treatment Plant, Filter Instrumentation and Raw Water Flow Metering Improvements	(15,527)	Removed the raw water flow meter from this CIP and have included it in a new CIP #
114002*	Active	Springwells Water Treatment Plant, Low-Lift and High-Lift Pumping Station Improvements	29,313	Added the replacement of 3 primary transformers, replacement of six (6) 84" gate valves, increased cost of the electrical switchgear and exterior windows.
114011*	Active	Springwells Water Treatment Plant Steam, Condensate Return, and Compressed Air Piping Improvements	13,368	Actual construction bids were all greater than the estimated costs and therefore budget. The construction bids received were all similar.
115001*	Active	Water Works Park Water Treatment Plant Yard Piping, Valves and Venturi Meters Replacement	(17,471)	The revised CIP budgeted amount is based on the most recent detailed cost estimate.
122006	Active	Wick Road Water Transmission Main Construction	7,496	Last year's budgeted CIP amount was based on a conceptual cost estimate developed several years ago. This year's estimate is based on a near 100% complete design and should better represent actual bids to be submitted.
170800	Active	System-Wide Finished Water Reservoir Inspection, Design and Rehabilitation	44,749	All previous reservoir inspection, design & rehabilitation projects have been reclassified into this program.

Projects With Significant Year-To-Year Adjustments – WASTEWATER Summary

CIP#	Project Status	Title	Total Difference Between 2019 and 2020 CIP	Reasoning
216006*	Future Planned	Assessment and Rehabilitation of WRRF yard piping and underground utilities	(29,603)	New Project 216008, Rehabilitation of Screened Final Effluent Pump Station, was previously included in this project. To improve project effectiveness, the project has been split into two.
222004	Future Planned	Collection System Infrastructure Improvements (Excluding Interceptors)	84,659	Projects 222005 and 233002 have been reclassified into this project. In addition, this project expenses have been extended into the later years of the 5-year plan. The majority of the projected expenses occur in year 2025+.
222007	Cancelled	NIEA Rehabilitation from WRRF to Gratiot Ave. and Sylvester St.	(21,003)	Based upon the completion of the condition assessment along this reach, no major rehabilitation is required during this timeframe and therefore the project has been canceled.
232002*	Active	Freud & Conner Creek Pump Station Improvements	129,948	Basis of design and life cycle costs dictate the necessity of a complete rebuild of Conner Creek and major upgrades to Freud.
260200*	Active	Sewer and Interceptor Rehabilitation Program	114,415	These project expenses have been extended into the later years of the 5-year plan. The majority of the projected expenses occur in year 2025+.
260300	Active	Scheduled Replacement Program of Critical Assets	(9,243)	This legacy program is now either being addressed in individual projects or being addressed through Capital Outlay.
260500*	Active	CSO Outfall Rehabilitation	44,851	Projects 222006 and 233001 have been reclassified into this project.
260600	Active	CSO FACILITIES IMPROVEMENT PROGRAM	18,370	These program expenses have been extended another year into the future causing the majority of the increase.

*Project will be discussed in greater detail.

Project Changes – Pending Closeout or Closed

CIP #	Title	2019 Status	2020 Status
116003	Genesee and Lapeer County Transmission System Improvements	Active	Pending Closeout
122010	Water Main Replacement within the City of Detroit - Joy Rd from Greenfield to Schaefer and Davison Ave from Lindwood to Livernois	Active	Pending Closeout
132004	North Service Center PS - Hydraulic Surge Control	Active	Pending Closeout
380500	Wastewater General Engineering Services on an As-needed Basis	Active	Pending Closeout
380900	General Engineering Services	Active	Pending Closeout
212001	WRRF Returned Activated Sludge (RAS) Pumps, Influent Mixed Liquor System and Motor Control Centers (MCC) Improvements for Secondary Clarifiers	Pending Closeout	Closed
212002	WRRF Study, Design, & Construction Management Services for Modified Detroit River Outfall No. 2	Pending Closeout	Closed
212005	WRRF Rouge River Outfall No. 2 (RRO-2) Segment 1	Pending Closeout	Closed
213003	WRRF Sewage Sludge Incinerator Air Quality Improvements	Pending Closeout	Closed

Project Changes – Reclassified or Canceled

CIP #	Title	2019 Status	2020 Status
112001	Phase 1 WWP to NE Transmission - Flow Control Station at NE WTP	Future Planned	Reclassified into 122003
113005	SW WTP Residuals Management	New	Reclassified - Capital Outlay
132024	Reservoir Inspection, Design and Rehabilitation @ Adams, East-side, Farmington, Ford Road, Franklin, Haggerty and Joy Road	New	Reclassified into Program 170800
211003	WRRF Rehabilitation of Primary Clarifiers	Active	Reclassified into 211001
222005	Collection System Access Hatch Improvements	Active	Reclassified into 222004
233002	Collection System In System Storage Devices (ISDs) Improvement	Future Planned	Reclassified into 222004
251002	Wastewater System-Wide Instrumentation & Control Software and Hardware Upgrade	Future Planned	Reclassified - Capital Outlay
260400	Sewage Meter Design, Installation, Replacement and Rehabilitation Program	Active	Reclassified - Capital Outlay
222007	NIEA Rehabilitation from WRRF to Gratiot Ave. and Sylvester St.	Future Planned	Canceled

Project Priorities & Risk



Project Prioritization – Water


Rank	CIP No.	Title		0	20	40	60	80	100
1	115005	Emergency WWP WTP Building Ventilation Improvements	115005						
2	111001	LH WTP Low and High Lift Pumping, and Filter Backwash Pumps...	111001						
3	113003	SW WTP Low & High Lift Pumping & Rapid Mix Chamber BFVs, ...	113003						
4	112006	NE WTP Flocculator Replacement	112006						
5	114007	SPW WTP Powdered Activated Carbon System Improvements	114007						
6	132025	Northwest Booster Station Yard Piping Improvements	132025						
7	111009	LH-WTP Two 35-MGD High Lift Pumps, Water Production Flow...	111009						
8	114010	SPW WTP Yard Piping and High Lift Header Improvements	114010						
9	132012	Ypsilanti PS Improvements	132012						
10	112005	NE Steel Cover Replacement	112005						
11	331001	Roofing Systems Replacement at Water Plants and BPS	331001						
12	122013	14 Mile Transmission Main Loop	122013						
13	122016	Downriver Transmission Main Loop	122016						
14	132016	North Service Center BPS Improvements	132016						
15	132021	Imlay BPS - Replace VFDs, Pumps, Motors and HVAC	132021						
16	132017	North Service Center BPS - On-Site & Off-Site Yard Piping & Valve...	132017						
17	122007	Newburgh Road Transmission Main	122007						
18	132014	Adams Road Pumping Booster Pumping & Switch Gear Improvements	132014						
19	132015	Newburgh BPS - Pumping System & Building Upgrades	132015						
20	132018	Schoolcraft BPS - Pumps, Yard Piping, Valves & Reservoir Pumps & ...	132018						
21	132019	Wick Road BPS - Switchgear, Control Valves & Hydropneumatic Tank...	132019						
22	132020	Franklin BPS - Isolation Gate Valves & Electrical Actuator...	132020						
23	132022	Joy Road BPS - Replace Reservoir Pumps, Motors and Isolation Valves	132022						
24	132013	Adams Road Pumping Booster VFD & Gate Valves to Optimize...	132013						
25	132010	West Service Center PS - Reservoir, Reservoir Pumping, and Division...	132010						
26	112003	NE WTP High-Lift Pumping Station Electrical Improvements	112003						
27	114017	SPW WTP Flocculator Drive Replacement	114017						
28	113006	SW WTP Chlorine Scrubber, Raw Water Screens & Related Improv...	113006						
29	122017	7 Mile/Nevada Transmission Main Rehab and Carrie/Nevada Flow...	122017						
30	111008	LH WTP Architectural Programming - Laboratory and Admin...	111008						
31	132007	Imlay PS - Energy Management: Freeze Protection Pump Installation	132007						
32	114016	SPW 1958 Settled Water Conduit Concrete Replacement	114016						
33	113007	SW WTP Architectural and Building Mechanical Improvements	113007						

Risk Matrix - Water


- 115005 WWP WTP Ventilation Improvements – NEW 2019
- 111001 LH WTP Low & High Lift Filter Backwash Pumping Improvements – Future Planned 2019
- 113003 SW WTP Low & High Lift Pumping, Flocculation and Filter Improvements – Future Planned 2025+
- 112006 NE WTP Flocculator Improvements – Future Planned 2019
- 114007 SPW WTP Powdered Activated Carbon Improvements – Future Planned 2025+

Programs (Ongoing programs are not scored)

- 170400 & 170500 Transmission System Improvement & Assessment
- 170800 Reservoir Inspection, Repair & Rehabilitation
- 170500 Transmission System Valve Repair & Rehabilitation



Project Prioritization - Wastewater




Risk Matrix - Wastewater

- 232003 Northeast Pump Station – Future Planned 2025+
- 216007 DTE Primary Electric 3rd Feed – Construction Future Planned
- 211007 WRRF PS #2 Improvements – Future Planned 2021
- 212008 WRRF Intermediate Lift Pumps – Future Planned 2020
- 211006 WRRF PS #1 Improvements – Future Planned 2019
- 216006 WRRF Yard Piping – Future Planned 2020

Programs (Ongoing programs are not scored)

- 260200 Sewer Rehabilitation Program
- 260500 Sewer Outfall Rehabilitation Program
- 260600 CSO Improvement Program



High Level Water Summary



FY2020-2024 WATER Summary

FY2020 - 2024 CIP Summary - WATER

All Figures are in \$1,000's

CIP Document	FY 19	FY 20	FY 21	FY 22	FY 23	FY 24	5-Year Total (2019-2023)	5-Year Total (2020-2024)
Approved CIP FY 2019-2023	66,038	137,583	155,734	178,300	175,174	NA	712,829	NA
Draft CIP FY2020-2024 V1.0	68,746	143,247	166,599	182,595	169,006	190,866	730,193	852,313
Difference (\$)	2,708	5,664	10,865	4,295	-6,168		17,364	
Difference (%)	4.1%	4.1%	7.0%	2.4%	-3.5%		2.4%	

- 2.4% Increase in years 2019-2023 between FY19 and Proposed FY20 CIP
- Total 5-Year projected expenditures (2020-2024) is \$852,313

FY2020-2029 Draft 10-Year WATER CIP Outlook


10-Year Water CIP Outlook

Note: Figures below are in thousands of dollars

2019 Outlook	FY2019	FY2020	FY2021	FY2022	FY2023	FY 2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	Total 2019-2028
Projects	46,785	116,870	130,656	157,209	148,672	152,017	126,675	112,980	60,711	58,426	NA	1,111,001
Programs	19,253	20,713	25,078	21,091	26,502	50,733	46,309	49,539	49,033	48,675	NA	356,925
Not Yet Specified Projects								15,000	70,000	75,000	NA	160,000
Subtotal 2019 Water CIP	66,038	137,583	155,734	178,300	175,174	202,750	172,984	177,519	179,744	182,101	NA	1,627,926

Proposed 2020 Outlook	FY2019	FY2020	FY2021	FY2022	FY2023	FY2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	Total 2020-2029
Projects	53,341	117,829	142,981	158,855	144,811	164,373	140,250	133,489	73,450	68,604	72,152	1,216,795
Programs	15,405	25,418	23,618	23,740	24,195	26,493	42,875	42,875	42,875	42,875	41,681	336,643
Not Yet Specified Projects									60,000	70,000	70,000	200,000
Subtotal 2020 Water CIP	68,746	143,247	166,599	182,595	169,006	190,866	183,125	176,364	176,325	181,478	183,833	1,753,438

FY2020-2029 Draft 10-Year WATER CIP Outlook (Cont'd)



High Level Wastewater Summary



FY2020-2024 WASTEWATER Summary

FY2020 - 2024 CIP Summary - WASTEWATER

All Figures are in \$1,000's

CIP Document	FY 19	FY 20	FY 21	FY 22	FY 23	FY 24	5-Year Total (2019-2023)	5-Year Total (2020-2024)
Approved CIP FY 2019-2023	105,183	111,155	111,952	136,411	168,458	NA	633,159	NA
Draft CIP FY2020-2024 V1.0	104,931	139,480	107,430	139,677	156,884	130,159	648,402	673,630
Difference (\$)	-252	28,325	-4,522	3,266	-11,574		15,243	
Difference (%)	-0.2%	25.5%	-4.0%	2.4%	-6.9%		2.4%	

- 2.4% Increase in years 2019-2023 between FY19 and Proposed FY20 CIP
- Total 5-Year projected expenditures (2020-2024) is \$673,630

FY2020-2029 Draft 10-Year WASTEWATER CIP Outlook


10 -Year Wastewater CIP Outlook

Note: Figures below are in thousands of dollars

FY2019 Outlook	FY2019	FY2020	FY2021	FY2022	FY2023	FY2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	Total 2019-2028
Projects	80,114	86,482	81,237	105,004	131,867	89,123	43,800	29,867	15,100	15,100	NA	732,944
Programs	25,069	24,673	30,715	31,407	36,591	31,683	35,568	34,708	34,852	35,001	NA	335,649
Not Yet Specified Masterplan Projects						30,000	70,000	90,000	105,000	110,000	NA	405,000
Subtotal 2019 Wastewater CIP	105,183	111,155	111,952	136,411	168,458	150,806	149,368	154,575	154,952	160,101	NA	1,473,593

Proposed FY2020 Outlook	FY2019	FY2020	FY2021	FY2022	FY2023	FY2024	FY 2025	FY 2026	FY 2027	FY 2028	FY 2029	Total 2020-2029
Projects	82,780	102,674	68,830	106,826	115,357	85,596	62,592	73,206	49,393	21,000	16,438	701,911
Programs	22,151	36,806	38,600	32,851	41,527	44,563	34,600	33,600	38,600	38,600	43,600	383,347
Not Yet Specified Masterplan Projects							50,000	50,000	70,000	100,000	110,000	380,000
Subtotal 2020 Wastewater CIP	104,931	139,480	107,430	139,677	156,884	130,159	147,192	156,806	157,993	159,600	170,038	1,465,258

FY2020-2029 Draft 10-Year WASTEWATER CIP Outlook (Cont'd)





Highlighted Water CIP Projects

*Grant Gartrell, Tim Kuhns
& Erich Klun*



CIP Number: 122013

Project Title 14 Mile Transmission Main Loop

Project Status Future Planned

Class Lvl 1 Water

Class Lvl 2 Field Services

Class Lvl 3 Transmission System

Location Oakland County

- ☐ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 58.4



Example transmission main

Project Engineer/Manager Timothy Kuhns

Manager Grant Gartrell

Project Significance The 14 Mile Transmission Main that currently serves West Bloomfield Township, Farmington Hills, Commerce Township, Novi, Walled Lake, and Wixom is a single feed transmission system. If a disruption to service were to occur on this transmission main, many of the users along this main would experience a complete loss of pressure and flow. This project would provide a transmission main loop to the 14 Mile system to increase redundancy on this branch of the system.

Scope of Work Install approximately 6 Miles of 48-inch transmission main from 8 Mile Road to 14 Mile Road along Haggerty Road. The work will also include connections to the yard piping and reservoir fill line at the Haggerty Booster Station as well as a control valve to regulate flows along the transmission main.

Challenges Routing and construction staging for the proposed piping in the vicinity of the Haggerty and 8 Mile Intersection appears to be a significant challenge as this intersection is one of the highest traffic volume intersections in Southeast Michigan.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018		1,300	10,500	12,000	6,000				0	0	29,800
2019	0				751	1,315	1,507	13,420	37,433	0	54,426
2020	0	0		0	751	1,315	1,507	13,420	12,000	25,433	54,426

CIP Number: 122016

Project Title Downriver Transmission Main Loop

Project Status Future Planned

Class Lvl 1 Water

Class Lvl 2 Field Services

Class Lvl 3 Transmission System

Location Wayne County - Outside Detroit

☐ Innovation☐ Water MP Right Sizing☒ Reliability/Redundancy☐ NEWTP Repurposing

Project Score 58.4



Example transmission main

Project Engineer/Manager Timothy Kuhns

Manager Grant Gartrell

Project Significance The Downriver Transmission Main that currently serves Brownstown, Riverview, Woodhaven, Trenton, Flat Rock, Gibraltar, Rockwood, South Rockwood, and Berlin Township is a single feed transmission system. If a disruption to service were to occur on this transmission main, many of the users along this main would experience a complete loss of pressure and flow. This project would provide a transmission main loop to the Downriver system to increase redundancy on this branch of the system.

Scope of Work Install approximately 6 Miles of 16-inch transmission main and 3 Miles of 24-inch transmission main from along the Electric Avenue corridor to parallel the existing transmission system in this branch of the system.

Challenges Assuming ownership of the 24-inch transmission main through the City of Trenton may require condition assessment of this portion of pipeline.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2019	0				297	964	3,051	10,763	22,122	0	37,197
2020	0	0		0	297	964	3,051	10,763	22,122	0	37,197

CIP Number: 112006

Project Title Northeast Water Treatment Plant Flocculator Replacements

Project Status New

Class Lvl 1 Water

Class Lvl 2 Treatment Plants and Facilities

Class Lvl 3 Northeast

Location City of Detroit

- ☐ Innovation
- ☐ Water MP Right Sizing
- ☐ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 67.4



Project Engineer/Manager Peter Fromm
 Manager Grant Gartrell

Project Significance Most of the existing flocculators are not operable and are beyond repair, which reduces sedimentation effectiveness and creates a greater load on the filtration process.

Scope of Work Replace 1/2 of the existing flocculators, including drives, motors, shafts, and paddles with new.

Challenges Water production during construction

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2020	0	0		3	1,356	1,356	3				2,718

CIP Number: 115005

Project Title WWP WTP Building Ventilation Improvements

Project Status New

Class Lvl 1 Water

Class Lvl 2 Treatment Plants and Facilities

Class Lvl 3 Water Works Park

Location City of Detroit

☐ Innovation☐ Water MP Right Sizing☐ Reliability/Redundancy☐ NEWTP Repurposing

Project Score

76

Project Engineer/Manager Mike Dunn

Manager Terry Daniel

Project Significance Design and construction of ventilation system improvements for certain chemical storage rooms and the ozone generator and destruct rooms at the Water Works Park Water Treatment Plant to improve employee and visitor safety.

Scope of Work

Challenges

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2020	0	0		7	507	3,907	650	0	0	0	5,071

CIP Number: 111001

Project Title Lake Huron Water Treatment Plant, Low-Lift, High Lift and Filter Backwash Pumping System Improvements

Project Status Future Planned

Class Lvl 1 Water

Class Lvl 2 Treatment Plants and Facilities

Class Lvl 3 Lake Huron

Location Saint Clair County

- ☒ Innovation
- ☒ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 71.6



Lake Huron WTP

Project Engineer/Manager Eric Kramp

Manager Grant Gartrell

Project Significance 111003 RECLASSIFIED INTO THIS PROJECT. Improvements needed to align the existing low lift pumping rate with the Lake Huron WTP production rate per the 2015 WMPU. Currently constant speed pumping forces the WTP to operate in a batch mode. Existing electrical gear for low and high lift pumping units and filter backwash pumps are original to plant, beyond useful service life and need to be replaced to improve reliability, serviceability, maintainability, and efficiency. Replacement of phosphoric acid chemical storage tanks and fill piping. Flocculation moved to new project proposed CIP Project for filter rehabilitation and flocculators.

Scope of Work Currently constant speed pumping forces the Lake Huron WTP to operate in a batch mode as the low lift pump capacities exceed the high lift pump capacities. Improvements needed to align the existing low lift pumping rate with the Lake Huron WTP production rate per the 2015 WMPU. Replace with new:

1. High-voltage electrical system
2. Replace LL Pumps 3 and 4 with new pumps to meet 2015 WMPU
3. Improve HL Pump resilience & flexibility
4. Improve WW Pump capability and update as necessary
4. Phosphoric acid system upgrades

Challenges Coordination between existing pumping unit and motor required during design. Critical speed analysis may show pump improvements needed to operate at reduced speeds. Uncovering an innovative rehabilitation design to minimize maintenance of existing drives.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018		200	2,500	3,000					0	0	5,700
2019	0				401	1,611	3,169	4,450	42,757	0	52,388
2020	0	0		0	401	1,611	3,169	4,450	10,000	32,757	52,388

CIP Number: 114007

Project Title Springwells Water Treatment Plant, Powdered Activated Carbon System Improvements

Project Status Future Planned

Class Lvl 1 Water


Class Lvl 2 Treatment Plants and Facilities

Class Lvl 3 Springwells

Location Wayne County - Outside Detroit

☐ Innovation☐ Water MP Right Sizing☐ Reliability/Redundancy☐ NEWTP Repurposing

Project Score 63.8



Springwells WTP

Project Engineer/Manager TBD

Manager Grant Gartrell

Project Significance Although the existing powdered activated carbon (PAC) system is operable, it is difficult to operate and maintain when needed for taste and odor control. The PAC system needs to be replaced with a new system using a different design that provides for improved operation and maintainability. The plant is able to feed powdered activated carbon (PAC) when needed but only through extraordinary measures because the existing PAC feed systems does not operate as intended. The extraordinary measures cause additional operation and maintenance expense and inefficiencies that should be corrected in the long term. Due to the infrequent need to feed PAC, there is not an immediate need to replace the entire existing PAC system at Springwells. If raw water quality deteriorates unexpectedly and taste and odor causing compound concentrations steadily increase, then replacement of the PAC system at an earlier date would be warranted.

Scope of Work Replace the existing PAC system with a new system of a different design that provides improved operations and maintainability when PAC dosing is needed to control taste and odor in the raw water supply.

Challenges Layout of piping to correct existing problems and drainage difficult. Diffuser replacement/relocation/installation will require plant shutdowns to complete, so it will be seasonal demand dependent.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018					900	2,000			0	0	2,900
2019	0								3,939	0	3,939
2020	0	0		0	0	0	0	0	0	3,938	3,938

CIP Number: 113003

Project Title Southwest Water Treatment Plant, Low- and High-Lift Pumping Station, Flocculation and Filtration System

Project Status Future Planned

Class Lvl 1 Water

Class Lvl 2 Treatment Plants and Facilities

Class Lvl 3 Southwest

Location Wayne County - Outside Detroit

- ☐ Innovation
- ☒ Water MP Right Sizing
- ☐ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 67.6



Example of a butterfly valve

Project Engineer/Manager Shakil Ahmed

Manager Grant Gartrell

Project Significance Replacing improperly functioning as well as cracked valves and gates, causing operational and maintenance concerns. Low and High Lift Pumping Improvements: Existing pumping station equipment including pumps, motors, switchgear, controls, gates, valves, etc. are all original to the plant and are over-sized for the current and projected system water demands for at least the next 20 years. The station's electrical system and controls are difficult and costly to maintain and have reduced reliability due to age and lack of available parts on the market. Large size and age of pumps and motors are inefficient. Flocculation & Filtration System Improvements: Existing filter media, auxiliary scour, backwash, and related appurtenances are all original to the plant construction (circa 1962) and need to be replaced for reliability and efficiency improvements. Flocculator equipment upgrades were identified in the 2015 WMPU project.

Scope of Work The work includes study, design, and construction services for the replacement of 2 - 72" diameter butterfly valves, 4 motorized sluice gates, 7 potable sluice gates, and 1 - 36" flag valve. Replacement of high and low lift pumps, motors, motor controls, medium-voltage switchgear, and MCCs. Replace and improve filtration system equipment and components as well as flocculator equipment upgrades.

Challenges**Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)**

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018								2,940	0	0	2,940
2019	0								148,286	0	148,286
2020	0	0		0	0	0	0	0	0	148,286	148,286



Highlighted Wastewater CIP Projects

*Dan Alford, Ali Khraizat,
Todd King, Biren Saparia
& Chris Nastally*



CIP Number: 216006

Project Title Assessment and Rehabilitation of WRRF yard piping and underground utilities

Project Status Future Planned

Class Lvl 1 Wastewater

Class Lvl 2 WRRF

Class Lvl 3 General Purpose

Location City of Detroit

- ☒ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 76.4



GLWA WRRF

Project Engineer/Manager Ali Khraizat

Manager Ali Khraizat

Project Significance Yard piping and underground utilities are vital to the operations of the WRRF. The integrity of these systems will be maintained with this project. The Secondary Water system needs to be relocated or completely refurbished to provide uninterrupted water for fire protection and process applications such as seal water to the pumps. Some of the yard piping is original to the plant and requires a condition assessment.

Scope of Work This project will include the study, design, and construction for the needed improvements to yard piping and underground utilities. This includes right sizing, as-built confirmation and condition assessment of our yard piping and underground utilities. It is possible that the secondary water system may need to be relocated. The distribution models for the water systems will also be updated. A redundant potable water feed to the WRRF will also be evaluated.

Challenges Maintaining the adequate supply of our water systems required for treatment processes during assessment and rehabilitation of underground utilities will be the most significant challenge on this project. Temporary power, air, water, natural gas system shutdowns may also be required to perform the work.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018			1,700	2,000	12,000	15,600	16,279	4,141	0	0	51,720
2019	0				1,718	4,008	7,174	17,530	24,026	0	54,456
2020	0	0		0	323	5,258	3,849	4,500	3,500	7,423	24,853

CIP Number: 211006
Project Title WRRF PS No. 1 Improvements

Project Status Future Planned

Class Lvl 1 Wastewater

Class Lvl 2 WRRF

Class Lvl 3 Primary Treatment

Location City of Detroit

- ☒ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 75



Pump Station 1 Interior

Project Engineer/Manager Alfredo Lava

Manager Ali Khraizat

Project Significance Condition assessment and rehabilitation of all pumps at Pump Station No. 1 to increase efficiency and reliability.

Scope of Work The study/design work will identify all major parts including impellers and wear rings to be refurbished for each pump and all related appurtenances. The construction services will provide rehabilitation and/or replacement as determined in the study and design along with the sequencing of pump shutdown throughout the rehabilitation period.
Investigation and evaluation of all the inlet gates, outlet gates and associated actuators, Motor Control Centers (MCCs) and other related equipment, HVAC system, Control System and provide recommendation and design for rehabilitation or replacement are also part of the scope.

Challenges Maintaining the adequate pumping capacity during construction.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018			600	5,350	5,125	2,054			0	0	13,129
2019	0			500	1,800	2,462	9,394	9,245	719	0	24,120
2020	0	0		498	1,803	2,325	8,424	8,370	811	84	22,315

CIP Number: 260600
 Project Title CSO FACILITIES IMPROVEMENT PROGRAM

Project Status Active

Class Lvl 1 Wastewater

Class Lvl 2 Programs

Class Lvl 3 Programs

Location Multiple Counties

- ☐ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 90.6



Retrofitted chemical feed pump replacement at Puritan-Fenkell RTB and makeshift wooden stairs to enter Basin Valve Gallery

Project Engineer/Manager Chris Nastally

Manager Chris Nastally

Project Significance This program is being established to facilitate the study, design, construction administration, and construction of improvements necessary to maintain the facilities which contribute to the CSO Control Program and compliance herewith.

Scope of Work This program is intended to include studies, design, construction administration, and construction projects which serve to improve process areas or functions of the CSO Facilities. The overall scope of this program is to complete the following: Needs Assessment, Condition Assessment, and update to the 2013 Scheduled Replacement Plan (SRP); Replacement of CSO Facilities Fire Alarm Systems; Structural Condition Assessment Design/Build project; and flushing improvements to Baby Creek CSO Facility. A direct product of the Needs/Condition Assessment and SRP is identification of facility needs with projects identified, prioritized, and conceptual cost estimates. From this output, RFP's will be developed to address these needs. For this purpose, Design and Construction dollars have been identified in the later years of this Program to facilitate design and construction of those identified needs. It is anticipated that the primary drivers of these improvements will be obsolescence/end of service life, excessive O&M problems, reliability, efficiency and system standardization which arise from feedback from operation & maintenance, the scheduled replacement plan, and the needs/condition assessment. Following completion of the Wastewater Master Plan, new projects may be otherwise defined which will be incorporated into the CIP. These projects will likely be entered into the CIP as stand-alone projects rather than falling under this program. Furthermore, upon completion of the NPDES permit, new regulatory requirements may arise which require capital improvements. Depending on the nature of those improvements, they may be stand-alone projects or fall within the elements of this Program.

Challenges As this program starts off, there is a lot of design RFPs in the beginning which will lead to a refined projects aimed at improving operations, which lead to RFPs for design and large scale construction projects in the later years (3-5). A significant challenge to be faced will be maintaining the CSO facilities

CIP Number: 260600

Project Title CSO FACILITIES IMPROVEMENT PROGRAM

in current operations without the benefit of large-scale improvements of the CSO Systems. Another significant challenge of this program will be unforeseen conditions that may be encountered as facility inspections & condition assessments begin. For example, finding significant structural distress of a basin could lead to increase of budget or extension of timeline of improvements. Considering much of the equipment/systems identified for inclusion in this program are at or near obsolescence or are actively causing O&M issues, delays in improvements could possibly cause operational or compliance issues.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018		3,428	2,247	6,400	9,000	7,200	3,610		0	0	31,885
2019	0	764	1,658	9,277	6,218	2,351	4,351	9,351	11,251	0	45,221
2020	0	0	481	8,442	5,604	4,553	5,825	10,325	13,361	15,000	63,591

CIP Number: 232002

Project Title Freud & Conner Creek Pump Station Improvements

Project Status Active

Class Lvl 1 Wastewater

Class Lvl 2 SCC

Class Lvl 3 Pumping Stations

Location City of Detroit

- ☐ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 79.6



Freud Pump Station

Project Engineer/Manager Mini Panicker

Manager Biren Saparia

Project Significance The primary objective of this project is to study the overall performance of Connor Creek and Freud sewage pumping stations and develop design, and build an operational strategy to optimize the utilization of interconnected piping and operation between both pumping stations and the Connor Creek Retention and Treatment Basin.

Scope of Work Provide basis of design, and final design for an operational strategy to optimize the utilization of interconnected piping and operation between Connor Creek and Freud pumping stations and the Connor Creek Retention and Treatment Basin. Provide construction of the emerging project and construction assistance during construction of the emerging project.

Challenges Meeting the collection system transport capacity during the construction

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018		8,040	5,900	5,100	2,460	1,000			0	0	22,500
2019	0	2,101	1,384	1,192		223	1,582	11,000	15,000	0	32,482
2020	0	0	5,111	1,984	17,029	13,014	50,014	50,014	25,007	257	162,430

CIP Number: 260500

Project Title CSO Outfall Rehabilitation

Project Status Active

Class Lvl 1 Wastewater

Class Lvl 2 Programs

Class Lvl 3 Programs

Location Multiple Counties

☐ Innovation☐ Water MP Right Sizing☒ Reliability/Redundancy☐ NEWTP Repurposing

Project Score 72.8



Sewer tap piping in B009 outfall (left) and
sludge buildup and poor masonry in B007
outfall (right)

Project Engineer/Manager Mini Panicker

Manager Biren Saparia

Project Significance PROJECTS 222006 AND 233001 HAVE BEEN INCORPORATED INTO THIS PROJECT. Rehabilitation of the CSO outfalls is essential to properly discharge the uncontrollable combined sewer overflows to the receiving waters and to prevent sewer back up into the Conveyance System. Recent inspections of the outfalls revealed structural deficiencies like fractures, missing mortar from bricks etc. There are sediment and debris deposits in many of them.

Scope of Work Preliminary Scope of Work of the project is construction. Contract CS-168 will review the existing records, evaluate the existing conditions, and provide the necessary design to rehabilitate the outfalls.

Challenges Some outfalls are below the river elevation; rehabilitation may be challenging.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018			6,000	6,000	6,000	6,000	6,000	6,000	0	0	36,000
2019	0			507	3,826	10,001	10,001	10,001	10,001	0	44,337
2020	0	0	9	4,000	15,102	17,947	10,926	15,102	15,102	11,000	89,188

CIP Number: 260200

Project Title Sewer and Interceptor Rehabilitation Program

Project Status Active

Class Lvl 1 Wastewater

Class Lvl 2 Programs

Class Lvl 3 Programs

Location Multiple Counties

- ☐ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 0



An example interceptor

Project Engineer/Manager Mini Panicker

Manager Biren Saparia

Project Significance Rehabilitation and replacement program of the existing sewers and interceptors based upon structural deficiencies identified from the evaluation results. This replacement, rehabilitation and cleaning program is essential to optimize the transportation capacity of the GLWA collection system and to increase its life expectancy.

Scope of Work Provide CCTV and/or sonar inspection of the GLWA Collection System Interceptors and Trunk Sewers to reveal the existing conditions as per the National Association of Sewer Service Companies' (NASSCO) Pipeline Assessment Certification Program (PACP) standards, evaluate the existing conditions, and provide the necessary cleaning/rehabilitation/replace to optimize the design capacity of the collection system and to minimize the inflow and infiltration into the collection system.

Challenges Large sewers and interceptors may have flow control challenges for both inspection and rehabilitation.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018		2,612	8,000	8,000	20,000	20,000	20,000		0	0	78,612
2019	0	3,397	7,751	10,601	10,400	11,400	11,400	11,400	11,400	0	77,749
2020	0	0	13,555	8,609	15,000	15,000	15,000	15,000	15,000	95,000	192,164

CIP Number: 216007

Project Title DTE Primary Electric 3rd Feed Supply to WRRF

Project Status Future Planned

Class Lvl 1 Wastewater

Class Lvl 2 WRRF

Class Lvl 3 General Purpose

Location City of Detroit

- ☐ Innovation
☐ Water MP Right Sizing
☒ Reliability/Redundancy
☐ NEWTP Repurposing

Project Score 82.8



The new 3rd 120/13.8 kV Transformer installed and owned by the Great Lakes Water Authority waiting for the 3rd Primary Electric Feed Line to be installed and energized

Project Engineer/Manager Phillip Kora

Manager Philip Kora

Project Significance GLWA's WWTP will have a redundant primary electrical service to power the WRRF equipment.

Scope of Work The scope of this design-build project includes design and construction of 3rd 120 kV primary electric supply transmission line owned by DTE tapping into the 120-kV Waterman-Zug line in the vicinity of Dearborn St. and Copland St right-of-way at Tower 1368. The design-build services also include securing the property right-of-way easements from the property owners, as well as the design and construction of power transmission supply line. This primary transmission power line will energize the already installed new 120-13.8 industrial substation owned by GLWA near EB-1.

Challenges Negotiation with private property owners and testing of the automatic switch over will require co-ordination with operations.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018			3,500	3,500					0	0	7,000
2019	0	15		2,002	1,326	3,326				0	6,669
2020	0	0	583	2,108	1,381	3,374	0	0	0	0	7,446

CIP Number: 211007

Project Title WRRF PS #2 Bar Racks Replacements and Grit Collection System Improvements

Project Status Future Planned

Class Lvl 1 Wastewater

Class Lvl 2 WRRF

Class Lvl 3 Primary Treatment

Location City of Detroit

- ☒ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 65.2



WRRF Pumping Station 2: Bar Racks and Grit Collection System

Project Engineer/Manager Beena Chackunkal

Manager Ali Khraizat

Project Significance Replacement of all bar racks and associated equipment for more reliable and efficient operations. Improvements to the grit collection system will prevent the grit affecting the downstream equipment. These improvements will enable WRRF to be in compliance with NPDES permit.

Scope of Work The work consists of evaluation, design and construction for the replacement of Bar Racks and Grit Collection System including their associated motors and electrical panels as necessary to meet the long-term wet weather capacity requirements at the PS-2.

Challenges Maintaining the MDEQ-NPDES required capacity during the construction phase of the project.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2018			650	2,900	3,300	2,817			0	0	9,667
2019	0			7	402	1,980	2,404	6,956	8,814	0	20,563
2020	0	0		6	269	1,329	2,039	6,306	7,838	49	17,836

CIP Number: 212008

Project Title WRRF Rehabilitation of Intermediate Lift Pumps (ILPs)

Project Status Future Planned

Class Lvl 1 Wastewater

Class Lvl 2 WRRF

Class Lvl 3 Secondary Treatment & Disinfection

Location City of Detroit

- ☒ Innovation
- ☐ Water MP Right Sizing
- ☒ Reliability/Redundancy
- ☐ NEWTP Repurposing

Project Score 72.8



Intermediate Lift Pump Station N.2

Project Engineer/Manager Beena Chackunkal

Manager Ali Khraizat

Project Significance The ILPs are old and reached the end of life cycle. The ILPs convey primary effluent to the secondary bioreactors. Therefore a replacement or rehabilitation will help to comply with the permit capacity requirement for the Secondary Process Area.

Scope of Work Feasibility study, design and construction of the existing process flow to maximize conveyance redundancy/distribution, pump sizing to accommodate dry and wet weather operations for the five intermediate lift pumps that lift primary effluent to the aeration basins for secondary treatment.

Challenges Maintaining the required wet weather secondary capacity of 930 MGD while operating efficiently during dry weather flows.

Project Expenses Compared to Previous CIP Versions (All figures are in \$1,000's)

CIP	FY16	FY17	FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	Total
2019	0				230	1,141	6,569	5,767	6,809	0	20,516
2020	0	0			229	500	656	6,727	5,910	6,811	20,833

CIP Schedule & Closing Remarks



Anticipated CIP Roll-Out Schedule - TENTATIVE

FY2020 - 2024 CIP SCHEDULE (Revised 10/24/18)

Completed	Date	Meeting Type	Notes
✓	8/20/2018	NA	Distribute & Train Business Case Evaluation Database
✓	9/26/2018	NA	BCE's Due
✓	10/1/2018	Water Review Committee Meeting	Review existing project priorities, identify new project priorities and potentially adjust schedules for projects in order to align with overall CIP projected expenditures previously approved
✓	10/3/2018	Wastewater Review Committee Meeting	
✓	10/18/2018	Executive Leadership Team review of BCEs and Modifications to CIP	Review of New BCEs & CIP Modifications
✓	10/25/2018	Charges Roll-Out Mtg #1 - CIP @ AM/CIP Work Group	1st Member Partner Review of CIP - Version 1.0
✓	10/29/2018	GLWA CIP Committee	1st CIP Committee Review of CIP - Version 1.0
	11/19/2018	NA	Member Partner & Board Comments Due
	11/30/2018	GLWA CIP Committee	
	12/18/2018	AM/CIP Committee Work Group Meeting	2nd Member Partner Review of CIP - Version 2.0
	12/18/2018	GLWA CIP Committee	2nd CIP Committee Review of CIP - Version 2.0

Questions





GLWA

Great Lakes Water Authority

Have a Great Day!