Executive Summary | Pump Station 2 Rack & Grit Improvements

- WRRF PS 2 Rack and Grit was constructed in 1990 and last updated 2015 and its capacity is 900 MGD.
- It removes a combined ~15 tons of screenings and grit from the influent to the WRRF each day.
- The existing screen and grit processes operates at 15% and 32% efficiency, respectively. This means that ~64 tons of inorganic material goes to the downstream process areas each day.
- The proposed improvements will remove ~35 tons of screenings and grit per day, more than doubling the current removal of solids.



Capital Improvement Project (CIP) 211007 Timeline

WRRF Pump Station 2 Bar Rack Replacement and Grit System Improvements Project type: Design - Bid – Build

The Master Planning evaluation confirms that **Board presentation** it is imperative that these projects move **Capital Projects Committee** forward in a timely fashion to maintain EGLE -(CPC) / Capital Improvement NPDES required capacity by improving the Plan (CIP) Outreach reliability of the existing system.¹ Nov 2022 June EGLE: Michigan dept. of Environment, Great Lakes, & Energy 2022 **Today** NPDES: National Polutant Discharge Elimination System Master BCE Construction Study Design RFB RFP Plan /CIP Request for Request proposal for bid BCE: Business Case Evaluation Timeline not to scale **CIP: Capital Improvement Plan** Feb June Sept 2022 2022 2023

1. GLWA 2020 Master Plan, 7.4.5.1: PS2 and Preliminary Treatment Improvements



Rack and Grit is sewage preprocessing to PROTECT the WRRF



Screenings of floating debris = Clogs for pipes Grit = Sandpaper for pumps and valves, blocks for aeration




Project Purpose

System reliability

Fewer process upsets & less equipment damage


Improved screening and grit removal

Existing Facilities | At discharge side of Pump Station 2





Existing Facilities | At discharge side of Pump Station 2






Current State | The equipment is approaching end of life


Equipment to upgrade

- Eight ³/₄" gap bar screens
- Screening conveyor
- Aerated grit channels
- Clamshell Bucket
- Building and auxiliary systems





The alternatives evaluation balanced cost vs. design priorities



GLWA Great Lakes Water Authority

Alternatives evaluation compared combos of screen & grit systems

A1.	A2.	A3.	В.	С.	D.
Tank rehab	Tank rehab	Tank rehab			Dry
+ screw	+	+ chain &	Stacked	Stirred	weather
conveyors	grit pump	flight	tray	vortex	system

A. Narrow bars

in existing racks


A1. Narrow bars

+ 2 new racks

- B. Coarse and fine screens in existing building
- C. Coarse and fine screens in two locations
- **D. A** + fine screens@ grit tank inlet
- E. A + fine screens@ grit tank inlet



Alternatives evaluation compared combos of screen & grit systems





Alternatives evaluated | Feasibility check eliminated two systems

	A1. Tank rehab + screw conveyors	A2. Tank rehab + grit pump	A3. Tank rehab + chain & flight	B. Stacked tray	C. Stirred vortex	D. Dry weather system
A. Narrow bars in existing racks						
A1. Narrow bars + 2 new racks						
B. Coarse and fine screens in existing building		Blocked em	Elimin ergency egress		ance access	
C. Coarse and fine screens in two locations	Eliminated Not feasible with hydraulic limitations					
D. A + fine screens@ grit tank inlet						

E. A + fine screens@ grit tank inlet



Alternatives evaluated | Two more options eliminated in early scoring

	A1. Tank rehab + screw conveyors	A2. Tank rehab + grit pump	A3. Tank rehab + chain & flight	B. Stacked tray	C. Stirred vortex	D. Dry weather system
A. Narrow bars in existing racks						
A1. Narrow bars + 2 new racks						
B. Coarse and fine screens in existing building			Eliminated			Eliminated
C. Coarse and fine screens in two locations			Operations & maintenance concerns			High cost
D. A + fine screens@ grit tank inlet						
E. A + fine screens@ grit tank inlet						



Alternatives evaluated | Two more options eliminated in early scoring

	A1. Tank rehab + screw conveyors	A2. Tank rehab + grit pump	A3. Tank rehab + chain & flight	B. Stacked tray	C. Stirred vortex	D. Dry weather system
A. Narrow bars in existing racks						
A1. Narrow bars + 2 new racks					Selected	
B. Coarse and fine screens in existing building			Eliminated			Eliminated
C. Coarse and fine screens in two locations			Operations & maintenance concerns			High cost
D. A + fine screens@ grit tank inlet						
E. A + fine screens@ grit tank inlet						



Viable system alternatives were scored on cost and priority criteria

Design Combinations (comparison)					
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex	
A. Narrow bars in existing racks					
A1. Narrow bars + 2 new racks				Selected	
D. A + fine screens @ grit tank inlet					
E. A + fine screens @ grit tank inlet					



Scoring | Screening capture ratio

		Combinat eenings ren		 75% & above 50%-74% 25%-49% Below 25%
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex
A. Narrow bars in existing racks		15	%	
A1. Narrow bars + 2 new racks		Selected		
D. A + fine screens @ grit tank inlet		00	0/	
E. A + fine screens @ grit tank inlet		80	70	



Scoring | Grit removal efficiency

		Combina t grit remov		 75% & above 50% - 74% 25% - 49% Below 25%
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex
A. Narrow bars in existing racks	25	0/		
A1. Narrow bars + 2 new racks	23	25%		Selected
D. A + fine screens @ grit tank inlet	13%			
E. A + fine screens @ grit tank inlet	13	70		



Scoring | Total solids removal

 75 & above 50-74 25-49 Below 25 						
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex		
A. Narrow bars in existing racks	19		3	37		
A1. Narrow bars + 2 new racks	31		49			
D. A + fine screens @ grit tank inlet	50					
E. A + fine screens @ grit tank inlet	.	52		75		



Scoring | Qualitative factors

Performance

Regulatory

History of performance in similar wastewater treatment facilities

GLWA experience

Resistance to damage / failure

Flexibility to meet NPDES requirements during construction

Adaptability to future flows

Operations and Maintenance

Maintainability

Ease of operation

Constructability and Maintenance of Ongoing Plant Operations (MOPO)

Health and Safety (H&S)

Plant traffic impact

Changes to existing H&S exposure

Public Benefit

Nuisance potential: odor / traffic / noise

Efficiency and Innovation

Energy savings

Reduces future costs

Sustainability

Facility footprint



Scoring | Qualitative factors

		Combinat 0 possible		 55 and above 50-54 45-49 Below 45
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex
A. Narrow bars in existing racks	5	3	43	49
A1. Narrow bars + 2 new racks	5	7	52	61
D. A + fine screens @ grit tank inlet	44	4	40	51
E. A + fine screens @ grit tank inlet		47		56



Scoring | Est. Construction cost

	t = 100)	 Below 60 60-69 70-79 80 and above 		
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex
A. Narrow bars in existing racks	52	65	74	57
A1. Narrow bars + 2 new racks	61	74	83	66
D. A + fine screens @ grit tank inlet	70	00	100	05
E. A + fine screens @ grit tank inlet	78	90	100	85




Scoring | Est. Lifecycle cost

	t = 100)	 Below 60 60-69 70-79 80 and above 		
Grit Screening	A1. Tank rehab + conveyors	A2. Tank rehab + grit pump	B. Stacked tray	C. Stirred vortex
A. Narrow bars in existing racks	54	67	75	58
A1. Narrow bars + 2 new racks	62	76	83	67
D. A + fine screens @ grit tank inlet	70	0.2	100	86
E. A + fine screens @ grit tank inlet	79	92	100	85




Performance Improvement | Better screening and grit removal





Proposed PS2 screening and grit removal facilities



New





Screening Upgrades I/II | Replace bar screens with finer screens

Existing Bar Screens

Proposed





 $\frac{3}{4}$ " Bar screens (8 total)

¹/₄" Bar screens (10 total)




Screening Upgrades II/II | Replace conveyor with sluice trough

Existing conveyor to dumpster



Proposed



Belt rolling to dumpster

Trough flowing to washers & compactors




Grit Upgrades I/II | Install stirred vortex grit collectors

Existing Grit Chambers



Aerated channels with weirs (8 total)

Proposed



Stirred vortex grit collectors (8 total)



Grit Upgrades II/II | Replace bucket with grit classifiers

Existing Grit Removal



Proposed



Clamshell bucket

Cyclone classifiers (6 total)



Construction Summary Timeline and Costs

Construction duration	58 months (April 2030 assuming Oct. 2024 NTP)
Designer	Hazen and Sawyer
Builder	Commercial Construction Company
Design cost	\$11.8M
Amendment	\$5.4M (construction phase support)
Construction cost	\$225M
Total	\$242M



Summary | Pump Station 2 Rack & Grit is a strategic capital project

Goals

- Remove a higher percentage of solids
- Replace equipment
 nearing end-of-life
- Simplify operations and reduce maintenance costs

Other benefits

- Reduce wear on primary sludge pumps and other processing equipment
- Improve quality of biosolids products
- Inform upcoming Pump Station 1 Screening and Grit project

Recommendation

- Replace the 8 existing bar screens with 10 finer bar screens for debris removal
- Install stirred vortex units and cyclone classifiers for grit removal
- Building, mechanical, electrical, and other misc. improvements

